


# PRELIMINARY STORMWATER

---

## TECHNICAL INFORMATION REPORT JUNE 29, 2023



## 438 Homestead Washington Street

City of Woodland, Washington

---

**Submitted by**  
Windsor Engineers  
Civil, Mechanical & Electrical Engineers  
27300 NE 10<sup>th</sup> Avenue  
Ridgefield, WA 98642  
360.610.4931

**Prepared for**  
City of Woodland  
230 Davidson Avenue  
Woodland, WA 98674



## Table of Contents

<b>1.0 CERTIFICATION PAGE</b> .....	<b>1</b>
<b>2.0 REFERENCES</b> .....	<b>2</b>
<b>3.0 PROJECT TEAM</b> .....	<b>3</b>
<b>4.0 GENERAL</b> .....	<b>4</b>
4.1 Purpose and Scope .....	4
4.2 Project Location .....	4
4.3 Project Description .....	4
4.4 Applicable Codes and Standards .....	5
4.5 Determination of Applicable Minimum Requirements .....	6
<b>5.0 MINIMUM REQUIREMENTS</b> .....	<b>8</b>
5.1 Minimum Requirement #1: Preparation of Stormwater Site Plans .....	9
5.2 Minimum Requirement #2: Construction Stormwater Pollution Prevention .....	9
5.3 Minimum Requirement #3: Source Control of Pollution .....	9
5.4 Minimum Requirement #4: Preservation of Natural Drainage Systems and Outfalls .....	9
5.5 Minimum Requirement #5: On-site Stormwater Management .....	9
5.6 Minimum Requirement #6: Runoff Treatment .....	10
5.6.1 Modeling .....	10
5.7 Minimum Requirement #7: Flow Control .....	11
5.8 Minimum Requirement #8: Wetlands Protection .....	11
5.9 Minimum Requirement #9: Operation and Maintenance .....	11
<b>6.0 CONVEYANCE SYSTEMS ANALYSIS AND DESIGN</b> .....	<b>12</b>
<b>7.0 ADDITIONAL REQUIREMENTS</b> .....	<b>13</b>
7.1 Offsite Analysis .....	13
7.2 Closed Depression Analysis .....	13
7.3 Other Permits .....	13
7.4 Approval Conditions Summary .....	13
7.5 Special Reports and Studies .....	13
<b>8.0 APPENDICES</b> .....	<b>14</b>
Appendix A – Stormwater Calculation Assumptions and Stormwater Concept .....	14
Appendix B – Geotechnical Information .....	14
Appendix C – MGS Flood Modeling Results .....	14
Appendix D – BMP Details .....	14

### Tables

Table 1: Modeling Land Cover and Impervious Assumptions .....	7
Table 2: Model Inputs .....	11



**Figures**

Figure 1: Project Location via Lewis County GIS Base Map ..... 5  
Figure 2: MGSFlood Results Showing for LID and Flow Control Requirements ..... 10



## 1.0 CERTIFICATION PAGE

---

### CERTIFICATE OF THE ENGINEER

**Title:** Preliminary Stormwater Technical Information Report


**Project:** 438 Homestead Washington Street

This Technical Information Report (TIR) has been prepared under my supervision and meets the standard of care for similar documents within this community. The TIR includes the required information per the below references and complies with the code. The proposed stormwater design is feasible.

**References:**

2019 Stormwater Management Manual for Western Washington (The 2019 SWMMWW) – Department of Ecology, State of Washington

Windsor Engineers LLC



Reviewed By: Emily Stephens, PE

Designed By: Dan Koistinen, EIT



## 2.0 REFERENCES

---

*Clean Water Act. (n.d.). Retrieved from <https://www.epa.gov/laws-regulations/summary-clean-water-act>*

*Department of Ecology. (n.d.). Western Washington Stormwater Manual (WWSWM). Retrieved from <https://www.clark.wa.gov/public-works/stormwater-code-and-manual>*

*DOE Water Quality Permits. (n.d.). Retrieved from <https://ecology.wa.gov/Water-Shorelines/Water-quality/Water-quality-permits>*

*National Pollutant Discharge Elimination System (NPDES). (n.d.). Retrieved from <https://www.epa.gov/npdes>*

*Washington Department of Ecology. (n.d.). Construction Stormwater General Permit. Retrieved from <https://ecology.wa.gov/Regulations-Permits/Permits-certifications/Stormwater-general-permits/Construction-stormwater-permit>*

*Washington State Department of Ecology. (n.d.). DOE Stormwater Manuals. Retrieved from <https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Stormwater-permittee-guidance-resources/Stormwater-manuals>*



### 3.0 PROJECT TEAM

---

**Jurisdiction** City of Woodland  
230 Davidson Avenue  
Woodland, WA 98674



**Developer** Homestead, LLC  
PO Box 255  
Yacolt, WA 98675  
roger.foley505@gmail.com  
360.667.8477

**Civil Engineer** Windsor Engineers LLC  
27300 NE 10<sup>th</sup> Avenue  
Ridgefield, WA 98642  
360.610.4931



**WINDSOR  
ENGINEERS**

Reviewed By:  
Emily Stephens, PE, Civil Engineer  
[estephens@windsorengineers.com](mailto:estephens@windsorengineers.com)

Designed By:  
Dan Koistinen, EIT  
[dkoistinen@windsorengineers.com](mailto:dkoistinen@windsorengineers.com)

---



## 4.0 GENERAL

---

### 4.1 Purpose and Scope

The purpose of this report is to demonstrate preliminary feasibility of stormwater management associated with the construction of 438 Homestead Washington Street. This report will evaluate and describe the proposed stormwater conveyance, water quality, and water quantity design.

### 4.2 Project Location

Address	438 Washington Street, Woodland WA 98674
Parcels	50339
Area	0.93 acre
Section-Township-Range	24-5N-1W
Jurisdiction	City of Woodland

### 4.3 Project Description

The project site is located on a 0.93-acre parcel (50339) at 438 Washington Street, Woodland WA 98674 in the City of Woodland (Figure 1). The developer plans to construct 6 single-family homes. There is currently an existing single-family residence and driveway on the parcel accounting for approximately 2,600 square feet (SF) of existing impervious area.

The site topography is generally flat with slopes of 0-3 percent (%). A geotechnical analysis is currently in progress for the site; and will be included with the final TIR. A geotechnical report by Jolma Design, LLC for an adjacent site has been included in Appendix B. For the preliminary modeling, 3.27 in/hr for a design infiltration rate was used from this geotechnical report. According to the USDA Web Soil survey, soil types near the site primarily consist of Newberg fine sandy loam, 0 to 3 % slopes. Soil data from Web Soil Survey is included in **Appendix B**. There does not appear to be any wetlands or hydric soils on this site.

Site grading will be done in a manner that will drain runoff away from the homes. Runoff from driveways will be treated with compost-amended vegetated filter strips and conveyed to infiltration trenches on each lot to provide flow control. Runoff from the roofs will also drain to these infiltration trenches to provide flow control.




**Figure 1: Project Location via Lewis County GIS Base Map**

#### **4.4 Applicable Codes and Standards**

To protect our country’s waters, legislature was enacted starting very broadly as the Clean Water Act of 1972, administered by the Environmental Protection Agency (EPA) as the National Pollutant Discharge Elimination System (NPDES) and subsequently delegated to the local (state) authority as a Washington Department of Ecology (DOE) Water Quality Permit, and finally managed as the Construction Stormwater General Permit (CSGP). Washington State implements the CSGP through the Washington DOE Stormwater Manual and municipalities/counties may adopt portions of this manual or an equivalent.





The calculations and stormwater management edition methods in the report are based on the following references:

2019 Stormwater Management Manual for Western Washington (SWMMWW)

#### 4.5 Determination of Applicable Minimum Requirements

The 0.93-acre (ac) project will construct 6 single family homes, driveways, half width road improvements to Washington Street, utilities, and stormwater facilities. It is assumed that 0.93 acres will be disturbed.

- Total Site Area: 0.93 acres
- Disturbed Area: 0.93 acres
- Existing Impervious: 0.06 acres
- Proposed Impervious: 0.48 acres

The project proposes more than 5,000 square feet of new impervious surfaces. All minimum requirements (MRs) #1-9 will apply to the project sites new and replaced hard surfaces.



Assumptions included in the calculations and MGS Flood modeling described in this report include the values listed in Table 1:

**Table 1: Modeling Land Cover and Impervious Assumptions**

MGS Flood Areas	Lot Area		Paved/Concrete Area		Roof Area		Green Space	
Lot Number	SF	ac	SF	ac	SF	ac	SF	ac
Lot 1	6,057	0.14	501	0.01	1,900	0.04	3,656	0.08
Lot 2	6,021	0.14	501	0.01	1,900	0.04	3,620	0.08
Lot 3	6,021	0.14	501	0.01	1,900	0.04	3,620	0.08
Lot 4	6,841	0.16	2,037	0.04	1,900	0.04	2,904	0.07
Lot 5	6,741	0.15	2,037	0.04	1,900	0.04	2,804	0.06
Lot 6	6,746	0.15	2,039	0.04	1,900	0.04	2,807	0.06
Right of Way	2,066	0.05	1,678	0.04	0	0.00	388	0.01
<b>Total</b>	<b>40,493</b>	<b>0.93</b>	<b>9,294</b>	<b>0.20</b>	<b>11,400</b>	<b>0.26</b>	<b>19,799</b>	<b>0.45</b>



## 5.0 MINIMUM REQUIREMENTS

---

This site triggers minimum requirements (MRs) #1-9 because it will add more than 5,000 SF of impervious surface. The following best management practices (BMP) are proposed to be incorporated into the site and will be discussed with each applicable MR in the sections below:

- Roofs and Driveways - Infiltration Trenches (BMP T7.20)
  - The infiltration trenches will receive runoff treated from CAVFS and from roof areas to provide flow control.
  - The proposed BMP T7.20 Infiltration Trenches will meet the standard set by the 2019 SWMMWW. The proposed trenches per lot are 40 feet (ft) long x 3.5 ft wide x 3 ft deep.
- Driveways - Composted-Amended Vegetated Filter Strips (CAVFS) (BMP T7.40)
  - The CAVFS System will follow the contour of the driveway and parking area for an approximate length of each driveway. The CAVFS system will be built to the DOE Standard for BMP T7.40 CAVFS and will have a total amended soil depth of 12 inches. The CAVFS System serving the sidewalk area is 2.5 ft wide.
  - The modeling for the driveway surface areas are modeled as impervious area flowing into a CAVFS element/facility. Each impervious area will meet the treatment standards of the 2019 SWMMWW. The driveway runoff flows through a 1' flow spreader, CAVFS and then through area drains to a center infiltration gallery for each lot.
  - The CAVFS dimensions are 1.5 ft width x 1 ft depth x 25 ft length for lots 1, 2, & 3.
  - The CAVFS dimensions are 1.1 ft width x 1 ft depth x 116 ft length for lots 4, 5, & 6.
- Lawn and Landscape Areas - Post-Construction Soil Quality and Depth (BMP T5.13)
  - The area converted to lawn and landscape is under  $\frac{3}{4}$  of an acre. The green space will be constructed to meet the Department of Ecology's BMP T5.13 standard detail and will fully disperse or soils meeting BMP T5.13.
  - The dispersion element/facility (BMP T5.13 dispersion area) is represented in the MGS Flood model by a long, shallow pond with a maximum depth of 0.15 feet. The length represents the flow path dispersion area, that is constructed to BMP T5.13 standards. The width of the pond was determined by measuring the width of the lawn. The runoff from the lawn area flows through the soils meeting BMP 5.13. For the preliminary modeling we used the dimensions 54 ft x 15 ft for lots 1, 2, & 3, and 70 ft x 15 ft for lots 4, 5, & 6.

Typical details for the BMP's listed above can be found in **Appendix D**.



### 5.1 Minimum Requirement #1: Preparation of Stormwater Site Plans

A site stormwater plan is included in the preliminary engineering plans. A preliminary stormwater concept has been included in **Appendix A** along with the preliminary stormwater calculations and assumptions to accompany the preliminary plat application.

### 5.2 Minimum Requirement #2: Construction Stormwater Pollution Prevention

The project results in more than 2,000 SF of new impervious and less than one acre of disturbed area; therefore, a Construction Stormwater Pollution Prevention Plan (SWPPP) is required but the NPDES Permit is not required. The SWPPP is included in the Engineering Plans as the Erosion Control Plan C110.

Should clearing, grading and other soil disturbing activities occur between October 1 through April 30th, additional measures, as needed, will be taken to satisfy the SWMMWW seasonal work limitations.

### 5.3 Minimum Requirement #3: Source Control of Pollution

The residential site consists of frontage improvements, driveways, single family homes, utilities, and stormwater BMPs. The driveways and streets are considered pollutant generating hard surfaces (PGHS). All PGHS within the project site will be routed over CAVFS to provide treatment meeting a low impact development (LID) approach and basic treatment requirements.

### 5.4 Minimum Requirement #4: Preservation of Natural Drainage Systems and Outfalls

Mass grading of the site will not be performed. The lot is an already graded lot located within a subdivision.


### 5.5 Minimum Requirement #5: On-site Stormwater Management

The project is within the City of Woodland limits and is less than 1 acre in size; therefore, based on the SWMMWW, LID standards are required to be met by using “any Flow Control BMPs desired to achieve the LID Performance Standard, and applying BMP T5.13: Post-Construction Soil Quality and Depth.” The LID performance standard is being met using a combination of BMP T7.40 CAVFS, BMP T7.20 Infiltration Trenches, and BMP T5.13 Post Construction Soils Depth and Quality.

See **Appendix C** for MGSFlood model inputs and results.



## Flow Duration Plot



**Figure 2: MGSFlood Results Showing for LID and Flow Control Requirements**

### 5.6 Minimum Requirement #6: Runoff Treatment

MR #6 is applicable to threshold discharge areas (TDAs) that have more than 5,000 SF of PGHS. The project proposes approximately 20,694 sf (0.48 acres) of new impervious surfaces from the frontage improvements, roofs and driveways; therefore, MR #6 applies. All new PGHS will be routed over CAVFs to achieve a minimum treatment level of 91% with continuous stormwater modeling. The runoff will then be captured and routed to an infiltration trench via area drains. Roof runoff will first be routed directly to the same infiltration trench for infiltration and flow control.

#### 5.6.1 Modeling

MGS Flood was used to model compliance with the requirements of the 2019 SWMMWW. This is a single-family residential development; therefore, enhanced treatment is not required.

Model inputs used for the subbasin are shown in Table 2 below:



**Table 2: Model Inputs**

TREATMENT CALCULATIONS			
	SF	ACRES	COVER
Total site	40,493	0.93	
Disturbed Area to be modeled	40,493	0.93	
Roofs	11,400	0.26	ROOFTOPS, FLAT
Lawn - Modified Soils	19,799	0.46	A/B, LAWN, FLAT
Driveways	9,294	0.21	DRIVEWAYS/FLAT

**Abbreviations**

A/B– Soil Type A

An estimated infiltration rate of 3.27 inches per hour (in/hr) was used in these preliminary calculations. Due to the current pending status of the geotechnical analysis and report, this rate is an estimate based off the findings from recent geotechnical studies completed in the surrounding area with similar soils. Once the geotechnical findings are completed, the actual infiltration rates will be updated to reflect the findings.

**5.7 Minimum Requirement #7: Flow Control**

Developed discharge durations must match pre-developed durations for the range of pre-developed discharge rates from 50% of the 20-year peak flow up to the full 50-year peak flow. The infiltration basins located on each lot provide adequate flow control. All new PGHS will be routed over CAVFs to achieve a minimum treatment level of 91% with continuous stormwater modeling. The runoff will then be captured and routed to an infiltration trench via area drains for flow control. Roof runoff will first be routed to the same infiltration trench for dispersion. See Figure 2 above, and **Appendix C** for MGSFlood results that demonstrate flow control provided with the by the BMP’s.

**5.8 Minimum Requirement #8: Wetlands Protection**

There are no critical areas or wetlands found within the immediate vicinity of the site.

**5.9 Minimum Requirement #9: Operation and Maintenance**

The stormwater systems will all be privately owned, operated, and maintained by the individual homeowners. See Volume V of the SWMMWW. The City of Woodland will assume ownership for the CAVFS that treat runoff associated with the frontage improvements.



## 6.0 CONVEYANCE SYSTEMS ANALYSIS AND DESIGN

---

All stormwater piping shall meet the minimum requirements of the Woodland City Code. All storm sewer conveyance calculations will be completed with the final stormwater TIR and managed following the 2019 SWMMWW, making the potential impact on the downstream properties and conveyances systems minimal.



## **7.0 ADDITIONAL REQUIREMENTS**

---

### **7.1 Offsite Analysis**

No offsite analysis has been complete at this stage. The site is located in an established subdivision with slopes from 0-5%. Flow from adjacent parcels is very minimal.

### **7.2 Closed Depression Analysis**

This site is not classified as a closed depression; therefore, this section does not apply.

### **7.3 Other Permits**

A NPDES permit will not be required due to there being less than one acre of disturbance.

### **7.4 Approval Conditions Summary**

All conditions from the site plan review will be addressed in the final TIR.

### **7.5 Special Reports and Studies**

The following analysis have been, or will be completed:

- Geotechnical – To be completed.





## 8.0 APPENDICES

---

**Appendix A – Stormwater Calculation Assumptions and Stormwater Concept**

**Appendix B – Geotechnical Information**



**Appendix C – MGS Flood Modeling Results**

**Appendix D – BMP Details**

APPENDIX A: STORMWATER  
CALCULATION ASSUMPTIONS AND  
STORMWATER CONCEPT



**Figure I-3.1: Flow Chart for Determining Requirements for New Development**




**Flow Chart for Determining Requirements for New Development**

Revised March 2019

Please see <http://www.ecy.wa.gov/copyright.html> for copyright notice including permissions, limitation of liability, and disclaimer.

**STORMWATER KEYNOTES:**

- A. STORMWATER FACILITIES THAT ARE PRIVATELY OWNED AND SHALL BE MAINTAINED BY THE LANDOWNER
- B. ALL INFILTRATION SHALL BE AT LEAST 10 FEET FROM ANY STRUCTURE, PROPERTY LINE, OR SENSITIVE AREA (EXCEPT SLOPES OVER 40%)



**STORMWATER PLAN**  
SCALE: 1" = 20'



Know what's below.  
**Call before you dig.**  
CALL 2 BUSINESS DAYS BEFORE YOU DIG.  
CAUTION: UTILITY INFORMATION IS APPROXIMATE.  
VERIFY ALL UTILITIES PRIOR TO CONSTRUCTION.

Revisions:


LINE IS 1" ON FULL SCALE DRAWING



Ridgefield, WA  
Duluth + Minneapolis, MN  
www.windsorengineers.com  
Copyright 2023 By Windsor Engineers, LLC  
All Rights Reserved.



**438 HOMESTEAD**  
438 WASHINGTON STREET, WOODLAND, WA 98674

**SITE PLAN REVIEW**  
Project No: 21035.1  
Issue Date: 6/21/2023


Project Manager: DCK  
Drawn by: CKJ/QK  
Checked by: TWT

**STORMWATER PLAN**  
  
**C390**

ISSUED FOR SITE PLAN REVIEW

PLOT DATE: 6/20/2023 4:35 PM - FILE: C:\Users\DanK\OneDrive - Windsor Engineers\OneDrive - Windsor Engineers\05\_Projects\2023\21035.1\_438\_Homestead\02\_Drawings\01\_Working\04\_Final\Sheet\21035.1\_PSI\_STM\_P1C.rvt

**APPENDIX B: GEOTECHNICAL  
INFORMATION**





United States  
Department of  
Agriculture

**NRCS**

Natural  
Resources  
Conservation  
Service

A product of the National  
Cooperative Soil Survey,  
a joint effort of the United  
States Department of  
Agriculture and other  
Federal agencies, State  
agencies including the  
Agricultural Experiment  
Stations, and local  
participants

# Custom Soil Resource Report for **Cowlitz County, Washington**



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.



# Contents

---

<b>Preface</b> .....	2
<b>How Soil Surveys Are Made</b> .....	5
<b>Soil Map</b> .....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
Cowlitz County, Washington.....	13
141—Newberg fine sandy loam, 0 to 3 percent slopes.....	13
<b>References</b> .....	15

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

## Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

## Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map

---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

# Custom Soil Resource Report Soil Map



Map Scale: 1:517 if printed on A landscape (11" x 8.5") sheet.




Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 10N WGS84





### MAP LEGEND


**Area of Interest (AOI)**

 Area of Interest (AOI)




















**Soils**







 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

**Special Point Features**






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Cowlitz County, Washington  
 Survey Area Data: Version 23, Aug 31, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 26, 2019—Jun 11, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
141	Newberg fine sandy loam, 0 to 3 percent slopes	0.9	100.0%
<b>Totals for Area of Interest</b>		<b>0.9</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.



## Custom Soil Resource Report

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## Cowlitz County, Washington

### 141—Newberg fine sandy loam, 0 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2f3d  
*Elevation:* 10 to 1,500 feet  
*Mean annual precipitation:* 18 to 60 inches  
*Mean annual air temperature:* 50 to 54 degrees F  
*Frost-free period:* 165 to 210 days  
*Farmland classification:* All areas are prime farmland

#### Map Unit Composition

*Newberg and similar soils:* 85 percent  
*Minor components:* 5 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Newberg

##### Setting

*Landform:* Flood plains  
*Parent material:* Alluvium

##### Typical profile

*H1 - 0 to 10 inches:* fine sandy loam  
*H2 - 10 to 28 inches:* very fine sandy loam  
*H3 - 28 to 60 inches:* fine sandy loam

##### Properties and qualities

*Slope:* 0 to 3 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Well drained  
*Capacity of the most limiting layer to transmit water (Ksat):* High (1.98 to 5.95 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* OccasionalNone  
*Frequency of ponding:* None  
*Available water supply, 0 to 60 inches:* Moderate (about 7.6 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 3w  
*Hydrologic Soil Group:* A  
*Ecological site:* F002XA008WA - Puget Lowlands Riparian Forest  
*Forage suitability group:* Soils with Few Limitations (G002XV502WA)  
*Other vegetative classification:* Soils with Few Limitations (G002XV502WA)  
*Hydric soil rating:* No

#### Minor Components

##### Chehalis

*Percent of map unit:* 5 percent  
*Hydric soil rating:* No

## Custom Soil Resource Report

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)

# SOILS ANALYSIS REPORT

---

WASHINGTON STREET SHORT PLAT

& CC STREET SHORT PLAT

**FEBRUARY 13, 2020**

**PREPARED FOR:**

ROGER FOLEY  
35909 NE 251<sup>ST</sup> AVENUE  
PO BOX 99  
YACOLT, WA 98675  
ROGER.FOLEY505@GMAIL.COM  
(360) 901-0056

**PREPARED BY:**


JOLMA DESIGN, LLC  
PO BOX 1281  
BATTLE GROUND, WA 98604  
ADMIN@JOLMADESIGN.COM  
(360) 723-0392

# SOILS ANALYSIS REPORT

WASHINGTON STREET SHORT PLAT  
& CC STREET SHORT PLAT

*THE MATERIAL AND DATA IN THIS REPORT WERE PREPARED  
UNDER THE SUPERVISION AND DIRECTION OF THE UNDERSIGNED.*

JOLMA DESIGN, LLC



---

BYRON JOLMA, PE  
PRINCIPAL ENGINEER

# CONTENTS

---

1	Introduction .....	1
1.1	Site Location & Description .....	1
1.2	Proposed Development .....	1
2	Soils Description .....	1
2.1	Mapped Soil Type .....	1
2.2	Infiltration Testing .....	1
2.3	Conclusions and Recommendations .....	1

## FIGURES

### ATTACHMENT 1

#### INFILTRATION TEST RESULTS



# 1 INTRODUCTION

---

## 1.1 Site Location & Description

The project site is comprised of two (2) tax lots located at 437 Washington Street and 438 CC Street, Woodland, Washington 98674.

Both sites have an existing house and garage. Each site currently contains its own existing driveway located on the property.

## 1.2 Proposed Development

The client is proposing to divide these two parcels, approximately 1.1-acres total, zoned low density residential (LDR-6) under City of Woodland short plat land division procedures. This project will be divided into two (2) short plat applications and this process will require a boundary line adjustment.

# 2 SOILS DESCRIPTION

---

## 2.1 Mapped Soil Type

According to the Cowlitz County GIS at the site of 438 CC street and 437 Washington Street in Woodland, Washington. Onsite soils primary consists of Newberg sandy loam (NbB), 0 to 3 percent slopes.

The Newberg series generally consists of very deep, somewhat excessively drained soils formed in loamy and sandy alluvium from sedimentary and basic igneous rocks on flood plains having 0 to 4 percent slopes. NbB soils typically have moderately rapid permeability, slow runoff, and are classified under Hydrologic Soil Group.


## 2.2 Infiltration Testing

An infiltration test was conducted on January 2, 2020. There were two (2) tests at approximately 6" depth that were performed along Washington Street (IT-01) and CC Street (IT-02). The infiltration test results are included in the appendix of this report.

## 2.3 Conclusions and Recommendations

JD recommends infiltration to near-surface soils downgradient of dispersion BMPs be used to meet the flow control requirements.

# FIGURES



# ATTACHMENT 1

INFILTRATION TEST RESULTS

# INFILTRATION TEST DATA SHEET

## Project Information


<b>Project Name:</b>	CC Street Short Plat	<b>Project No.:</b>	19166
<b>Project Address:</b>	438 CC Street & 437 Washington Street Woodland, WA 98674	<b>Tested By:</b>	DRR
<b>Test Hole No.:</b>	IT-01	<b>Date:</b>	1/2/2020
<b>Test Hole Depth:</b>	6"	<b>Weather:</b>	Cloudy, 46°
<b>Depth to Groundwater</b>	>5 ft		

## Calculations

### Parameters

Parameter	Description	Equation	Value
L	Length of Flow/Embedment Depth (in)	n/a	6
t	Elapsed Drawdown Time (hr)	Stop Time - Start Time	Varies
k <sub>r</sub>	Tested Coefficient of Permeability (in/hr)	$k_r = (L/t) * \ln(h_i / h_f)$	Varies
k <sub>AVG</sub>	AVG. Tested Coefficient of Permeability (in/hr)	$k_{AVG} = k_{DES} = k_{AVG} / CF_{TOT}$	6.55
CF	Correction Factor		2
k <sub>DES</sub>	Design Coefficient of Permeability (in/hr)		3.27

**Notes:**  
This test was an adjacent to Washington Street.



## Field Data

Trial No.	Start Time	Stop Time	Elapsed Drawdown Time, t (hr)	Initial Depth to Water (in)	Final Depth to Water (in)	Initial Height of Water, h <sub>i</sub> (in)	Final Height of Water, h <sub>f</sub> (in)	k <sub>r</sub> (in/hr)
1	11:21 AM	12:21 PM	1:00	0.00	6.25	9.00	2.75	7.11
2	12:21 PM	1:21 PM	1:00	0.00	6.13	9.00	2.88	6.85
3	1:21 PM	1:41 PM	0:20	0.00	2.44	9.00	6.56	5.69

# INFILTRATION TEST DATA SHEET

## Project Information


<b>Project Name:</b>	CC Street Short Plat	<b>Project No.:</b>	19166
<b>Project Address:</b>	438 CC Street & 437 Washington Street Woodland, WA 98674	<b>Tested By:</b>	DRR
<b>Test Hole No.:</b>	IT-02	<b>Date:</b>	1/2/2020
<b>Test Hole Depth:</b>	6"	<b>Weather:</b>	Cloudy, 46°
<b>Depth to Groundwater</b>	>5 ft		

## Calculations

### Parameters

Parameter	Description	Equation	Value
L	Length of Flow/Embedment Depth (in)	n/a	6
t	Elapsed Drawdown Time (hr)	Stop Time - Start Time	Varies
k <sub>r</sub>	Tested Coefficient of Permeability (in/hr)	$k_r = (L/t) * \ln(h_i / h_f)$	Varies
k <sub>AVG</sub>	Avg. Tested Coefficient of Permeability (in/hr)	$k_{AVG} = k_{T1+T2+...Tn} / \text{No. of Trials}$	13.18
CF	Correction Factor		2
k <sub>DES</sub>	Design Coefficient of Permeability (in/hr)	$k_{DES} = k_{AVG} / CF_{TOT}$	6.59

**Notes:**  
This test was adjacent to CC Street.



## Field Data

Trial No.	Start Time	Stop Time	Elapsed Drawdown Time, t (hr)	Initial Depth to Water (in)	Final Depth to Water (in)	Initial Height of Water, h <sub>i</sub> (in)	Final Height of Water, h <sub>f</sub> (in)	k <sub>r</sub> (in/hr)
1	11:33 AM	12:08 PM	0:35	0.00	6.63	9.00	2.38	13.70
2	12:08 PM	12:43 PM	0:35	0.00	6.50	9.00	2.50	13.18
3	12:43 PM	1:18 PM	0:35	0.00	6.38	9.00	2.63	12.67

# Custom Soil Resource Report for **Cowlitz County, Washington**

## CC Street Short Plat Soils Report



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require



alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

<b>Preface</b> .....	2
<b>Soil Map</b> .....	5
Soil Map.....	6
Legend.....	7
Map Unit Legend.....	8
Map Unit Descriptions.....	8
Cowlitz County, Washington.....	10
141—Newberg fine sandy loam, 0 to 3 percent slopes.....	10
<b>References</b> .....	12

# Soil Map

---


The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report  
Soil Map



Soil Map may not be valid at this scale.

Map Scale: 1:1,330 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 10N WGS84

## MAP LEGEND

- Area of Interest (AOI)**
  - Area of Interest (AOI)
- Soils**
  - Soil Map Unit Polygons
  - Soil Map Unit Lines
  - Soil Map Unit Points
- Special Point Features**
  - Blowout
  - Borrow Pit
  - Clay Spot
  - Closed Depression
  - Gravel Pit
  - Gravelly Spot
  - Landfill
  - Lava Flow
  - Marsh or swamp
  - Mine or Quarry
  - Miscellaneous Water
  - Perennial Water
  - Rock Outcrop
  - Saline Spot
  - Sandy Spot
  - Severely Eroded Spot
  - Sinkhole
  - Slide or Slip
  - Sodic Spot
- Water Features**
  - Streams and Canals
- Transportation**
  - Rails
  - Interstate Highways
  - US Routes
  - Major Roads
  - Local Roads
- Background**
  - Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Cowlitz County, Washington  
 Survey Area Data: Version 20, Sep 16, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 26, 2019—Jun 11, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
141	Newberg fine sandy loam, 0 to 3 percent slopes	6.6	100.0%
<b>Totals for Area of Interest</b>		<b>6.6</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

## Custom Soil Resource Report

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## Cowlitz County, Washington

### 141—Newberg fine sandy loam, 0 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2f3d

*Elevation:* 10 to 1,500 feet

*Mean annual precipitation:* 18 to 60 inches

*Mean annual air temperature:* 50 to 54 degrees F

*Frost-free period:* 165 to 210 days

*Farmland classification:* Prime farmland if protected from flooding or not frequently flooded during the growing season

#### Map Unit Composition

*Newberg and similar soils:* 85 percent

*Minor components:* 5 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Newberg

##### Setting

*Landform:* Flood plains

*Parent material:* Alluvium

##### Typical profile

*H1 - 0 to 10 inches:* fine sandy loam

*H2 - 10 to 28 inches:* very fine sandy loam, sandy loam, fine sandy loam

*H2 - 10 to 28 inches:* fine sandy loam, loamy fine sand, loamy very fine sand

*H2 - 10 to 28 inches:*

*H3 - 28 to 60 inches:*

*H3 - 28 to 60 inches:*

*H3 - 28 to 60 inches:*

##### Properties and qualities

*Slope:* 0 to 3 percent

*Depth to restrictive feature:* More than 80 inches

*Natural drainage class:* Well drained

*Capacity of the most limiting layer to transmit water (Ksat):* High (1.98 to 5.95 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* Occasional

*Frequency of ponding:* None

*Available water storage in profile:* Very high (about 20.1 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 3w

*Hydrologic Soil Group:* A

*Forage suitability group:* Soils with Few Limitations (G002XV502WA)

*Hydric soil rating:* No

#### Minor Components

##### Chehalis

*Percent of map unit:* 5 percent

*Hydric soil rating:* No



# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)

APPENDIX C: MGS FLOOD MODELING RESULTS



# MGS FLOOD PROJECT REPORT

Program Version: MGSFlood 4.58  
Program License Number: 202010002  
Project Simulation Performed on: 06/29/2023 11:53 AM  
Report Generation Date: 06/29/2023 11:53 AM

Input File Name: 438 Homestead - Prelim 2.fld  
Project Name: 438 Homestead  
Analysis Title: Preliminary  
Comments:

## PRECIPITATION INPUT

Computational Time Step (Minutes): 15

Extended Precipitation Time Series Selected

Full Period of Record Available used for Routing

Climatic Region Number: 26  
Precipitation Station : 97004805 Vancouver 48 in\_5min 10/01/1939-10/01/2060  
Evaporation Station : 971048 Vancouver 48 in MAP

Evaporation Scale Factor : 0.750

HSPF Parameter Region Number: 1  
HSPF Parameter Region Name : Ecology Default

\*\*\*\*\* Default HSPF Parameters Used (Not Modified by User) \*\*\*\*\*

## \*\*\*\*\* WATERSHED DEFINITION \*\*\*\*\*

### Predevelopment/Post Development Tributary Area Summary

	Predeveloped	Post Developed
Total Subbasin Area (acres)	0.930	0.912
Area of Links that Include Precip/Evap (acres)	0.000	0.018
Total (acres)	0.930	0.930

### -----SCENARIO: PREDEVELOPED

Number of Subbasins: 1

----- Subbasin : Subbasin 1 -----  
-----Area (Acres) -----  
A/B, Forest, Flat 0.930

-----  
Subbasin Total 0.930

### -----SCENARIO: POSTDEVELOPED

Number of Subbasins: 19

----- Subbasin : Lot 1 Roof -----  
-----Area (Acres) -----  
ROOF TOPS/FLAT 0.044

-----  
Subbasin Total 0.044

----- Subbasin : Right of Way -----  
-----Area (Acres) -----  
ROADS/FLAT 0.037

-----  
Subbasin Total 0.037

----- Subbasin : Lot 2 Roof -----  
-----Area (Acres) -----  
ROOF TOPS/FLAT 0.044  
-----  
Subbasin Total 0.044

----- Subbasin : Lot 3 Roof -----  
-----Area (Acres) -----  
ROOF TOPS/FLAT 0.044  
-----  
Subbasin Total 0.044

----- Subbasin : Lot 4 Roof -----  
-----Area (Acres) -----  
ROOF TOPS/FLAT 0.044  
-----  
Subbasin Total 0.044

----- Subbasin : Lot 5 Roof -----  
-----Area (Acres) -----  
ROOF TOPS/FLAT 0.044  
-----  
Subbasin Total 0.044

----- Subbasin : Lot 5 Driveway -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.045  
-----  
Subbasin Total 0.045

----- Subbasin : Lot 4 Driveway -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.045  
-----  
Subbasin Total 0.045

----- Subbasin : Lot 3 Driveway -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.011  
-----  
Subbasin Total 0.011

----- Subbasin : Lot 2 Driveway -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.011  
-----  
Subbasin Total 0.011

----- Subbasin : Lot 1 Driveway -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.011  
-----  
Subbasin Total 0.011

----- Subbasin : Lot 6 Roof -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.044  
-----  
Subbasin Total 0.044

----- Subbasin : Lot 6 Driveway -----  
-----Area (Acres) -----  
DRIVEWAYS/FLAT 0.045  
-----  
Subbasin Total 0.045

----- Subbasin : Lot 1 Lawn -----  
-----Area (Acres) -----  
A/B, Lawn, Flat 0.082  
-----  
Subbasin Total 0.082

----- Subbasin : Lot 2 Lawn -----  
-----Area (Acres) -----  
A/B, Lawn, Flat 0.083  
-----  
Subbasin Total 0.083

----- Subbasin : Lot 3 Lawn -----  
-----Area (Acres) -----  
A/B, Lawn, Flat 0.083  
-----  
Subbasin Total 0.083

----- Subbasin : Lot 4 Lawn -----  
-----Area (Acres) -----  
A/B, Lawn, Flat 0.067  
-----  
Subbasin Total 0.067

----- Subbasin : Lot 5 Lawn -----  
-----Area (Acres) -----  
A/B, Lawn, Flat 0.064  
-----  
Subbasin Total 0.064

----- Subbasin : Lot 6 Lawn -----  
-----Area (Acres) -----  
A/B, Lawn, Flat 0.064  
-----  
Subbasin Total 0.064

\*\*\*\*\* LINK DATA \*\*\*\*\*

-----SCENARIO: PREDEVELOPED  
Number of Links: 0

\*\*\*\*\* LINK DATA \*\*\*\*\*

-----SCENARIO: POSTDEVELOPED  
Number of Links: 20

-----  
**Link Name: POC**  
Link Type: Copy  
Downstream Link: None

-----  
**Link Name: Lot 1 - BMP T5.10C**

Link Type: Infiltration Trench  
Downstream Link Name: POC

Trench Type : Trench on Embankment Sideslope  
Trench Length (ft) : 40.00  
Trench Width (ft) : 3.50  
Trench Depth (ft) : 3.00  
Trench Bottom Elev (ft) : 100.00  
Trench Rockfill Porosity (%) : 30.00

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

-----  
**Link Name: Lot 2 - BMP T5.10C**

Link Type: Infiltration Trench  
Downstream Link Name: POC

Trench Type : Trench on Embankment Sideslope  
Trench Length (ft) : 40.00  
Trench Width (ft) : 3.50  
Trench Depth (ft) : 3.00  
Trench Bottom Elev (ft) : 100.00  
Trench Rockfill Porosity (%) : 30.00

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

-----  
**Link Name: Lot 3 - BMP T5.10C**

Link Type: Infiltration Trench  
Downstream Link Name: POC

Trench Type : Trench on Embankment Sideslope  
Trench Length (ft) : 40.00  
Trench Width (ft) : 3.50  
Trench Depth (ft) : 3.00  
Trench Bottom Elev (ft) : 100.00  
Trench Rockfill Porosity (%) : 30.00

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

-----  
**Link Name: Lot 4 - BMP T5.10C**

Link Type: Infiltration Trench  
Downstream Link Name: POC

Trench Type : Trench on Embankment Sideslope  
Trench Length (ft) : 40.00  
Trench Width (ft) : 3.50  
Trench Depth (ft) : 3.00  
Trench Bottom Elev (ft) : 100.00  
Trench Rockfill Porosity (%) : 30.00

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

-----  
**Link Name: Lot 5 - BMP T5.10C**

Link Type: Infiltration Trench  
Downstream Link Name: POC

Trench Type : Trench on Embankment Sideslope  
Trench Length (ft) : 40.00  
Trench Width (ft) : 3.50  
Trench Depth (ft) : 3.00



Trench Bottom Elev (ft) : 100.00  
Trench Rockfill Porosity (%) : 30.00

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

---

**Link Name: Lot 5 CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: Lot 5 - BMP T5.10C

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 116.000  
CAVFS Width (ft) : 1.100  
CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

---

**Link Name: Lot 4 CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: Lot 4 - BMP T5.10C

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 116.000  
CAVFS Width (ft) : 1.100  
CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

---

**Link Name: Lot 3 CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: Lot 3 - BMP T5.10C

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 25.000  
CAVFS Width (ft) : 1.500  
CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

---

**Link Name: Lot 2 CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: Lot 2 - BMP T5.10C

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 25.000  
CAVFS Width (ft) : 1.500

CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

-----  
**Link Name: Lot 1 CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: Lot 1 - BMP T5.10C

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 25.000  
CAVFS Width (ft) : 1.500  
CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

-----  
**Link Name: ROW CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: POC

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 110.000  
CAVFS Width (ft) : 2.500  
CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

-----  
**Link Name: Lot 6 CAVFS**

Link Type: Compost Amended Vegetated Filter Strip (CAVFS)  
Downstream Link Name: Lot 6 - BMP T5.10C

Compost Thickness (ft) : 1.000  
Compost Porosity (%) : 10.000  
Compost Hydraulic Conductivity (in/hr) : 1.000  
CAVFS Length (ft) : 116.000  
CAVFS Width (ft) : 1.100  
CAVFS Slope, Z (ft/ft) : 100.000  
Gravel Spreader Width (ft) : 1.000  
Gravel Hydraulic Conductivity (in/hr) : 2.000  
Gravel Porosity (%) : 30.000  
Soil Infiltration Rate (in/hr) : 3.270  
Precipitation and Evaporation Applied to Surface of CAVFS

-----  
**Link Name: Lot 6 - BMP T5.10C**

Link Type: Infiltration Trench  
Downstream Link Name: POC

Trench Type : Trench on Embankment Sideslope  
Trench Length (ft) : 40.00  
Trench Width (ft) : 3.50  
Trench Depth (ft) : 3.00

Trench Bottom Elev (ft) : 100.00  
Trench Rockfill Porosity (%) : 30.00

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

---

**Link Name: Lot 1 BMP T5.13**

Link Type: Structure  
Downstream Link Name: POC

Prismatic Pond Option Used

Pond Floor Elevation (ft) : 100.00  
Riser Crest Elevation (ft) : 100.10  
Max Pond Elevation (ft) : 100.15  
Storage Depth (ft) : 0.10  
Pond Bottom Length (ft) : 54.0  
Pond Bottom Width (ft) : 15.0  
Pond Side Slopes (ft/ft) : Z1= 3.00 Z2= 3.00 Z3= 3.00 Z4= 3.00  
Bottom Area (sq-ft) : 810.  
Area at Riser Crest El (sq-ft) : 852.  
(acres) : 0.020  
Volume at Riser Crest (cu-ft) : 83.  
(ac-ft) : 0.002  
Area at Max Elevation (sq-ft) : 873.  
(acres) : 0.020  
Vol at Max Elevation (cu-ft) : 126.  
(ac-ft) : 0.003

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

Riser Geometry

Riser Structure Type : Circular  
Riser Diameter (in) : 24.00  
Common Length (ft) : 0.000  
Riser Crest Elevation : 100.10 ft

Hydraulic Structure Geometry

Number of Devices: 1

---Device Number 1 ---

Device Type : Circular Orifice  
Control Elevation (ft) : 100.00  
Diameter (in) : 1.00  
Orientation : Horizontal  
Elbow : Yes

---

**Link Name: Lot 2 BMP T5.13**

Link Type: Structure  
Downstream Link Name: POC

Prismatic Pond Option Used

Pond Floor Elevation (ft) : 100.00  
Riser Crest Elevation (ft) : 100.10  
Max Pond Elevation (ft) : 100.15  
Storage Depth (ft) : 0.10  
Pond Bottom Length (ft) : 54.0  
Pond Bottom Width (ft) : 15.0  
Pond Side Slopes (ft/ft) : Z1= 3.00 Z2= 3.00 Z3= 3.00 Z4= 3.00  
Bottom Area (sq-ft) : 810.  
Area at Riser Crest El (sq-ft) : 852.  
(acres) : 0.020  
Volume at Riser Crest (cu-ft) : 83.  
(ac-ft) : 0.002  
Area at Max Elevation (sq-ft) : 873.  
(acres) : 0.020

Vol at Max Elevation (cu-ft) : 126.  
(ac-ft) : 0.003

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

Riser Geometry  
Riser Structure Type : Circular  
Riser Diameter (in) : 24.00  
Common Length (ft) : 0.000  
Riser Crest Elevation : 100.10 ft

Hydraulic Structure Geometry

Number of Devices: 1

---Device Number 1 ---  
Device Type : Circular Orifice  
Control Elevation (ft) : 100.00  
Diameter (in) : 1.00  
Orientation : Horizontal  
Elbow : Yes

---

**Link Name: Lot 3 BMP T5.13**

Link Type: Structure  
Downstream Link Name: POC

Prismatic Pond Option Used

Pond Floor Elevation (ft) : 100.00  
Riser Crest Elevation (ft) : 100.10  
Max Pond Elevation (ft) : 100.15  
Storage Depth (ft) : 0.10  
Pond Bottom Length (ft) : 54.0  
Pond Bottom Width (ft) : 15.0  
Pond Side Slopes (ft/ft) : Z1= 3.00 Z2= 3.00 Z3= 3.00 Z4= 3.00  
Bottom Area (sq-ft) : 810.  
Area at Riser Crest El (sq-ft) : 852.  
(acres) : 0.020  
Volume at Riser Crest (cu-ft) : 83.  
(ac-ft) : 0.002  
Area at Max Elevation (sq-ft) : 873.  
(acres) : 0.020  
Vol at Max Elevation (cu-ft) : 126.  
(ac-ft) : 0.003

Constant Infiltration Option Used  
Infiltration Rate (in/hr): 3.27

Riser Geometry  
Riser Structure Type : Circular  
Riser Diameter (in) : 24.00  
Common Length (ft) : 0.000  
Riser Crest Elevation : 100.10 ft

Hydraulic Structure Geometry

Number of Devices: 1

---Device Number 1 ---  
Device Type : Circular Orifice  
Control Elevation (ft) : 100.00  
Diameter (in) : 1.00  
Orientation : Horizontal  
Elbow : Yes

---

**Link Name: Lot 4 BMP T5.13**

Link Type: Structure

Downstream Link Name: POC

Prismatic Pond Option Used

Pond Floor Elevation (ft) : 100.00  
Riser Crest Elevation (ft) : 100.10  
Max Pond Elevation (ft) : 100.15  
Storage Depth (ft) : 0.10  
Pond Bottom Length (ft) : 70.0  
Pond Bottom Width (ft) : 15.0  
Pond Side Slopes (ft/ft) : Z1= 3.00 Z2= 3.00 Z3= 3.00 Z4= 3.00  
Bottom Area (sq-ft) : 1050.  
Area at Riser Crest El (sq-ft) : 1,101.  
(acres) : 0.025  
Volume at Riser Crest (cu-ft) : 108.  
(ac-ft) : 0.002  
Area at Max Elevation (sq-ft) : 1127.  
(acres) : 0.026  
Vol at Max Elevation (cu-ft) : 163.  
(ac-ft) : 0.004

Constant Infiltration Option Used

Infiltration Rate (in/hr): 3.27

Riser Geometry

Riser Structure Type : Circular  
Riser Diameter (in) : 24.00  
Common Length (ft) : 0.000  
Riser Crest Elevation : 100.10 ft

Hydraulic Structure Geometry

Number of Devices: 1

---Device Number 1 ---

Device Type : Circular Orifice  
Control Elevation (ft) : 100.00  
Diameter (in) : 1.00  
Orientation : Horizontal  
Elbow : Yes

-----  
**Link Name: Lot 5 BMP T5.13**

Link Type: Structure

Downstream Link Name: POC

Prismatic Pond Option Used

Pond Floor Elevation (ft) : 100.00  
Riser Crest Elevation (ft) : 100.10  
Max Pond Elevation (ft) : 100.15  
Storage Depth (ft) : 0.10  
Pond Bottom Length (ft) : 68.0  
Pond Bottom Width (ft) : 15.0  
Pond Side Slopes (ft/ft) : Z1= 3.00 Z2= 3.00 Z3= 3.00 Z4= 3.00  
Bottom Area (sq-ft) : 1020.  
Area at Riser Crest El (sq-ft) : 1,070.  
(acres) : 0.025  
Volume at Riser Crest (cu-ft) : 105.  
(ac-ft) : 0.002  
Area at Max Elevation (sq-ft) : 1096.  
(acres) : 0.025  
Vol at Max Elevation (cu-ft) : 159.  
(ac-ft) : 0.004

Constant Infiltration Option Used

Infiltration Rate (in/hr): 3.27

Riser Geometry

Riser Structure Type : Circular  
Riser Diameter (in) : 24.00  
Common Length (ft) : 0.000

Riser Crest Elevation : 100.10 ft

Hydraulic Structure Geometry

Number of Devices: 1

---Device Number 1 ---

Device Type : Circular Orifice
Control Elevation (ft) : 100.00
Diameter (in) : 1.00
Orientation : Horizontal
Elbow : Yes

Link Name: Lot 6 BMP T5.13

Link Type: Structure
Downstream Link Name: POC

Prismatic Pond Option Used

Pond Floor Elevation (ft) : 100.00
Riser Crest Elevation (ft) : 100.10
Max Pond Elevation (ft) : 100.15
Storage Depth (ft) : 0.10
Pond Bottom Length (ft) : 68.0
Pond Bottom Width (ft) : 15.0
Pond Side Slopes (ft/ft) : Z1= 3.00 Z2= 3.00 Z3= 3.00 Z4= 3.00
Bottom Area (sq-ft) : 1020.
Area at Riser Crest El (sq-ft) : 1,070.
(acres) : 0.025
Volume at Riser Crest (cu-ft) : 105.
(ac-ft) : 0.002
Area at Max Elevation (sq-ft) : 1096.
(acres) : 0.025
Vol at Max Elevation (cu-ft) : 159.
(ac-ft) : 0.004

Constant Infiltration Option Used

Infiltration Rate (in/hr): 3.27

Riser Geometry

Riser Structure Type : Circular
Riser Diameter (in) : 24.00
Common Length (ft) : 0.000
Riser Crest Elevation : 100.10 ft

Hydraulic Structure Geometry

Number of Devices: 1

---Device Number 1 ---

Device Type : Circular Orifice
Control Elevation (ft) : 100.00
Diameter (in) : 1.00
Orientation : Horizontal
Elbow : Yes

\*\*\*\*\*FLOOD FREQUENCY AND DURATION STATISTICS\*\*\*\*\*

-----SCENARIO: PREDEVELOPED

Number of Subbasins: 1
Number of Links: 0

-----SCENARIO: POSTDEVELOPED

Number of Subbasins: 19
Number of Links: 20

\*\*\*\*\* Subbasin: Lot 1 Roof \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.895E-02
5-Year	2.521E-02
10-Year	2.949E-02
25-Year	3.629E-02
50-Year	4.044E-02
100-Year	5.196E-02
200-Year	5.833E-02
500-Year	6.673E-02

\*\*\*\*\* Subbasin: Right of Way \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.593E-02
5-Year	2.120E-02
10-Year	2.480E-02
25-Year	3.051E-02
50-Year	3.401E-02
100-Year	4.370E-02
200-Year	4.905E-02
500-Year	5.612E-02

\*\*\*\*\* Subbasin: Lot 2 Roof \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.895E-02
5-Year	2.521E-02
10-Year	2.949E-02
25-Year	3.629E-02
50-Year	4.044E-02
100-Year	5.196E-02
200-Year	5.833E-02
500-Year	6.673E-02

\*\*\*\*\* Subbasin: Lot 3 Roof \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.895E-02
5-Year	2.521E-02
10-Year	2.949E-02
25-Year	3.629E-02
50-Year	4.044E-02
100-Year	5.196E-02
200-Year	5.833E-02
500-Year	6.673E-02

\*\*\*\*\* Subbasin: Lot 4 Roof \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.895E-02
5-Year	2.521E-02
10-Year	2.949E-02

25-Year	3.629E-02
50-Year	4.044E-02
100-Year	5.196E-02
200-Year	5.833E-02
500-Year	6.673E-02

\*\*\*\*\* Subbasin: Lot 5 Roof \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.895E-02
5-Year	2.521E-02
10-Year	2.949E-02
25-Year	3.629E-02
50-Year	4.044E-02
100-Year	5.196E-02
200-Year	5.833E-02
500-Year	6.673E-02

\*\*\*\*\* Subbasin: Lot 5 Driveway \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.938E-02
5-Year	2.579E-02
10-Year	3.016E-02
25-Year	3.711E-02
50-Year	4.136E-02
100-Year	5.315E-02
200-Year	5.965E-02
500-Year	6.825E-02

\*\*\*\*\* Subbasin: Lot 4 Driveway \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.938E-02
5-Year	2.579E-02
10-Year	3.016E-02
25-Year	3.711E-02
50-Year	4.136E-02
100-Year	5.315E-02
200-Year	5.965E-02
500-Year	6.825E-02

\*\*\*\*\* Subbasin: Lot 3 Driveway \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.736E-03
5-Year	6.303E-03
10-Year	7.372E-03
25-Year	9.072E-03
50-Year	1.011E-02
100-Year	1.299E-02
200-Year	1.458E-02
500-Year	1.668E-02



\*\*\*\*\* Subbasin: Lot 2 Driveway \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.736E-03
5-Year	6.303E-03
10-Year	7.372E-03
25-Year	9.072E-03
50-Year	1.011E-02
100-Year	1.299E-02
200-Year	1.458E-02
500-Year	1.668E-02

\*\*\*\*\* Subbasin: Lot 1 Driveway \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.736E-03
5-Year	6.303E-03
10-Year	7.372E-03
25-Year	9.072E-03
50-Year	1.011E-02
100-Year	1.299E-02
200-Year	1.458E-02
500-Year	1.668E-02

\*\*\*\*\* Subbasin: Lot 6 Roof \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.895E-02
5-Year	2.521E-02
10-Year	2.949E-02
25-Year	3.629E-02
50-Year	4.044E-02
100-Year	5.196E-02
200-Year	5.833E-02
500-Year	6.673E-02

\*\*\*\*\* Subbasin: Lot 6 Driveway \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.938E-02
5-Year	2.579E-02
10-Year	3.016E-02
25-Year	3.711E-02
50-Year	4.136E-02
100-Year	5.315E-02
200-Year	5.965E-02
500-Year	6.825E-02

\*\*\*\*\* Subbasin: Lot 1 Lawn \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.210E-03

5-Year	4.838E-03
10-Year	7.352E-03
25-Year	1.523E-02
50-Year	1.740E-02
100-Year	2.240E-02
200-Year	3.319E-02
500-Year	4.745E-02

\*\*\*\*\* Subbasin: Lot 2 Lawn \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.225E-03
5-Year	4.897E-03
10-Year	7.442E-03
25-Year	1.541E-02
50-Year	1.761E-02
100-Year	2.267E-02
200-Year	3.360E-02
500-Year	4.803E-02

\*\*\*\*\* Subbasin: Lot 3 Lawn \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.225E-03
5-Year	4.897E-03
10-Year	7.442E-03
25-Year	1.541E-02
50-Year	1.761E-02
100-Year	2.267E-02
200-Year	3.360E-02
500-Year	4.803E-02

\*\*\*\*\* Subbasin: Lot 4 Lawn \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	9.886E-04
5-Year	3.953E-03
10-Year	6.008E-03
25-Year	1.244E-02
50-Year	1.422E-02
100-Year	1.830E-02
200-Year	2.712E-02
500-Year	3.877E-02

\*\*\*\*\* Subbasin: Lot 5 Lawn \*\*\*\*\*

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	9.443E-04
5-Year	3.776E-03
10-Year	5.739E-03
25-Year	1.188E-02
50-Year	1.358E-02
100-Year	1.748E-02
200-Year	2.590E-02
500-Year	3.704E-02

\*\*\*\*\* Subbasin: Lot 6 Lawn \*\*\*\*\*

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	9.443E-04
5-Year	3.776E-03
10-Year	5.739E-03
25-Year	1.188E-02
50-Year	1.358E-02
100-Year	1.748E-02
200-Year	2.590E-02
500-Year	3.704E-02

\*\*\*\*\* Link: POC \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.985E-04
5-Year	8.005E-04
10-Year	1.390E-03
25-Year	2.750E-03
50-Year	5.938E-03
100-Year	1.547E-02
200-Year	3.410E-02
500-Year	5.874E-02

\*\*\*\*\* Link: Lot 1 - BMP T5.10C \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.916E-02
5-Year	2.643E-02
10-Year	3.114E-02
25-Year	4.176E-02
50-Year	4.851E-02
100-Year	6.371E-02
200-Year	7.192E-02
500-Year	8.277E-02

\*\*\*\*\* Link: Lot 1 - BMP T5.10C \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.565E-06
5-Year	3.172E-06
10-Year	4.948E-06
25-Year	6.739E-06
50-Year	7.942E-06
100-Year	8.693E-06
200-Year	9.218E-06
500-Year	9.913E-06

\*\*\*\*\* Link: Lot 1 - BMP T5.10C \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	WSEL Peak (ft)
----------	----------------

1.05-Year	100.025
1.11-Year	100.055
1.25-Year	100.104
2.00-Year	100.313
3.33-Year	100.499
5-Year	100.634
10-Year	100.990
25-Year	101.348
50-Year	101.588
100-Year	101.739

\*\*\*\*\* Link: Lot 2 - BMP T5.10C \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	1.916E-02
5-Year	2.643E-02
10-Year	3.114E-02
25-Year	4.176E-02
50-Year	4.851E-02
100-Year	6.371E-02
200-Year	7.192E-02
500-Year	8.277E-02

\*\*\*\*\* Link: Lot 2 - BMP T5.10C \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	1.565E-06
5-Year	3.172E-06
10-Year	4.948E-06
25-Year	6.739E-06
50-Year	7.942E-06
100-Year	8.693E-06
200-Year	9.218E-06
500-Year	9.913E-06

\*\*\*\*\* Link: Lot 2 - BMP T5.10C \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) WSEL Peak (ft)

1.05-Year	100.025
1.11-Year	100.055
1.25-Year	100.104
2.00-Year	100.313
3.33-Year	100.499
5-Year	100.634
10-Year	100.990
25-Year	101.348
50-Year	101.588
100-Year	101.739

\*\*\*\*\* Link: Lot 3 - BMP T5.10C \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	1.916E-02
5-Year	2.643E-02

10-Year	3.114E-02
25-Year	4.176E-02
50-Year	4.851E-02
100-Year	6.371E-02
200-Year	7.192E-02
500-Year	8.277E-02

\*\*\*\*\* Link: Lot 3 - BMP T5.10C \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

=====	
2-Year	1.565E-06
5-Year	3.172E-06
10-Year	4.948E-06
25-Year	6.739E-06
50-Year	7.942E-06
100-Year	8.693E-06
200-Year	9.218E-06
500-Year	9.913E-06

\*\*\*\*\* Link: Lot 3 - BMP T5.10C \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) WSEL Peak (ft)

=====	
1.05-Year	100.025
1.11-Year	100.055
1.25-Year	100.104
2.00-Year	100.313
3.33-Year	100.499
5-Year	100.634
10-Year	100.990
25-Year	101.348
50-Year	101.588
100-Year	101.739

\*\*\*\*\* Link: Lot 4 - BMP T5.10C \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

=====	
2-Year	2.042E-02
5-Year	3.596E-02
10-Year	4.711E-02
25-Year	6.457E-02
50-Year	7.484E-02
100-Year	0.101
200-Year	0.115
500-Year	0.134

\*\*\*\*\* Link: Lot 4 - BMP T5.10C \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

=====	
2-Year	1.910E-06
5-Year	5.397E-06
10-Year	8.754E-06
25-Year	1.184E-05
50-Year	1.361E-05
100-Year	2.742E-03
200-Year	1.021E-02

\*\*\*\*\* Link: Lot 4 - BMP T5.10C \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
(Recurrence Interval Computed Using Gringorten Plotting Position)  
Tr (yrs) WSEL Peak (ft)

=====	
1.05-Year	100.025
1.11-Year	100.056
1.25-Year	100.104
2.00-Year	100.382
3.33-Year	100.796
5-Year	101.080
10-Year	101.751
25-Year	102.367
50-Year	102.721
100-Year	102.905

\*\*\*\*\* Link: Lot 5 - BMP T5.10C \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)  
Tr (yrs) Flood Peak (cfs)

=====	
2-Year	2.042E-02
5-Year	3.596E-02
10-Year	4.711E-02
25-Year	6.457E-02
50-Year	7.484E-02
100-Year	0.101
200-Year	0.115
500-Year	0.134

\*\*\*\*\* Link: Lot 5 - BMP T5.10C \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)  
Tr (yrs) Flood Peak (cfs)

=====	
2-Year	1.910E-06
5-Year	5.397E-06
10-Year	8.754E-06
25-Year	1.184E-05
50-Year	1.361E-05
100-Year	2.742E-03
200-Year	1.021E-02
500-Year	2.009E-02

\*\*\*\*\* Link: Lot 5 - BMP T5.10C \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
(Recurrence Interval Computed Using Gringorten Plotting Position)  
Tr (yrs) WSEL Peak (ft)

=====	
1.05-Year	100.025
1.11-Year	100.056
1.25-Year	100.104
2.00-Year	100.382
3.33-Year	100.796
5-Year	101.080
10-Year	101.751
25-Year	102.367
50-Year	102.721
100-Year	102.905

\*\*\*\*\* Link: Lot 5 CAVFS \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.938E-02
5-Year	2.579E-02
10-Year	3.016E-02
25-Year	3.711E-02
50-Year	4.136E-02
100-Year	5.315E-02
200-Year	5.965E-02
500-Year	6.825E-02

\*\*\*\*\* Link: Lot 5 CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	3.710E-03
5-Year	1.446E-02
10-Year	1.982E-02
25-Year	2.906E-02
50-Year	3.439E-02
100-Year	4.910E-02
200-Year	5.698E-02
500-Year	6.739E-02

\*\*\*\*\* Link: Lot 4 CAVFS \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.938E-02
5-Year	2.579E-02
10-Year	3.016E-02
25-Year	3.711E-02
50-Year	4.136E-02
100-Year	5.315E-02
200-Year	5.965E-02
500-Year	6.825E-02

\*\*\*\*\* Link: Lot 4 CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	3.710E-03
5-Year	1.446E-02
10-Year	1.982E-02
25-Year	2.906E-02
50-Year	3.439E-02
100-Year	4.910E-02
200-Year	5.698E-02
500-Year	6.739E-02

\*\*\*\*\* Link: Lot 3 CAVFS \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.736E-03

5-Year	6.303E-03
10-Year	7.372E-03
25-Year	9.072E-03
50-Year	1.011E-02
100-Year	1.299E-02
200-Year	1.458E-02
500-Year	1.668E-02

\*\*\*\*\* Link: Lot 3 CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	6.178E-06
5-Year	2.317E-03
10-Year	3.869E-03
25-Year	6.613E-03
50-Year	8.061E-03
100-Year	1.175E-02
200-Year	1.359E-02
500-Year	1.603E-02

\*\*\*\*\* Link: Lot 2 CAVFS \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.736E-03
5-Year	6.303E-03
10-Year	7.372E-03
25-Year	9.072E-03
50-Year	1.011E-02
100-Year	1.299E-02
200-Year	1.458E-02
500-Year	1.668E-02

\*\*\*\*\* Link: Lot 2 CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	6.178E-06
5-Year	2.317E-03
10-Year	3.869E-03
25-Year	6.613E-03
50-Year	8.061E-03
100-Year	1.175E-02
200-Year	1.359E-02
500-Year	1.603E-02

\*\*\*\*\* Link: Lot 1 CAVFS \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.736E-03
5-Year	6.303E-03
10-Year	7.372E-03
25-Year	9.072E-03
50-Year	1.011E-02
100-Year	1.299E-02
200-Year	1.458E-02
500-Year	1.668E-02



\*\*\*\*\* Link: Lot 1 CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats  
 Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)  
 =====  
 2-Year 6.178E-06  
 5-Year 2.317E-03  
 10-Year 3.869E-03  
 25-Year 6.613E-03  
 50-Year 8.061E-03  
 100-Year 1.175E-02  
 200-Year 1.359E-02  
 500-Year 1.603E-02

\*\*\*\*\* Link: ROW CAVFS \*\*\*\*\* Link Inflow Frequency Stats  
 Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)  
 =====  
 2-Year 1.593E-02  
 5-Year 2.120E-02  
 10-Year 2.480E-02  
 25-Year 3.051E-02  
 50-Year 3.401E-02  
 100-Year 4.370E-02  
 200-Year 4.905E-02  
 500-Year 5.612E-02

\*\*\*\*\* Link: ROW CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats  
 Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)  
 =====  
 2-Year 1.473E-06  
 5-Year 4.207E-06  
 10-Year 9.450E-06  
 25-Year 1.628E-05  
 50-Year 3.636E-04  
 100-Year 4.397E-03  
 200-Year 8.177E-03  
 500-Year 1.317E-02

\*\*\*\*\* Link: Lot 6 CAVFS \*\*\*\*\* Link Inflow Frequency Stats  
 Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)  
 =====  
 2-Year 1.895E-02  
 5-Year 2.521E-02  
 10-Year 2.949E-02  
 25-Year 3.629E-02  
 50-Year 4.044E-02  
 100-Year 5.196E-02  
 200-Year 5.833E-02  
 500-Year 6.673E-02

\*\*\*\*\* Link: Lot 6 CAVFS \*\*\*\*\* Link Outflow 1 Frequency Stats  
 Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	1.867E-03
5-Year	1.343E-02
10-Year	1.921E-02
25-Year	2.825E-02
50-Year	3.347E-02
100-Year	4.792E-02
200-Year	5.566E-02
500-Year	6.588E-02

\*\*\*\*\* Link: Lot 6 - BMP T5.10C \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	2.053E-02
5-Year	3.556E-02
10-Year	4.711E-02
25-Year	6.457E-02
50-Year	7.484E-02
100-Year	0.101
200-Year	0.115
500-Year	0.134

\*\*\*\*\* Link: Lot 6 - BMP T5.10C \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	1.882E-06
5-Year	5.313E-06
10-Year	8.817E-06
25-Year	1.181E-05
50-Year	1.320E-05
100-Year	2.742E-03
200-Year	1.021E-02
500-Year	2.009E-02

\*\*\*\*\* Link: Lot 6 - BMP T5.10C \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) WSEL Peak (ft)

1.05-Year	100.030
1.11-Year	100.064
1.25-Year	100.120
2.00-Year	100.376
3.33-Year	100.790
5-Year	101.063
10-Year	101.763
25-Year	102.363
50-Year	102.639
100-Year	102.908

\*\*\*\*\* Link: Lot 1 BMP T5.13

\*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

2-Year	1.210E-03
5-Year	4.838E-03
10-Year	7.352E-03
25-Year	1.523E-02

50-Year 1.740E-02  
 100-Year 2.240E-02  
 200-Year 3.319E-02  
 500-Year 4.745E-02

\*\*\*\*\* Link: Lot 1 BMP T5.13 \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

```
=====
```

2-Year	4.026E-05
5-Year	1.587E-04
10-Year	2.472E-04
25-Year	5.185E-04
50-Year	5.702E-04
100-Year	7.571E-04
200-Year	1.092E-03
500-Year	1.535E-03

\*\*\*\*\* Link: Lot 1 BMP T5.13 \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) WSEL Peak (ft)

```
=====
```

1.05-Year	-1.000E+03
1.11-Year	-1.000E+03
1.25-Year	-1.000E+03
2.00-Year	-1.000E+03
3.33-Year	-1.000E+03
5-Year	-1.000E+03
10-Year	-1.000E+03
25-Year	-1.000E+03
50-Year	-1.000E+03
100-Year	-1.000E+03

\*\*\*\*\* Link: Lot 2 BMP T5.13 \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

```
=====
```

2-Year	1.225E-03
5-Year	4.897E-03
10-Year	7.442E-03
25-Year	1.541E-02
50-Year	1.761E-02
100-Year	2.267E-02
200-Year	3.360E-02
500-Year	4.803E-02

\*\*\*\*\* Link: Lot 2 BMP T5.13 \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)  
 Tr (yrs) Flood Peak (cfs)

```
=====
```

2-Year	4.075E-05
5-Year	1.607E-04
10-Year	2.503E-04
25-Year	5.248E-04
50-Year	5.771E-04
100-Year	7.663E-04
200-Year	1.105E-03
500-Year	1.554E-03

\*\*\*\*\* Link: Lot 2 BMP T5.13 \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	WSEL Peak (ft)
1.05-Year	-1.000E+03
1.11-Year	-1.000E+03
1.25-Year	-1.000E+03
2.00-Year	-1.000E+03
3.33-Year	-1.000E+03
5-Year	-1.000E+03
10-Year	-1.000E+03
25-Year	-1.000E+03
50-Year	-1.000E+03
100-Year	-1.000E+03

\*\*\*\*\* Link: Lot 3 BMP T5.13 \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	1.225E-03
5-Year	4.897E-03
10-Year	7.442E-03
25-Year	1.541E-02
50-Year	1.761E-02
100-Year	2.267E-02
200-Year	3.360E-02
500-Year	4.803E-02

\*\*\*\*\* Link: Lot 3 BMP T5.13 \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	4.075E-05
5-Year	1.607E-04
10-Year	2.503E-04
25-Year	5.248E-04
50-Year	5.771E-04
100-Year	7.663E-04
200-Year	1.105E-03
500-Year	1.554E-03

\*\*\*\*\* Link: Lot 3 BMP T5.13 \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	WSEL Peak (ft)
1.05-Year	-1.000E+03
1.11-Year	-1.000E+03
1.25-Year	-1.000E+03
2.00-Year	-1.000E+03
3.33-Year	-1.000E+03
5-Year	-1.000E+03
10-Year	-1.000E+03
25-Year	-1.000E+03
50-Year	-1.000E+03
100-Year	-1.000E+03

\*\*\*\*\* Link: Lot 4 BMP T5.13 \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	9.886E-04
5-Year	3.953E-03
10-Year	6.008E-03
25-Year	1.244E-02
50-Year	1.422E-02
100-Year	1.830E-02
200-Year	2.712E-02
500-Year	3.877E-02

\*\*\*\*\* Link: Lot 4 BMP T5.13

\*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	2.557E-05
5-Year	1.008E-04
10-Year	1.571E-04
25-Year	3.294E-04
50-Year	3.622E-04
100-Year	4.810E-04
200-Year	6.937E-04
500-Year	9.748E-04

\*\*\*\*\* Link: Lot 4 BMP T5.13

\*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	WSEL Peak (ft)
1.05-Year	-1.000E+03
1.11-Year	-1.000E+03
1.25-Year	-1.000E+03
2.00-Year	-1.000E+03
3.33-Year	-1.000E+03
5-Year	-1.000E+03
10-Year	-1.000E+03
25-Year	-1.000E+03
50-Year	-1.000E+03
100-Year	-1.000E+03

\*\*\*\*\* Link: Lot 5 BMP T5.13

\*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	9.443E-04
5-Year	3.776E-03
10-Year	5.739E-03
25-Year	1.188E-02
50-Year	1.358E-02
100-Year	1.748E-02
200-Year	2.590E-02
500-Year	3.704E-02

\*\*\*\*\* Link: Lot 5 BMP T5.13

\*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
(Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	2.512E-05

5-Year 9.907E-05  
 10-Year 1.543E-04  
 25-Year 3.237E-04  
 50-Year 3.559E-04  
 100-Year 4.726E-04  
 200-Year 6.816E-04  
 500-Year 9.579E-04

\*\*\*\*\* Link: Lot 5 BMP T5.13 \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	WSEL Peak (ft)
1.05-Year	-1.000E+03
1.11-Year	-1.000E+03
1.25-Year	-1.000E+03
2.00-Year	-1.000E+03
3.33-Year	-1.000E+03
5-Year	-1.000E+03
10-Year	-1.000E+03
25-Year	-1.000E+03
50-Year	-1.000E+03
100-Year	-1.000E+03

\*\*\*\*\* Link: Lot 6 BMP T5.13 \*\*\*\*\* Link Inflow Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	9.443E-04
5-Year	3.776E-03
10-Year	5.739E-03
25-Year	1.188E-02
50-Year	1.358E-02
100-Year	1.748E-02
200-Year	2.590E-02
500-Year	3.704E-02

\*\*\*\*\* Link: Lot 6 BMP T5.13 \*\*\*\*\* Link Outflow 1 Frequency Stats

Flood Frequency Data(cfs)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	Flood Peak (cfs)
2-Year	2.512E-05
5-Year	9.907E-05
10-Year	1.543E-04
25-Year	3.237E-04
50-Year	3.559E-04
100-Year	4.726E-04
200-Year	6.816E-04
500-Year	9.579E-04

\*\*\*\*\* Link: Lot 6 BMP T5.13 \*\*\*\*\* Link WSEL Stats

WSEL Frequency Data(ft)  
 (Recurrence Interval Computed Using Gringorten Plotting Position)

Tr (yrs)	WSEL Peak (ft)
1.05-Year	-1.000E+03
1.11-Year	-1.000E+03
1.25-Year	-1.000E+03
2.00-Year	-1.000E+03
3.33-Year	-1.000E+03
5-Year	-1.000E+03

10-Year -1.000E+03  
 25-Year -1.000E+03  
 50-Year -1.000E+03  
 100-Year -1.000E+03

\*\*\*\*\*Groundwater Recharge Summary\*\*\*\*\*

Recharge is computed as input to PerInd Groundwater Plus Infiltration in Structures

Total Predeveloped Recharge During Simulation	
Model Element	Recharge Amount (ac-ft)
Subbasin: Subbasin 1	260.004
<b>Total:</b>	<b>260.004</b>

Total Post Developed Recharge During Simulation	
Model Element	Recharge Amount (ac-ft)
Subbasin: Lot 1 Roof	0.000
Subbasin: Right of Way	0.000
Subbasin: Lot 2 Roof	0.000
Subbasin: Lot 3 Roof	0.000
Subbasin: Lot 4 Roof	0.000
Subbasin: Lot 5 Roof	0.000
Subbasin: Lot 5 Driveway	0.000
Subbasin: Lot 4 Driveway	0.000
Subbasin: Lot 3 Driveway	0.000
Subbasin: Lot 2 Driveway	0.000
Subbasin: Lot 1 Driveway	0.000
Subbasin: Lot 6 Roof	0.000
Subbasin: Lot 6 Driveway	0.000
Subbasin: Lot 1 Lawn	27.176
Subbasin: Lot 2 Lawn	27.507
Subbasin: Lot 3 Lawn	27.507
Subbasin: Lot 4 Lawn	22.205
Subbasin: Lot 5 Lawn	21.211
Subbasin: Lot 6 Lawn	21.211
Link: POC	0.000
Link: Lot 1 - BMP T5.10C	18.737
Link: Lot 2 - BMP T5.10C	18.737
Link: Lot 3 - BMP T5.10C	18.737
Link: Lot 4 - BMP T5.10C	18.806
Link: Lot 5 - BMP T5.10C	18.806
Link: Lot 5 CAVFS	20.344
Link: Lot 4 CAVFS	20.344
Link: Lot 3 CAVFS	5.047
Link: Lot 2 CAVFS	5.047
Link: Lot 1 CAVFS	5.047
Link: ROW CAVFS	18.522
Link: Lot 6 CAVFS	19.926
Link: Lot 6 - BMP T5.10C	19.223
Link: Lot 1 BMP T5.13	0.128
Link: Lot 2 BMP T5.13	0.129
Link: Lot 3 BMP T5.13	0.129
Link: Lot 4 BMP T5.13	0.104
Link: Lot 5 BMP T5.13	0.100
Link: Lot 6 BMP T5.13	0.100
<b>Total:</b>	<b>354.830</b>

**Total Predevelopment Recharge is Less than Post Developed**  
**Average Recharge Per Year, (Number of Years= 121)**  
**Predeveloped: 2.149 ac-ft/year, Post Developed: 2.932 ac-ft/year**

\*\*\*\*\*Water Quality Facility Data\*\*\*\*\*

-----SCENARIO: PREDEVELOPED

Number of Links: 0

-----SCENARIO: POSTDEVELOPED

Number of Links: 20

\*\*\*\*\* Link: POC \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.00 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.03  
Inflow Volume Including PPT-Evap (ac-ft): 0.03  
Total Runoff Infiltrated (ac-ft): 0.00, 0.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.03  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 0.00%

\*\*\*\*\* Link: Lot 1 - BMP T5.10C \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 18.74  
Inflow Volume Including PPT-Evap (ac-ft): 18.74  
Total Runoff Infiltrated (ac-ft): 18.74, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 2 - BMP T5.10C \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 18.74  
Inflow Volume Including PPT-Evap (ac-ft): 18.74  
Total Runoff Infiltrated (ac-ft): 18.74, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 3 - BMP T5.10C \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs



Infiltration/Filtration Statistics-----  
Inflow Volume (ac-ft): 18.74  
Inflow Volume Including PPT-Evap (ac-ft): 18.74  
Total Runoff Infiltrated (ac-ft): 18.74, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 4 - BMP T5.10C \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----  
Inflow Volume (ac-ft): 18.81  
Inflow Volume Including PPT-Evap (ac-ft): 18.81  
Total Runoff Infiltrated (ac-ft): 18.81, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 5 - BMP T5.10C \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----  
Inflow Volume (ac-ft): 18.81  
Inflow Volume Including PPT-Evap (ac-ft): 18.81  
Total Runoff Infiltrated (ac-ft): 18.81, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 5 CAVFS \*\*\*\*\*

2-Year Discharge Rate : 0.004 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----  
Inflow Volume (ac-ft): 19.15  
Inflow Volume Including PPT-Evap (ac-ft): 20.41  
Total Runoff Infiltrated (ac-ft): 20.34, 99.69%  
Total Runoff Filtered (ac-ft): 0.01, 0.03%  
Primary Outflow To Downstream System (ac-ft): 0.08  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 99.72%

\*\*\*\*\* Link: Lot 4 CAVFS \*\*\*\*\*

2-Year Discharge Rate : 0.004 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge

On-line Design Discharge Rate (91% Exceedance): 0.01 cfs

Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 19.15

Inflow Volume Including PPT-Evap (ac-ft): 20.41

Total Runoff Infiltrated (ac-ft): 20.34, 99.69%

Total Runoff Filtered (ac-ft): 0.01, 0.03%

Primary Outflow To Downstream System (ac-ft): 0.08

Secondary Outflow To Downstream System (ac-ft): 0.00

Volume Lost to ET (ac-ft): 0.00

Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 99.72%

\*\*\*\*\* Link: Lot 3 CAVFS

\*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge

On-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 4.68

Inflow Volume Including PPT-Evap (ac-ft): 5.05

Total Runoff Infiltrated (ac-ft): 5.05, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.02%

Primary Outflow To Downstream System (ac-ft): 0.01

Secondary Outflow To Downstream System (ac-ft): 0.00

Volume Lost to ET (ac-ft): 0.00

Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 99.91%

\*\*\*\*\* Link: Lot 2 CAVFS

\*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge

On-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 4.68

Inflow Volume Including PPT-Evap (ac-ft): 5.05

Total Runoff Infiltrated (ac-ft): 5.05, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.02%

Primary Outflow To Downstream System (ac-ft): 0.01

Secondary Outflow To Downstream System (ac-ft): 0.00

Volume Lost to ET (ac-ft): 0.00

Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 99.91%

\*\*\*\*\* Link: Lot 1 CAVFS

\*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge

On-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 4.68

Inflow Volume Including PPT-Evap (ac-ft): 5.05

Total Runoff Infiltrated (ac-ft): 5.05, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.02%

Primary Outflow To Downstream System (ac-ft): 0.01

Secondary Outflow To Downstream System (ac-ft): 0.00

Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 99.91%

\*\*\*\*\* Link: ROW CAVFS \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 15.75  
Inflow Volume Including PPT-Evap (ac-ft): 18.51  
Total Runoff Infiltrated (ac-ft): 18.52, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.01%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.05%

\*\*\*\*\* Link: Lot 6 CAVFS \*\*\*\*\*

2-Year Discharge Rate : 0.002 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 18.73  
Inflow Volume Including PPT-Evap (ac-ft): 19.98  
Total Runoff Infiltrated (ac-ft): 19.93, 99.71%  
Total Runoff Filtered (ac-ft): 0.01, 0.03%  
Primary Outflow To Downstream System (ac-ft): 0.07  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 99.74%

\*\*\*\*\* Link: Lot 6 - BMP T5.10C \*\*\*\*\*

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 19.22  
Inflow Volume Including PPT-Evap (ac-ft): 19.22  
Total Runoff Infiltrated (ac-ft): 19.22, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 1 BMP T5.13 \*\*\*\*\*

Basic Wet Pond Volume (91% Exceedance): 65. cu-ft  
Computed Large Wet Pond Volume, 1.5\*Basic Volume: 98. cu-ft

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.13  
Inflow Volume Including PPT-Evap (ac-ft): 0.13  
Total Runoff Infiltrated (ac-ft): 0.13, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 2 BMP T5.13 \*\*\*\*\*

Basic Wet Pond Volume (91% Exceedance): 66. cu-ft  
Computed Large Wet Pond Volume, 1.5\*Basic Volume: 99. cu-ft

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.13  
Inflow Volume Including PPT-Evap (ac-ft): 0.13  
Total Runoff Infiltrated (ac-ft): 0.13, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 3 BMP T5.13 \*\*\*\*\*

Basic Wet Pond Volume (91% Exceedance): 66. cu-ft  
Computed Large Wet Pond Volume, 1.5\*Basic Volume: 99. cu-ft

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.13  
Inflow Volume Including PPT-Evap (ac-ft): 0.13  
Total Runoff Infiltrated (ac-ft): 0.13, 100.00%  
Total Runoff Filtered (ac-ft): 0.00, 0.00%  
Primary Outflow To Downstream System (ac-ft): 0.00  
Secondary Outflow To Downstream System (ac-ft): 0.00  
Volume Lost to ET (ac-ft): 0.00  
Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 4 BMP T5.13 \*\*\*\*\*

Basic Wet Pond Volume (91% Exceedance): 53. cu-ft  
Computed Large Wet Pond Volume, 1.5\*Basic Volume: 80. cu-ft

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.10  
Inflow Volume Including PPT-Evap (ac-ft): 0.10  
Total Runoff Infiltrated (ac-ft): 0.10, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.00%  
 Primary Outflow To Downstream System (ac-ft): 0.00  
 Secondary Outflow To Downstream System (ac-ft): 0.00  
 Volume Lost to ET (ac-ft): 0.00  
 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 5 BMP T5.13 \*\*\*\*\*

Basic Wet Pond Volume (91% Exceedance): 51. cu-ft  
 Computed Large Wet Pond Volume, 1.5\*Basic Volume: 76. cu-ft

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
 On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
 Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.10  
 Inflow Volume Including PPT-Evap (ac-ft): 0.10  
 Total Runoff Infiltrated (ac-ft): 0.10, 100.00%  
 Total Runoff Filtered (ac-ft): 0.00, 0.00%  
 Primary Outflow To Downstream System (ac-ft): 0.00  
 Secondary Outflow To Downstream System (ac-ft): 0.00  
 Volume Lost to ET (ac-ft): 0.00  
 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\* Link: Lot 6 BMP T5.13 \*\*\*\*\*

Basic Wet Pond Volume (91% Exceedance): 51. cu-ft  
 Computed Large Wet Pond Volume, 1.5\*Basic Volume: 76. cu-ft

2-Year Discharge Rate : 0.000 cfs

15-Minute Timestep, Water Quality Treatment Design Discharge  
 On-line Design Discharge Rate (91% Exceedance): 0.01 cfs  
 Off-line Design Discharge Rate (91% Exceedance): 0.00 cfs

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 0.10  
 Inflow Volume Including PPT-Evap (ac-ft): 0.10  
 Total Runoff Infiltrated (ac-ft): 0.10, 100.00%  
 Total Runoff Filtered (ac-ft): 0.00, 0.00%  
 Primary Outflow To Downstream System (ac-ft): 0.00  
 Secondary Outflow To Downstream System (ac-ft): 0.00  
 Volume Lost to ET (ac-ft): 0.00  
 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\***Compliance Point Results**\*\*\*\*\*

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: POC

\*\*\* **Point of Compliance Flow Frequency Data** \*\*\*

Recurrence Interval Computed Using Gringorten Plotting Position

Predevelopment Runoff Tr (Years)	Discharge (cfs)	Postdevelopment Runoff Tr (Years)	Discharge (cfs)
2-Year	7.236E-04	2-Year	1.985E-04
5-Year	7.470E-04	5-Year	8.005E-04
10-Year	2.003E-03	10-Year	1.390E-03
25-Year	1.190E-02	25-Year	2.750E-03
50-Year	1.563E-02	50-Year	5.938E-03
100-Year	2.095E-02	100-Year	1.547E-02
200-Year	3.038E-02	200-Year	3.410E-02
500-Year	4.285E-02	500-Year	5.874E-02

\*\*\*\* **Flow Duration Performance** \*\*\*\*

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	-93.4%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	-82.8%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):	-20.5%	PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

-----  
MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS  
-----


\*\*\*\* **LID Duration Performance** \*\*\*\*

Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	-99.7%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	-93.4%	PASS

-----  
MEETS ALL LID DURATION DESIGN CRITERIA: PASS  
-----




**Predeveloped**







**APPENDIX D: BMP DETAILS**



**Figure V-7.1: Example of a Compost Amended Vegetated Filter Strip (CAVFS)**




**Figure V-5.5: Schematic of an Infiltration Trench**



### Schematic of an Infiltration Trench

Revised May 2019

**Figure V-11.1: Planting Bed Cross-Section**



Reprinted from *Guidelines and Resources For Implementing Soil Quality and Depth BMP T5.13 in WDOE Stormwater Management Manual for Western Washington*, 2010, Washington Organic Recycling Council

NOT TO SCALE



## Planting Bed Cross-Section

Revised June 2016

Please see <http://www.ecy.wa.gov/copyright.html> for copyright notice including permissions, limitation of liability, and disclaimer.