# PRELIMINARY STORMWATER REPORT

## GOERIG APARTMENTS

**TAXLOT NOS.: 50630** 

PROPERTY ADDRESS: 1776 N. GOERIG ST, WOODLAND, WA 98674

#### June 24, 2022

REVISION LOG				
MARK	MARK DATE DESCRIPTION			
Α	6/24/2022	Issued for review.		

#### PREPARED FOR:

AIDAN WILLIS 4201 NE 66<sup>th</sup> AVE. #105, VANCOUVER, WA 98661 AWILLIS@TEAMCONSTRUCTION.COM 503.957.0966

#### **PREPARED BY:**

JOLMA DESIGN, LLC PO BOX 1281 BATTLE GROUND, WA 98604 ADMIN@JOLMADESIGN.COM 360.723.0392



# PRELIMINARY STORMWATER REPORT

## GOERIG APARTMENTS

THE MATERIAL AND DATA IN THIS REPORT WERE PREPARED UNDER THE SUPERVISION AND DIRECTION OF THE UNDERSIGNED.

## JOLMA DESIGN, LLC

**Engineer's Statement of Completeness and Feasibility:** I, the undersigned, do hereby state that, to the best of my knowledge, all information required by City of Woodland 15.12 Stormwater Management Code is included in the Preliminary Stormwater Plan and that the proposed stormwater facilities are feasible.



DAVID G. SPENCER, PE CIVIL ENGINEER

# CONTENTS

СО	NTENTS		i
А	VICINITY	MAPS	1
B B.1	Site	TOVERVIEW Information te Location	2
		kisting Conditions	
B.2	Prop	posed Development	2
В.З	Stor	mwater Management Overview	2
B.4	Stor	mwater Minimum Requirements	3
С		ATER MINIMUM REQUIREMENTS	
C.1		#1—Preparation of Stormwater Site Plans	
C.2		#2—Construction Stormwater Pollution Prevention	
C.3 C.4		#3—Source Control of Pollution #4—Preservation of Natural Drainage System and Outfalls	
C.4		#4—reservation of National Dialinage system and Outraits #5—Onsite Stormwater Management BMPs	
C.6		#6—Runoff Treatment	
C.7		#7—Flow Control	
C.8	MR	#8—Wetlands Protection	7
C.9	MR	#9—Operation and Maintenance	7
D	MGSFLO	OD METHODOLOGY	7
D.1	Ger	neral Information	7
D.2	Sce D.2.1	nario Predeveloped	
	D.2.2	Postdeveloped	8

## FIGURES & DRAWINGS

APPENDIX A

· · · · <u>-</u> · · <u>-</u> · · · · · · · · · · · · · · · · · · ·	MGSFLOOD RESULTS
APPENDIX B	INFILTRATION TEST RESULTS
APPENDIX C	
APPENDIX D	SWPPP
	SOIL REPORT

# A VICINITY MAPS



## **B PROJECT OVERVIEW**

## **B.1 Site Information**

## **B.1.1** Site Location

The project site is comprised of one existing tax lot totaling approximately 0.89 acres located at 1776 N. Goerig St, Woodland, WA 98674. The parcel number is 50630 and is legally described as Section 13, Township 5N, Range 1W, Willamette Meridian. The property is zoned as High Density Residential (HDR).

## **B.1.2** Existing Conditions

Existing conditions include an approximately 4,000 sf shop, a shed, and a gravel driveway. A sea wall extends across most of the site boundary to N. Goerig St. Existing access to site is from Scott Ave.

Description	Location	Approximate Area (sf)	Remarks
Existing Roofs	Southwest corner of site	4,153	
Existing Access Road	Site-wide	5,129	
Impervious Subtotal		9,282 sf (0.213 ac)	
Landscaping/Lawn		21,196	
Pervious Subtotal		29,486 sf (0.677 ac)	
Project Site Total		38,768 sf (0.89 ac)	

Table 1: Existing Site Conditions

## **B.2** Proposed Development

The project will add two 3-story apartment buildings. Building A will be a 27-unit building consisting of a mix of 1, 2, and 3-bedroom units, and Building B will consist of six 2-bedroom units.

There will be frontage half-street improvements along Scott Ave and N. Goerig St.

## **B.3 Stormwater Management Overview**

This report and the associated stormwater management design applies to areas where right-ofway and onsite improvements are proposed (Project Site). The on-site stormwater is comprised of three catchment areas managed by three infiltration trenches and two stormfilter catch basins. The stormwater within the right-of-way is comprised of two catchment areas managed by two bioretention facilities.

The catchment runoff will be fully managed (treatment and detention) via a combination of infiltration trenches, stormfilters, and bioretention.

## **B.4** Stormwater Minimum Requirements

The project site is subject to the evaluation of Minimum Requirements (MR) numbers 1 through 9. Table 1 summarizes the proposed project site conditions; Table 2 includes information used to determine applicable stormwater minimum requirements.

Surface Type	Area (sf)	Remarks
Roofs (Existing + New)	8,000	
Road & Drive Aisle, and Parking Areas	24,307	
Sidewalks	5,244	
Pervious (Perimeter & Interior Landscaping)	12,119	
Impervious Subtotal	37,551 sf (0.86 ac)	
Pervious Subtotal	12,119 sf (0.28 ac)	
Project Site Total	49,670 sf (1.14 ac)	


#### Table 2: Post-Developed Project Site Conditions

#### Table 3: Project Site Parameters Used to Determine Applicable Minimum Requirements

Description	Value	Remarks
Project Site Area	49,670 sf (1.14 ac)	Includes on- and offsite areas where land-disturbing activity is proposed.
Existing Impervious Surface Area	O sf	Existing impervious surface treated as new surface.
Existing Impervious Surface Coverage	0%	
New Impervious Surface Area	37,551 sf (0.86 ac)	
Replaced Impervious Area	0 sf	
New + Replaced Impervious Area	37,551 sf (0.86 ac)	
Converted Pervious: Native Vegetation Converted to Lawn or Landscape	O sf	
Converted Pervious: Native Vegetation Converted to Pasture	O sf	
Pollution-Generating Impervious Surface (PGIS)	24,307 sf	
Non-Pollution Generating Impervious Surface (NPGIS)	13,244 sf	
Pollution-Generating Pervious Surface	0	
Total Pollution-Generating Surface Area	24,307 sf	
Total Area Subject to Land-Disturbing Activities	49,670 sf (1.14 ac)	

Exhibit 1 was used to evaluate applicable minimum requirements based on site parameters.

Exhibit 1: New Development Flow Chart



## **C** STORMWATER MINIMUM REQUIREMENTS

Following is a discussion regarding applicable Minimum Requirements and how each will be addressed.

## C.1 MR #1—Preparation of Stormwater Site Plans

The project will add more than 2,000 sf of new impervious surface; therefore, a stormwater site plan following the City guidelines for "Large and Engineered Projects" is required. This Technical Information Report (TIR) along with pertinent drawings, exhibits, and technical documents associated with this project collectively comprise the Stormwater Site Plan.

## C.2 MR #2—Construction Stormwater Pollution Prevention

A Construction Stormwater Pollution Prevention Plan (SWPPP) is required and will be submitted in the appendix of this report.

## C.3 MR #3—Source Control of Pollution

New development shall comply with the requirements of Volume IV of the Stormwater management Manual for Western Washington (SMMWW). The source control Best Management Practices (BMPs) that may apply to this project are outlined below:

- S407—BMPs for Dust Control at Disturbed Land Areas and Unpaved Roadways and Parking Lots
- > S411—BMPs for Landscaping and Lawn/Vegetation Maintenance
- > S417—BMPs for Maintenance of Stormwater Drainage and Treatment Facilities


Additional BMPs may be required depending on the specific activities taking place on site.

## C.4 MR #4—Preservation of Natural Drainage System and Outfalls

Natural drainage patterns will be maintained to the extent practicable. The entire project site generally flows toward the southeast and after development, stormwater will be routed to that same location.

## C.5 MR #5—Onsite Stormwater Management BMPs

Because the project will add more than 2,000 sf of new impervious surface, it is subject to MR #5, which requires the use of onsite stormwater management BMPs.



## C.6 MR #6—Runoff Treatment

The project will add more than 5,000 sf of new pollution-generating hard surface area within a threshold discharge area and is therefore subject to MR #6. Runoff from PGIS areas will be treated within the stormfilter catch basins (on-site) and bioretention (off-site). PGIS runoff and runoff from other surfaces that mixes with PGIS runoff will be treated.

## C.7 MR #7—Flow Control

More than 10,000 sf of new effective impervious surface is proposed; therefore, the project must comply with MR #7. Infiltration trenches and bioretention will be used to comply with the flow control standard. Infiltration testing was performed, and results used to determine the design infiltration rate for soils. See attached infiltration test results, MGSFlood calculations, and additional details in Appendixes A and B.

## C.8 MR #8—Wetlands Protection

The project does not propose any discharge of stormwater directly or indirectly into a wetland; therefore, MR #8 does not apply.

## C.9 MR #9—Operation and Maintenance

All stormwater systems will be privately owned, operated, and maintained. Final Operation and Maintenance guidelines are submitted in Appendix C of this report within the SWPPP.

## D MGSFLOOD METHODOLOGY

The Washington State Department of Ecology (DOE) requires flow control BMPs be designed using a calibrated continuous simulation hydrologic model based on the Environmental Protection Agency's HSPF (Hydrologic Simulation Program-Fortran) program. DOE has approved three continuous runoff models: Western Washington Hydrology Model (WWHM); KCRTS (King County Runoff Time Series); and MGSFlood, a program used by the Washington State Department of Transportation. JD elected to use MGSFlood because of its faster processing time, particularly with complex hydrologic models. The purpose of this section is to provide an overview of the methodology used to develop the Project Site MGSFlood hydrologic model.

## D.1 General Information

The project site is located at 1776 N Goerig St. Based upon coordinates the Mean Annual Precipitation (MAP) was computed as 48.7 inches. The project site is within one threshold discharge area with a single point of compliance (POC).

## D.2 Scenario


## **D.2.1** Predeveloped

The Project Site was modeled as a single 1.14-acre flat, forested subbasin (PD-1) with Soil Group (SG) 3 soils. See MGSFlood modeling results in Appendix A.

#### **D.2.2** Postdeveloped

The primary objective of the preliminary hydrologic model was to demonstrate postdeveloped stormwater runoff can be feasibly managed. The Project Site was modeled to reflect the postdeveloped condition as accurately as possible. Appendix A contains detailed MGSFlood model parameters (subcatchment areas, storm facility dimensions, etc.) and analysis results. Exhibit 3 illustrates the postdeveloped schematic objects used in the model.

#### Exhibit 3: Postdeveloped MGSFlood Schematic



Mark	Element Type	Area Modeled/ Managed	Modeled As	Discharge Point	Area (ac)	Remarks
NPGHS-1 On-site	Subbasin	Sidewalk	Impervious Flat	IT-01	0.0664	
NPGHS-2 On-site	Subbasin	Roof, Sidewalk	Impervious Flat	IT-02	0.0396	
NPGHS-3 On-site	Subbasin	Roof	Impervious Flat	IT-03	0.1442	
PGHS-1 On-site	Subbasin	Parking Lot	Pavement/ Flat	IT-01	0.2369	

#### Table 3: WWHM Mitigated Scenario Methodology

Mark	Element Type	Area Modeled/ Managed	Modeled As	Discharge Point	Area (ac)	Remarks
PGHS-2	Subbasin	Parking Lot	Pavement/	IT-02	0.1383	
On-site	30000311		Flat	11-02	0.1000	
PGHS-3	Subbasin	Scott Ave	Pavement/	BIO-01	0.1465	
On-site	20000211	SCOILAVE	Flat		0.1465	
PGHS-4	Subbasin	Goerig St	Pavement/	BIO-02	0.1076	
On-site	30000311	Goeng Si	Flat	BIO-02	0.1076	
LAWN-1	Subbasin	Landscape	SG3 Lawn,	IT-01	0.0607	
On-site	30000311	Lanascape	Flat	11-01	0.0007	
LAWN-2	Subbasin	Landscape	SG3 Lawn,	IT-02	0.0622	
On-site	300000311	Lanascape	Flat 11-02 0.0022			
LAWN-3	Subbasin	Landscape	SG3 Lawn,	IT-03	0.0844	
On-site	00000000	Lanascapo	Flat	11 00	0.0044	
LAWN-4	Subbasin	Landscape	SG3 Lawn,	BIO-02	0.0455	
On-site	00000311	Lanascapo	Flat	DIC 02	0.0-00	
	<u> </u>	1	TOTAL AREA	REPRESENTED	1.14	

FIGURES & DRAWINGS

# APPENDIX A

**MGSFLOOD RESULTS** 


## MGS FLOOD PROJECT REPORT

Program Version: MGSFlood 4.55 Program License Number: 202010005 Project Simulation Performed on: 05/23/2022 3:48 PM Report Generation Date: 05/23/2022 3:48 PM

Input File Name: 22046_Analysis.fld Project Name: GoerigApartments Analysis Title: 22046_Analysis Comments:
PRECIPITATION INPUT
Computational Time Step (Minutes): 5
Extended Precipitation Time Series Selected Climatic Region Number: 26
Full Period of Record Available used for RoutingPrecipitation Station :97004805 Vancouver 48 in_5min 10/01/1939-10/01/2060Evaporation Station :971048 Vancouver 48 in MAPEvaporation Scale Factor :0.750
HSPF Parameter Region Number: 2 HSPF Parameter Region Name : Clark County
********* Default HSPF Parameters Used (Not Modified by User) ************************************
**************************** WATERSHED DEFINITION ************************************
Predevelopment/Post Development Tributary Area Summary Predeveloped Post Developed

	Predeveloped	Post Developed
Total Subbasin Area (acres)	1.140	1.131
Area of Links that Include Precip/Evap (acres)	0.000	0.009
Total (acres)	1.140	1.140

-----SCENARIO: PREDEVELOPED Number of Subbasins: 1



------ Subbasin : PGHS-2 -----------Area (Acres) ------Impervious Flat 0.138 ------Subbasin Total 0.138 ----- Subbasin : NPHGS-2 -----------Area (Acres) ------Impervious Flat 0.038 -----Subbasin Total 0.038 ------ Subbasin : NPGHS-3 -----------Area (Acres) ------Impervious Flat 0.141 Subbasin Total 0.141 ------ Subbasin : LAWN-1 -----------Area (Acres) ------Clark Co. SG3, Lawn, 0.061 \_\_\_\_\_ Subbasin Total 0.061 ------ Subbasin : LAWN-2 -----------Area (Acres) ------Clark Co. SG3, Lawn, 0.062 \_\_\_\_\_ Subbasin Total 0.062 ------ Subbasin : PGHS-3 -----------Area (Acres) ------Impervious Flat 0.147 Subbasin Total 0.147 ------ Subbasin : PGHS-4 -----------Area (Acres) ------Impervious Flat 0.108 \_\_\_\_\_ Subbasin Total 0.108 ----- Subbasin : LAWN-4 -----------Area (Acres) ------Clark Co. SG3, Lawn, 0.046 \_\_\_\_\_ Subbasin Total 0.046

------ Subbasin : LAWN-3 ------------Area (Acres) ------Clark Co. SG3, Lawn, 0.087 -------Subbasin Total 0.087

#### 

-----SCENARIO: PREDEVELOPED Number of Links: 1

Link Name: Predeveloped-POC Link Type: Copy Downstream Link: None

\_\_\_\_\_

-----SCENARIO: POSTDEVELOPED Number of Links: 6

Link Name: Postdeveloped-POC Link Type: Copy Downstream Link: None

\_\_\_\_\_

Link Name: IT-01

Link Type: Infiltration Trench Downstream Link Name: Postdeveloped-POC

Trench Type	: Trench at Toe of Embankment
Trench Length (ft)	: 45.00
Trench Width (ft)	: 5.00
Trench Depth (ft)	: 3.00
Trench Bottom Elev (ft)	: 100.00
Trench Rockfill Porosity (%)	: 30.00

Constant Infiltration Option Used Infiltration Rate (in/hr): 20.00

-----

Link Name: IT-02 Link Type: Infiltration Trench Downstream Link Name: Postdeveloped-POC

Trench Type

: Trench at Toe of Embankment

Constant Infiltration Option Used Infiltration Rate (in/hr): 20.00

-----

Link Name: IT-03 Link Type: Infiltration Trench Downstream Link Name: Postdeveloped-POC

Trench Type	: Trench at Toe of Embankment
Trench Length (ft)	: 30.00
Trench Width (ft)	: 3.00
Trench Depth (ft)	: 3.00
Trench Bottom Elev (ft)	: 100.00
Trench Rockfill Porosity (%)	: 30.00

Constant Infiltration Option Used Infiltration Rate (in/hr): 20.00

-----

Link Name: BIO-01

Link Type: Ecology Bioretention Facility Downstream Link Name: Postdeveloped-POC

Floor Elevation (ft)	:	100.00			
Riser Crest Elevation (ft)		:	100.50		
Storage Depth (ft)	:	0.50			
Bottom Length (ft)	:	65.0			
Bottom Width (ft)	:	3.0			
Bottom Slope (ft/ft)	:	0.000			
Side Slopes (ft/ft)	: L	1= 0.00	L2= 0.00	W1= 0.00	W2= 0.00
Bottom Area (sq-ft)	:	195.			
Area at Riser Crest El (sq-ft)	:	195.			
(acres)	:	0.004			
Volume at Riser Crest (cu-ft)	:	98.			
(ac-ft)	:	0.002			

Infiltration on Bottom and Sideslopes Selected

Soil PropertiesThickness (ft)1 ASTM 1000.2502 SMMWW 12 in/hr (Ecol1.5003 GRAVEL2.000KSat Safety Factor: None20.00Native Soil Infiltration Rate (in/hr):20.00

Underdrain Not Present

**Riser Geometry** Riser Structure Type : Circular Riser Diameter (in) : 6.00 Common Length (ft) : 0.000 Riser Crest Elevation : 100.50 ft Hydraulic Structure Geometry Number of Devices: 0 Link Name: BIO-02 Link Type: Ecology Bioretention Facility Downstream Link Name: Postdeveloped-POC Floor Elevation (ft) : 100.00 Riser Crest Elevation (ft) : 100.50 Storage Depth (ft) : 0.50 Bottom Length (ft) 65.0 . Bottom Width (ft) 3.0 : Bottom Slope (ft/ft) 0.000 : Side Slopes (ft/ft) : L1= 0.00 L2= 0.00 W1= 0.00 W2= 0.00 Bottom Area (sq-ft) 195. : Area at Riser Crest El (sq-ft) : 195. 0.004 (acres) : Volume at Riser Crest (cu-ft) 98. : (ac-ft) : 0.002 Infiltration on Bottom and Sideslopes Selected Soil Properties Layer No Soil Name Thickness (ft) 1 ASTM 100 0.250 2 SMMWW 12 in/hr (Ecol 1.500 3 GRAVEL 2.000 KSat Safety Factor: None Native Soil Infiltration Rate (in/hr) : 20.00 Underdrain Not Present **Riser Geometry** Riser Structure Type : Circular Riser Diameter (in) : 6.00 Common Length (ft) : 0.000 : 100.50 ft Riser Crest Elevation Hydraulic Structure Geometry Number of Devices: 0 \*FLOOD FREQUENCY AND DURATION STATISTICS\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

#### -----SCENARIO: PREDEVELOPED

Number of Subbasins: 1 Number of Links: 1

#### \*\*\*\*\*\*\*\*\*\* Subbasin: PD-1 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

2-Year	3.762E-02
5-Year	6.314E-02
10-Year	9.605E-02
25-Year 50-Year	9.005E-02 0.144 0.178
100-Year	0.235
200-Year	0.339
500-Year	0.477

 100-Year
 0.235

 200-Year
 0.339

 500-Year
 0.477

-----SCENARIO: POSTDEVELOPED Number of Subbasins: 11

Number of Links: 6

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: PGHS-1 \*\*\*\*\*\*\*\*\*\*\*

5-Year	0.178
10-Year	0.202
25-Year	0.248
50-Year	0.330
100-Year	0.376
200-Year	0.407
500-Year	0.448

\*\*\*\*\*\*\*\*\* Link Inflow

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: NPGHS-1 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs)

(Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

2-Year 3.550E-02 5-Year 4.981E-02

5-real	4.9010-02
10-Year	5.658E-02
25-Year	6.951E-02
50-Year	9.243E-02
100-Year	0.105
200-Year	0.114
500-Year	0.125

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: PGHS-2 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs)

(Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

\_\_\_\_\_

2-Year	7.395E-02
5-Year	0.104
10-Year	0.118
25-Year	0.145
50-Year	0.193
100-Year	0.219
200-Year	0.237
500-Year	0.261

#### \*\*\*\*\*\*\*\*\*\* Subbasin: NPHGS-2 \*\*\*\*\*\*\*\*\*\*

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: NPGHS-3 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs)

(Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

2-Year	7.561E-02
5-Year	0.106
10-Year	0.120
25-Year	0.148
50-Year	0.197
100-Year	0.224
200-Year	0.243
500-Year	0.267

#### \*\*\*\*\*\*\*\*\*\* Subbasin: LAWN-1 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

=============	
2-Year	5.500E-03
5-Year	1.134E-02
10-Year	1.474E-02
25-Year	1.938E-02
50-Year	2.591E-02
100-Year	2.865E-02
200-Year	3.218E-02
500-Year	3.685E-02

#### \*\*\*\*\*\*\*\*\*\* Subbasin: LAWN-2 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

2-Year 5-Year 10-Year	5.654E-03 1.166E-02 1.515E-02
25-Year	1.993E-02
50-Year	2.664E-02
100-Year	2.945E-02
200-Year	3.308E-02
500-Year	3.789E-02

#### \*\*\*\*\*\*\*\*\*\* Subbasin: PGHS-3 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

2-Year	7.833E-02
5-Year	0.110
10-Year	0.125
25-Year	0.153
50-Year	0.204
100-Year	0.232
200-Year	0.251
500-Year	0.277

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: PGHS-4 \*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs)

(Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

2-Year	5.753E-02	
5-Year	8.071E-02	
10-Year	9.168E-02	
25-Year	0.113	
50-Year	0.150	
100-Year	0.171	
200-Year	0.185	
500-Year	0.203	

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: LAWN-4 \*\*\*\*\*\*\*\*\*\*\*

Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs)

\_\_\_\_\_

2-Year 5-Year	4.122E-03 8.501E-03
10-Year	1.105E-02
25-Year	1.453E-02
50-Year	1.942E-02
100-Year	2.147E-02
200-Year	2.412E-02
500-Year	2.763E-02

#### \*\*\*\*\*\*\*\*\*\*\* Subbasin: LAWN-3 \*\*\*\*\*\*\*\*\*\*\*

2-1 cai	7.9012-03	
5-Year	1.629E-02	
10-Year	2.117E-02	
25-Year	2.785E-02	
50-Year	3.722E-02	
100-Year	4.115E-02	
200-Year	4.623E-02	
500-Year	5.294E-02	

\*\*\*\*\*\*\*\*\* Link: Postdeveloped-POC Frequency Stats Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs) \*\*\*\*\*\*\*\*\* Link Inflow


9.526E-06
2.099E-05
3.051E-05
4.128E-05
6.187E-02
0.266
0.289
0.318

********** Link:	: IT-01 *********	Link Inflow Frequency Stats
	ency Data(cfs)	
•		Using Gringorten Plotting Position)
Tr (yrs)	Flood Peak (cfs)	
==========		
2-Year	0.169	
5-Year	0.234	
10-Year	0.263	
25-Year	0.342	
50-Year	0.424	
100-Year	0.495	
200-Year	0.523	
500-Year	0.560	

********** Link: IT-01 *********	Link Outflow 1 Frequency Stats
Flood Frequency Data(cfs)	
(Recurrence Interval Computed	Using Gringorten Plotting Position)
Tr (yrs) Flood Peak (cfs)	
=======================================	

100-Year 200-Year 0.295 0.305

********** Link	: IT-02 *********	Link Inflow Frequency Stats
Flood Freque	ency Data(cfs)	
		Using Gringorten Plotting Position)
Tr (yrs)	Flood Peak (cfs)	
===========	=======================================	=============
2-Year	0.101	
5-Year	0.137	
10-Year	0.158	
25-Year	0.202	
50-Year	0.248	

500-Year 0.319

\*\*\*\*\*\*\*\*\* Link: IT-02 \*\*\*\*\*\*\*\*
Link Outflow 1 Frequency Stats
Flood Frequency Data(cfs)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs)
Flood Peak (cfs)


2-Year	2.444E-06
5-Year	5.700E-06
10-Year	8.275E-06
25-Year	1.103E-05
50-Year	5.561E-03
100-Year	5.322E-02
200-Year	6.273E-02
500-Year	7.530E-02

2-Year	8.221E-02	
5-Year	0.115	
10-Year	0.137	
25-Year	0.168	
50-Year	0.202	
100-Year	0.245	
200-Year	0.246	
500-Year	0.248	

5-Year	6.683E-06	
10-Year	1.012E-05	
25-Year	1.209E-05	
50-Year	3.818E-02	
100-Year	5.872E-02	
200-Year	9.279E-02	
500-Year	0.138	

\*\*\*\*\*\*\*\*\*\* Link: BIO-01 Frequency Stats Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) \*\*\*\*\*\*\*\*\* Link Inflow

Tr (yr	s)	Flood Peak	(cfs)	
--------	----	------------	-------	--

==========	=======================================
2-Year	7.833E-02
5-Year	0.110
10-Year	0.125
25-Year	0.153
50-Year	0.204
100-Year	0.232
200-Year	0.251
500-Year	0.277

\*\*\*\*\*\*\*\*\*\*\* Link: BIO-01 \*\*\*\*\*\* Link Outflow 1 **Frequency Stats** Flood Frequency Data(cfs) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) Flood Peak (cfs) \_\_\_\_\_ 2-Year 5.134E-07 5-Year 1.713E-06 10-Year 2.488E-06 25-Year 3.682E-06 50-Year 2.213E-02 100-Year 6.225E-02 200-Year 0.103 500-Year 0.157

\*\*\*\*\*\*\*\*\*\*\* Link: BIO-01

\*\*\*\*\*\*\*\*\*\* Link WSEL

Stats

WSEL Frequency Data(ft) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) WSEL Peak (ft)

1.05-Year	100.009
1.11-Year	100.010
1.25-Year	100.011
2.00-Year	100.051
3.33-Year	100.115
5-Year	100.171
10-Year	100.249
25-Year	100.368
50-Year	100.525
100-Year	100.551

2-Year 6.225E-02

\*\*\*\*\*\*\*\*\* Link Inflow

8.480E-02
9.834E-02
0.124
0.151
0.181
0.187
0.193

\*\*\*\*\*\*\*\*\*\* Link: BIO-02

\*\*\*\*\*\*\*\*\*\* Link WSEL

Stats WSEL Frequency Data(ft) (Recurrence Interval Computed Using Gringorten Plotting Position) Tr (yrs) WSEL Peak (ft)

1.05-Year	100.007
1.11-Year	100.007
1.25-Year	100.009
2.00-Year	100.012
3.33-Year	100.036
5-Year	100.059
10-Year	100.133
25-Year	100.229
50-Year	100.311
100-Year	100.417

#### \*\*\*\*\*\*\*\*\*Groundwater Recharge Summary \*\*\*\*\*\*\*\*\*\*\*\*

Recharge is computed as input to PerInd Groundwater Plus Infiltration in Structures

Model E	Total Predevelo Element	oped Recharge During Simulation Recharge Amount (ac-ft)				
	in: PD-1 Predeveloped-POC	190.326 0.000				
Total:		190.326				

Model El	TOLAL FUSL DEVELOP	oed Rech	arge D	uring Simu	lation
				ge Ämount	
Subbooir			0.000		
	า: PGHS-1 า: NPGHS-1		0.000 0.000		
	n: PGHS-2		0.000		
	n: NPHGS-2		0.000		
	n: NPGHS-3		0.000		
	n: LAWN-1		8.917		
Subbasir	n: LAWN-2		9.166		
Subbasir	n: PGHS-3		0.000		
Subbasir	n: PGHS-4		0.000		
	n: LAWN-4		6.684		
	n: LAWN-3		12.809		
	Postdeveloped-POC		0.000		
Link:	IT-01	139.303	3		
	IT-02	85.531			
Link:		74.752			
Link:		62.689			
Link:	BIO-02	53.633			
Total:				453.485	
Average	edevelopment Rechar Recharge Per Year, ( loped: 1.573 ac-ft/y	Number	of Yea	rs= 121)	
*******	**Water Quality Facili	ity Data	*******	****	
		-			
	SCENARIO: P	-			
	SCENARIO: P of Links: 1	-			
		-			
Number	of Links: 1	REDEVE			
Number		REDEVE			
Number	of Links: 1	REDEVE	ELOPEI		
Number	of Links: 1 Link: Predeveloped-P(	REDEVE	ELOPEI		
Number	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics	REDEVE	ELOPEI	D	
Number	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft):	<b>REDEVE</b> OC Evap (ac- 0.00, 0	<b>ELOPEI</b>  ft): 10 0.00%	D	
Number	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0	<b>REDEVE</b> OC Evap (ac- 0.00, (0) 0.00, 0.0	ft): 10 .00%	<b>D</b> 3.89	
Number ********** Infiltratio Inflow V Inflow V Total Ru Total Ru Primary	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0 Outflow To Downstrea	<b>REDEVE</b> OC Evap (ac- 0.00, 0.0 0.00, 0.0	ft): 10 .00% m (ac-ft	<b>)</b> 3.89 2): 103.89	
Number ********** Infiltratio Inflow V Inflow V Total Ru Total Ru Primary Second	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0 Outflow To Downstrea ary Outflow To Downst	REDEVE OC Evap (ac- 0.00, 0.0 0.00, 0.0 Im Syste ream Sy	ft): 10 .00% m (ac-ft	<b>)</b> 3.89 2): 103.89	)
Number ********* Infiltratio Inflow V Inflow V Total Ru Total Ru Primary Second Volume	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0 Outflow To Downstrea ary Outflow To Downstrea Lost to ET (ac-ft): 0.0	REDEVE DC Evap (ac- 0.00, 0 0.00, 0.0 m Syste ream Sy 00	ft): 10 .00% 0% m (ac-ft stem (a	<b>)</b> 3.89 c-ft): 0.00	
Number ********* Infiltratio Inflow V Inflow V Total Ru Total Ru Primary Second Volume	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0 Outflow To Downstrea ary Outflow To Downst	REDEVE DC Evap (ac- 0.00, 0 0.00, 0.0 m Syste ream Sy 00	ft): 10 .00% 0% m (ac-ft stem (a	<b>)</b> 3.89 c-ft): 0.00	
Number Infiltratio Inflow V Inflow V Total Ru Total Ru Primary Second Volume Percent	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0 Outflow To Downstrea ary Outflow To Downstrea Lost to ET (ac-ft): 0.0	REDEVE CC Evap (ac- 0.00, (0) 0.00, 0.0 m Syste rream Sy 00 ltered+E <sup>-</sup>	ft): 10  	<b>)</b> 3.89 :): 103.89 c-ft): 0.00 Volume: 0	
Number Infiltratio Inflow V Inflow V Total Ru Total Ru Primary Second Volume Percent	of Links: 1 Link: Predeveloped-Per on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): 0 Outflow To Downstrea ary Outflow To Downstrea Lost to ET (ac-ft): 0.0 Treated (Infiltrated+Fil	REDEVE CC Evap (ac- 0.00, (0) 0.00, 0.0 m Syste rream Sy 00 ltered+E <sup>-</sup>	ft): 10  	<b>)</b> 3.89 :): 103.89 c-ft): 0.00 Volume: 0	
Number Infiltratio Inflow V Inflow V Total Ru Total Ru Primary Second Volume Percent	of Links: 1 Link: Predeveloped-Per on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): Unoff Filtered (ac-ft): 0 Outflow To Downstrea ary Outflow To Downstrea Lost to ET (ac-ft): 0.0 Treated (Infiltrated+Fil	REDEVE CC Evap (ac- 0.00, (0) 0.00, 0.0 m Syste rream Sy 00 ltered+E <sup>-</sup>	ft): 10  	<b>)</b> 3.89 :): 103.89 c-ft): 0.00 Volume: 0	
Number	of Links: 1 Link: Predeveloped-Po on/Filtration Statistics olume (ac-ft): 103.89 olume Including PPT-E unoff Infiltrated (ac-ft): unoff Filtered (ac-ft): 0 Outflow To Downstrea ary Outflow To Downstrea ary Outflow To Downstrea Lost to ET (ac-ft): 0.0 Treated (Infiltrated+Fil SCENARIO: P of Links: 6	REDEVE REDEVE OC Evap (ac- 0.00, 0.0 0.00, 0.0 m Syste ream Sy 00 Itered+E <sup>-</sup> OSTDEV	ft): 10  	<b>)</b> 3.89 :): 103.89 c-ft): 0.00 Volume: 0	
Number	of Links: 1 Link: Predeveloped-Per on/Filtration Statistics 'olume (ac-ft): 103.89 'olume Including PPT-E unoff Infiltrated (ac-ft): 0 Outflow To Downstrea ary Outflow To Downstrea Lost to ET (ac-ft): 0.0 Treated (Infiltrated+Fil	REDEVE REDEVE OC Evap (ac- 0.00, 0.0 0.00, 0.0 m Syste ream Sy 00 Itered+E <sup>T</sup> OSTDEV	ELOPEI 	<b>)</b> 3.89 :): 103.89 c-ft): 0.00 Volume: 0	

\*\*\*\*\*\*

\*\*\*\*\*\*\*

Infiltration/Filtration Statistics------Inflow Volume (ac-ft): 0.01 Inflow Volume Including PPT-Evap (ac-ft): 0.01 Total Runoff Infiltrated (ac-ft): 0.00, 0.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.01 Secondary Outflow To Downstream System (ac-ft): 0.00 Volume Lost to ET (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 0.00%

#### \*\*\*\*\*\*\*\*\*\*\* Link: IT-01 \*\*\*\*\*\*\*\*\*

Infiltration/Filtration Statistics------Inflow Volume (ac-ft): 139.30 Inflow Volume Including PPT-Evap (ac-ft): 139.30 Total Runoff Infiltrated (ac-ft): 139.30, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Volume Lost to ET (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\*\*\*\*\*\*\*\* Link: IT-02 \*\*\*\*\*\*\*\*\*\*

Infiltration/Filtration Statistics------Inflow Volume (ac-ft): 85.53 Inflow Volume Including PPT-Evap (ac-ft): 85.53 Total Runoff Infiltrated (ac-ft): 85.53, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Volume Lost to ET (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\*\*\*\*\*\*\* Link: IT-03 \*\*\*\*\*\*\*\*\*

Infiltration/Filtration Statistics------Inflow Volume (ac-ft): 74.75 Inflow Volume Including PPT-Evap (ac-ft): 74.75 Total Runoff Infiltrated (ac-ft): 74.75, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Volume Lost to ET (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

\*\*\*\*\*\*\*\*\*\* Link: BIO-01

\*\*\*\*\*\*\*


Infiltration/Filtration Statistics------Inflow Volume (ac-ft): 62.40 Inflow Volume Including PPT-Evap (ac-ft): 62.69 Total Runoff Infiltrated (ac-ft): 62.69, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Volume Lost to ET (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%

#### \*\*\*\*\*\*\*\*\*\* Link: BIO-02

Infiltration/Filtration Statistics------Inflow Volume (ac-ft): 53.41 Inflow Volume Including PPT-Evap (ac-ft): 53.63 Total Runoff Infiltrated (ac-ft): 53.63, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Volume Lost to ET (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered+ET)/Total Volume: 100.00%


#### 

Scenario Predeveloped Compliance Link: Predeveloped-POC Scenario Postdeveloped Compliance Link: Postdeveloped-POC



	velopment Runoff	Postdevelopn		
Tr (Years)	Discharge (cfs)	Tr (Years) Disch	arge (cfs)	
2-Year	3.762E-02	2-Year	0.000	
5-Year	6.314E-02	5-Year	0.000	
10-Year	9.605E-02	10-Year	0.000	
25-Year	0.144	25-Year	0.000	
50-Year	0.178	50-Year	6.187E-02	
100-Year	0.235	100-Year	0.266	
200-Year	0.339	200-Year	0.289	
500-Year	0.477	500-Year	0.318	
** Record too	Short to Compute Peak	Discharge for These Re	ecurrence Intervals	

#### \*\*\*\* Flow Duration Performance \*\*\*\*



MEETS ALL LID DURATION DESIGN CRITERIA: PASS

# APPENDIX B

**INFILTRATION TEST RESULTS** 

		INFILT	RATION TEST DA	ATA SHEET				
			Project Information	on				
Project Name:	Goerig Apartments				22046			
Project Address:	1776 N Goerig Street	Goerig Apartments 1776 N Goerig Street, Woodland, WA 98674						
Test Hole No.:	IT-01			Tested By:	DDH			
Test Depth:	6 in			Date:	5/17/2022			
Depth to Groundwater:	>10 ft			Weather:	Sunny, 59°			
	Calculations				N	otes:		
	Parameters							
Parameter	Description	Equation	Value					
L	Length of Flow/Embedment Depth (in)	n/a	6					
t	Elapsed Drawdown Time (hr)	Stop Time - Start Time	Varies					
κ <sub>τ</sub>	Tested Coefficient of Permeability (in/hr)	k <sub>ī</sub> =(L/t)*In(h <sub>i</sub> ∕h <sub>f</sub> )	Varies					
k <sub>AVG</sub>	Avg. Tested Coefficient of Permeability (in/hr)	k <sub>AVG</sub> =k <sub>T1+T2+</sub> Tn/No. of Trials	3.06					
CF	Correction Factor		2					
k <sub>DES</sub>	Design Coefficient of Permeability (in/hr)	k <sub>DES</sub> =k <sub>AVG</sub> / CF <sub>TOT</sub>	1.53					
			Field Data					
Trial No.	Start Time	Stop Time	Elapsed Drawdown Time, † (hr)	Initial Depth to Water (in)	Final Depth to Water (in)	Initial Head, h <sub>i</sub> (in)	Final Head, h <sub>f</sub> (in)	k₁(in/hr)
1	8:48 AM	9:48 AM	1.00	0.00	6.00	15.00	9.00	3.06
2	9:48 AM	10:48 AM	1.00	0.00	6.00	15.00	9.00	3.06
3	10:48 AM	11:48 AM	1.00	0.00	6.00	15.00	9.00	3.06

		INFILT	RATION TEST DA	ATA SHEET				
			Project Information	on				
Project Name:	Goerig Apartments				22046			
Project Address:	1776 N Goerig Street	Goerig Apartments 1776 N Goerig Street, Woodland, WA 98674						
Test Hole No.:	IT-02			Tested By:	DDH			
Test Depth:	5 ft			Date:	5/17/2022			
Depth to Groundwater:	>10 ft			Weather:	Sunny, 59°			
	Calculations				N	otes:		
	Parameters							
Parameter	Description	Equation	Value					
L	Length of Flow/Embedment Depth (in)	n/a	6					
t	Elapsed Drawdown Time (hr)	Stop Time - Start Time	Varies					
k <sub>T</sub>	Tested Coefficient of Permeability (in/hr)	k <sub>ī</sub> =(L/t)*In(h <sub>i</sub> /h <sub>f</sub> )	Varies					
k <sub>avg</sub>	Avg. Tested Coefficient of Permeability (in/hr)	k <sub>AVG</sub> =k <sub>T1+T2+</sub> <sub>Tn</sub> /No. of Trials	91.95					
CF	Correction Factor		2					
k <sub>DES</sub>	Design Coefficient of Permeability (in/hr)	k <sub>DES</sub> =k <sub>AVG</sub> / CF <sub>TOT</sub>	45.97					
			Field Data					
Trial No.	Start Time	Stop Time	Elapsed Drawdown Time, † (hr)	Initial Depth to Water (in)	Final Depth to Water (in)	Initial Head, h <sub>i</sub> (in)	Final Head, h <sub>f</sub> (in)	k₁(in/hr)
1	10:31 AM	10:33 AM	0.03	0.00	6.00	15.00	9.00	91.95
2	10:33 AM	10:35 AM	0.03	0.00	6.00	15.00	9.00	91.95
3	10:35 AM	10:37 AM	0.03	0.00	6.00	15.00	9.00	91.95

		INFILT	RATION TEST DA	ATA SHEET				
			Project Information	on				
Project Name:	Goerig Apartments	Goerig Apartments			22046			
Project Address:	1776 N Goerig Street	Goerig Apartments 1776 N Goerig Street, Woodland, WA 98674						
Test Hole No.:	IT-03			Tested By:	DDH			
Test Depth:	6 ft			Date:	5/17/2022			
Depth to Groundwater:	>10 ft			Weather:	Sunny, 59°			
	Calculations				N	otes:		
	Parameters							
Parameter	Description	Equation	Value					
L	Length of Flow/Embedment Depth (in)	n/a	6					
t	Elapsed Drawdown Time (hr)	Stop Time - Start Time	Varies					
k <sub>ī</sub>	Tested Coefficient of Permeability (in/hr)	k <sub>t</sub> =(L/t)*In(h <sub>i</sub> /h <sub>f</sub> )	Varies					
k <sub>AVG</sub>	Avg. Tested Coefficient of Permeability (in/hr)	k <sub>AVG</sub> =k <sub>T1+T2+</sub> <sub>Tn</sub> /No. of Trials	91.95					
CF	Correction Factor		2					
K <sub>DES</sub>	Design Coefficient of Permeability (in/hr)	k <sub>DES</sub> =k <sub>AVG</sub> / CF <sub>TOT</sub>	45.97					
			Field Data					
Trial No.	Start Time	Stop Time	Elapsed Drawdown Time, † (hr)	Initial Depth to Water (in)	Final Depth to Water (in)	Initial Head, h <sub>i</sub> (in)	Final Head, h <sub>f</sub> (in)	k₁(in/hr)
1	10:50 AM	10:52 AM	0.03	0.00	6.00	15.00	9.00	91.95
2	10:52 AM	10:54 AM	0.03	0.00	6.00	15.00	9.00	91.95
3	10:54 AM	10:56 AM	0.03	0.00	6.00	15.00	9.00	91.95

# APPENDIX C

**Construction Stormwater General Permit (CSWGP)** 

# Stormwater Pollution Prevention Plan (SWPPP)

for Goerig Apartments

#### Prepared for: Department of Ecology Southwest Regional Office

Permittee / Owner	Developer	Operator / Contractor	
Goerig St, LLC	Goerig St, LLC	TBD	

#### Located at: 1776 N. Goerig St, Woodland, WA 98674

#### Parcel No. 50630

#### **Certified Erosion and Sediment Control Lead (CESCL)**

Name	Organization	Contact Phone Number
TBD	BD TBD T	

#### SWPPP Prepared By

Name	Organization	Contact Phone Number	
David G. Spencer	Jolma Design, LLC	(306) 723-0392	

#### **SWPPP** Preparation Date

May 31<sup>st</sup>, 2022

#### **Project Construction Dates**

Activity / Phase	Start Date	End Date
Sitework Construction	9/1/2022	9/1/2023

# List of Acronyms and Abbreviations

303(d)Section of the Clean Water Act pertaining to Impaired WaterbodiesBFOBellingham Field Office of the Department of EcologyBMP(s)Best Management Practice(s)CESCLCertified Erosion and Sediment Control LeadCO2Carbon DioxideCROCentral Regional Office of the Department of EcologyCRWPConstruction Stormwater General PermitCWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyERAUnited States Environmental Protection AgencyERSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologyPHPower of HydrogenRCWStormwater Management Manual for Eastern WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStormwater Management Manual for Western WashingtonSWMMEWStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWMROSouthwest Regional Office of the Department of EcologyVFDVancouver Field Office of the Department of EcologyWWROStormwater Management Manual for Western WashingtonSWMEWStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWRO <td< th=""><th>Acronym / Abbreviation</th><th>Explanation</th></td<>	Acronym / Abbreviation	Explanation
BMP(s)Best Management Practice(s)CESCLCertified Erosion and Sediment Control LeadCO2Carbon DioxideCR0Central Regional Office of the Department of EcologyCSWGPConstruction Stormwater General PermitCWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStarmwater Management Manual for Eastern WashingtonSWMMEWStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologypFPStormwater Management Manual for Eastern WashingtonSWPPPStormwater Regional Office of the Department of EcologyTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative Code	303(d)	Section of the Clean Water Act pertaining to Impaired Waterbodies
CESCLCertified Erosion and Sediment Control LeadCO2Carbon DioxideCROCentral Regional Office of the Department of EcologyCSWGPConstruction Stormwater General PermitCWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERSCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStardmard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologySWROSouthwest Regional Group PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	BFO	Bellingham Field Office of the Department of Ecology
CO2Carbon DioxideCR0Central Regional Office of the Department of EcologyCSWGPConstruction Stormwater General PermitCWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNepelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWSpill Prevention, Control, and CountermeasuresuStormwater Management Manual for Eastern WashingtonSWMMEWStormwater Pollution Prevention PlanFESCTemporary Erosion and Sediment ControlSWMMEWStormwater Regional Office of the Department of EcologypHStormwater Management Manual for Eastern WashingtonSWMMEWStormwater Management Manual for Eastern WashingtonSWMMEWStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyYFOVancouver Field Office of the Department of EcologyWACWACWashington Administrative CodeWSDOTWashington Administrative Code	BMP(s)	Best Management Practice(s)
ColCentral Regional Office of the Department of EcologyCSWGPConstruction Stornwater General PermitCWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNepheometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStornwater Management Manual for Eastern WashingtonSWMMEWStornwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyWROStornwater Management Manual for Eastern WashingtonSWMMEWStornwater Management Manual for Eastern WashingtonSWMMEWStornwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyYFOVancouver Field Office of the Department of EcologyWACWachWashington Administrative CodeWSDOTWashington Administrative Code	CESCL	Certified Erosion and Sediment Control Lead
CSWGPConstruction Stormwater General PermitCWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyWKOStormwater Management Manual for Western WashingtonSWPPPStormwater Management Manual for Eastern WashingtonSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	CO <sub>2</sub>	Carbon Dioxide
CWAClean Water ActDMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNTUNephelometric Turbidity UnitsNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWSpill Prevention, Control, and CountermeasuresuStormwater Management Manual for Eastern WashingtonSWMMEWStormwater Management Manual for Western WashingtonSWMMEWSouthwest Regional Office of the Department of EcologyFFDStormwater Management Manual for Western WashingtonSWPPPStormwater Management Manual for Eastern WashingtonSWROSouthwest Regional Office of the Department of EcologyFMDLTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyFMDLTotal Maximun Daily LoadVFOVancouver Field Office of the Department of EcologyFMACWashington Administrative CodeFWACWashington Administrative Code	CRO	Central Regional Office of the Department of Ecology
DMRDischarge Monitoring ReportDODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCEosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWSpill Prevention, Control, and CountermeasuresuStormwater Management Manual for Eastern WashingtonSWMMEWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyFMDLTotal Maximum Daily LoadYFOWaccuver Field Office of the Department of EcologyWACWashington Administrative Code	CSWGP	Construction Stormwater General Permit
DODissolved OxygenEcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWMPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadYFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	CWA	Clean Water Act
EcologyWashington State Department of EcologyEPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyYFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWACWashington Administrative Code	DMR	Discharge Monitoring Report
EPAUnited States Environmental Protection AgencyEROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyYFOVancouver Field Office of the Department of EcologyWACWashington Department of Transportation	DO	Dissolved Oxygen
EROEastern Regional Office of the Department of EcologyERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyYFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	Ecology	Washington State Department of Ecology
ERTSEnvironmental Report Tracking SystemESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyYFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	EPA	United States Environmental Protection Agency
ESCErosion and Sediment ControlGULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOWashington Administrative CodeWSDOTWashington Department of Transportation	ERO	Eastern Regional Office of the Department of Ecology
GULDGeneral Use Level DesignationNPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOWashington Administrative CodeWSDOTWashington Department of Transportation	ERTS	Environmental Report Tracking System
NPDESNational Pollutant Discharge Elimination SystemNTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOWashington Administrative CodeWSDOTWashington Department of Transportation	ESC	Erosion and Sediment Control
NTUNephelometric Turbidity UnitsNWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	GULD	General Use Level Designation
NWRONorthwest Regional Office of the Department of EcologypHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	NPDES	National Pollutant Discharge Elimination System
pHPower of HydrogenRCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWMMWWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	NTU	Nephelometric Turbidity Units
RCWRevised Code of WashingtonSPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWMMWWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	NWRO	Northwest Regional Office of the Department of Ecology
SPCCSpill Prevention, Control, and CountermeasuresuStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWMMWWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	рН	Power of Hydrogen
suStandard UnitsSWMMEWStormwater Management Manual for Eastern WashingtonSWMMWWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	RCW	Revised Code of Washington
SWMMEWStormwater Management Manual for Eastern WashingtonSWMMWWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	SPCC	Spill Prevention, Control, and Countermeasure
SWMMWWStormwater Management Manual for Western WashingtonSWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	su	Standard Units
SWPPPStormwater Pollution Prevention PlanTESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	SWMMEW	Stormwater Management Manual for Eastern Washington
TESCTemporary Erosion and Sediment ControlSWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	SWMMWW	Stormwater Management Manual for Western Washington
SWROSouthwest Regional Office of the Department of EcologyTMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	SWPPP	Stormwater Pollution Prevention Plan
TMDLTotal Maximum Daily LoadVFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	TESC	Temporary Erosion and Sediment Control
VFOVancouver Field Office of the Department of EcologyWACWashington Administrative CodeWSDOTWashington Department of Transportation	SWRO	Southwest Regional Office of the Department of Ecology
WACWashington Administrative CodeWSDOTWashington Department of Transportation	TMDL	Total Maximum Daily Load
WSDOT Washington Department of Transportation	VFO	Vancouver Field Office of the Department of Ecology
	WAC	Washington Administrative Code
WWHM Western Washington Hydrology Model	WSDOT	Washington Department of Transportation
	WWHM	Western Washington Hydrology Model

# **Project Information (1.0)**

Project/Site Name:Goerig ApartmentsStreet/Location:1776 N. Goerig StCity: WoodlandState:WAZip code: 98674Subdivision:N/AReceiving waterbody:N/A: Stormwater runoff will be managed on site via infiltration

# **Existing Conditions (1.1)**

Total acreage (including support activities such as off-site equipment staging yards, material storage areas, borrow areas).

Total acreage: 1.14 ac+/-

Disturbed acreage: 1.14 ac+/-

Existing structures:	Existing shop and shed
Landscape topography:	Rolling slopes trending toward southeast corner of site
Drainage patterns:	Majority of stormwater likely infiltrates into near-surface soils, runoff from the site could migrate south and east to the neighboring property.
Existing Vegetation:	Primarily field grasses, trees, and herbaceous ground cover
Critical Areas (wetlands, streams, high erosion risk, steep or difficult to stabilize slopes): None known.	

List of known impairments for 303(d) listed or Total Maximum Daily Load (TMDL) for the receiving waterbody: None known in the area of the site.

Table 1 includes a list of suspected and/or known contaminants associated with the construction activity.

 Table 1 – Summary of Site Pollutant Constituents

Constituent (Pollutant)	Location	Depth	Concentration
None	N/A	N/A	N/A

# **Proposed Construction Activities (1.2)**

Description of site development (example: subdivision):

This project proposes to construct two 3-story apartment buildings totaling 7,816 sf and parking, walkways, landscape, etc.

Description of construction activities (example: site preparation, demolition, excavation): Site preparation, site stripping, earthwork, utilities, stormwater, building and parking lot construction.

Description of site drainage including flow from and onto adjacent properties. Must be consistent with Site Map in Appendix A:

Minimal flow from adjacent properties. Site will minimize flow to adjacent properties. See erosion control plan.

Description of final stabilization (example: extent of revegetation, paving, landscaping): Site will be stabilized by construction of buildings, parking lot and stabilized landscaping.

#### Contaminated Site Information:

Proposed activities regarding contaminated soils or groundwater (example: on-site treatment system, authorized sanitary sewer discharge):

N/A - No known contaminated soils or groundwater.

# **Construction Stormwater Best Management Practices (BMPs) (2.0)**

The SWPPP is a living document reflecting current conditions and changes throughout the life of the project. These changes may be informal (i.e. hand-written notes and deletions). Update the SWPPP when the CESCL has noted a deficiency in BMPs or deviation from original design.

## The 13 Elements (2.1)

# Element 1: Preserve Vegetation / Mark Clearing Limits (2.1.1)

List and describe BMPs: To the extent possible, areas where grading is proposed shall be kept vegetated until activity in those areas begins. No grading will occur within two feet of the existing property boundary where it borders private property.

Installation Schedules: Grading limits shall be marked with silt fence prior to the start of construction.

Inspection and Maintenance plan: Inspect silt fence regularly to make sure it has not been removed or damaged. If silt fence has been damaged or visibility reduced, it shall be repaired or replaced immediately and visibility restored.

Responsible Staff: TBD

## Element 2: Establish Construction Access (2.1.2)

List and describe BMPs: : A stabilized construction entrance shall be installed in accordance with City of Woodland standard detail E-05 at the new shared driveway entrance onto Scott Ave. Vehicles entering or exiting the site shall use this entrance to prevent tracking sediment onto the adjacent asphalt pavement.

Installation Schedules: The stabilized construction entrance/exit shall be installed prior to the start of major grading activities.

Inspection and Maintenance plan: Quarry spalls shall be added if the pad is no longer in accordance with the specifications.

- If the entrance is not preventing sediment from being tracked onto pavement, then alternative measures to keep the streets free of sediment shall be used. This may include replacement/cleaning of the existing quarry spalls, street sweeping, an increase in the dimensions of the entrance, or the installation of a wheel wash.
- Any sediment that is tracked onto pavement shall be removed by shoveling or street sweeping. The sediment collected by sweeping shall be removed or stabilized on site. The pavement shall not be cleaned by washing down the street, except when high efficiency sweeping is ineffective and there is a threat to public safety. If it is necessary to wash the streets, the construction of a small sump to contain the wash water shall be considered. The sediment would then be washed into the sump where it can be controlled.

- Perform street sweeping by hand or with a high efficiency sweeper. Do not use a non-high efficiency mechanical sweeper because this creates dust and throws soils into storm systems or conveyance ditches.
- Any quarry spalls that are loosened from the pad, which end up on the roadway shall be removed immediately.
- If vehicles are entering or exiting the site at points other than the construction entrance(s), fencing (BMP C103) shall be installed to control traffic.

Upon project completion and site stabilization, all construction accesses intended as permanent access for maintenance shall be permanently stabilized.

Responsible Staff: TBD

# Element 3: Control Flow Rates (2.1.3)

Will you construct stormwater retention and/or detention facilities?  $\Box$  Yes  $\boxtimes$  No

Will you use permanent infiltration ponds or other low impact development (example: rain gardens, bio-retention, porous pavement) to control flow during construction? ☐ Yes ⊠ No

List and describe BMPs: Offsite runoff is not expected to occur during construction; therefore, no specific BMPs are currently proposed. In the unexpected event runoff does leave the site, the contractor will install the necessary BMPs using standard methods (e.g., wattles, temporary sediment pond) and/or materials on hand to control flow rates. Silt fence (see BMP C233 below) will be installed to prevent coarse sediment migration off site, and will also help mitigate flow rates if offsite runoff occurs.

Installation Schedules: Immediately after runoff from the site is observed.

Inspection and Maintenance plan: Follow the applicable maintenance and inspection guidelines contained in Volume II of the Stormwater Management Manual for Western Washington.

Responsible Staff: TBD

## **Element 4: Install Sediment Controls (2.1.4)**

List and describe BMPs: Silt fence will be installed along the entire perimeter of the Project Site, except at the construction entrancef.

Installation Schedules: Silt fence shall be installed prior to the start of site grading activities.

Inspection and Maintenance plan: Repair any damage immediately.

• Intercept and convey all evident concentrated flows uphill of the silt fence to a sediment pond.

Check the uphill side of the fence for signs of the fence clogging and acting as a barrier to flow and then causing channelization of flows parallel to the fence. If this occurs, replace the fence or remove the trapped sediment.

Responsible Staff: TBD

## Element 5: Stabilize Soils (2.1.5)

#### West of the Cascade Mountains Crest

Season	Dates	Number of Days Soils Can be Left Exposed
During the Dry Season	May 1 – September 30	7 days
During the Wet Season	October 1 – April 30	2 days

Soils must be stabilized at the end of the shift before a holiday or weekend if needed based on the weather forecast.

Anticipated project dates:

Start date: 9/1/2022

End date: 9/1/2023

Will you construct during the wet season? ⊠ Yes □ No

#### **BMP C120: Temporary and Permanent Seeding**

List and describe BMPs: The following areas shall be seeded during construction:

- Disturbed areas that have reached final grade and are not surfaced with asphalt, concrete, gravel, or landscape plantings within 30 days after being worked
- Disturbed areas that will remain unworked for more than 30 days

Installation Schedules: Optimum seeding windows for western Washington are April 1 through June 30, and September 1 through October 1.

- Between July 1 and August 30, seeding requires irrigation until 75 percent grass cover is established.
- Between October 1 and March 30 seeding requires a cover of mulch with straw or an erosion control blanket until 75 percent grass cover is established.

- Review all disturbed areas in late August to early September and complete all seeding by the end of September. Otherwise, vegetation will not establish itself enough to provide more than average protection.
- Mulch is required at all times for seeding because it protects seeds from heat, moisture loss, and transport due to runoff. Mulch can be applied on top of the seed or simultaneously by hydroseeding. See BMP C121: Mulching for specifications.

Seed and mulch all disturbed areas not otherwise vegetated at final site stabilization. Final stabilization means the completion of all soil disturbing activities at the site and the establishment of a permanent vegetative cover, or equivalent permanent stabilization measures (such as pavement, riprap, gabions or geotextiles) which will prevent erosion.

Inspection and Maintenance plan:

- Reseed any seeded areas that fail to establish at least 80 percent cover (100 percent cover for areas that receive sheet or concentrated flows). If reseeding is ineffective, use an alternate method such as sodding, mulching, or nets/blankets. If winter weather prevents adequate grass growth, this time limit may be relaxed at the discretion of the local authority when sensitive areas would otherwise be protected.
- Reseed and protect by mulch any areas that experience erosion after achieving adequate cover. Reseed and protect by mulch any eroded area.
- Supply seeded areas with adequate moisture, but do not water to the extent that it generates runoff.

Responsible Staff: TBD

#### **BMP C121: Mulching**

Description: Mulching provides immediate temporary erosion protection, and enhances plant establishment by conserving moisture, holding fertilizer, seed, and topsoil in place, and moderating soil temperatures. Mulch should be used on disturbed areas requiring cover for less than 30 days, and for all times for seeded areas.

Installation Schedules: As needed for immediate temporary erosion protection, and when seeding is applied.

Inspection and Maintenance plan:

- The thickness of the cover must be maintained.
- Any areas that experience erosion shall be remulched and/or protected with a net or blanket. If the erosion problem is drainage related, then the problem shall be fixed and the eroded area remulched.

Responsible Staff: TBD

#### **BMP C123: Plastic Covering**

Description: Plastic covering should be used to provide immediate, short-term erosion protection to stockpiles. Sand-filled burlap or geotextile bags shall be placed every 3 to 6 feet along seams, and tied together with twine to hold them in place.

Installation Schedules: As needed for immediate temporary erosion protection of soil stockpiles.

Inspection and Maintenance plan:

- Torn sheets must be replaced and open seams repaired.
- Completely remove and replace the plastic if it begins to deteriorate due to ultraviolet radiation.
- Completely remove plastic when no longer needed.
- Dispose of old tires used to weight down plastic sheeting appropriately.

Responsible Staff: TBD

#### BMP C140: Dust Control

Description: Dust control shall be implemented to prevent wind transport of dust from disturbed soil surfaces onto roadways, drainage ways, and surface waters. Control measures that may be used include the following:

- Vegetating, mulching, or applying gravel or landscaping rock to areas that will not receive vehicle traffic
- Clearing only those areas where immediate activity will take place, leaving the remaining area(s) in original condition. Maintain the original ground cover as long as practicable.
- Sprinkle the site with water until surface is wet. Repeat as needed. To prevent carryout of mud onto street, refer to Stabilized Construction Entrance (BMP C105).

Installation Schedules: As needed for immediate temporary erosion protection of soil stockpiles.

Inspection and Maintenance plan:

• Respray area as necessary to minimize dust.

Responsible Staff: TBD

## Element 6: Protect Slopes (2.1.6)

#### 🗌 Yes 🔀 No

Steep slopes are not expected to be present at the site during construction; therefore, no BMPs addressing Element 6 are proposed.

# Element 7: Protect Drain Inlets (2.1.7)

List and describe BMPs: Existing and new storm drain inlets that could likely receive runoff generated from the site will be protected using one of the following measures:

- Curb inlet protection
- Curb and gutter sediment barrier
- Catchbasin filters
- Other approved protection measures

Installation Schedules: Storm drain inlet protection measures shall be installed prior to ground-disturbing activities in areas that could generate runoff into existing or proposed storm drain inlets.

Inspection and Maintenance plan:

- Inspect catch basin filters frequently, especially after storm events.
- Clean and replace clogged inserts. For systems with clogged stone filters: pull away the stones from the inlet and clean or replace. An alternative approach would be to use the clogged stone as fill and put fresh stone around the inlet.
- Do not wash sediment into storm drains while cleaning. Spread all excavated material evenly over the surrounding land area or stockpile and stabilize as appropriate.
- Inlet protection devices will be cleaned (or removed and replaced), when sediment has filled the device by one third (1/3) or as specified by the manufacturer.
- Inlets will be inspected weekly at a minimum and daily during storm events.

Responsible Staff: TBD

### Element 8: Stabilize Channels and Outlets (2.1.8)

The site contains no existing onsite conveyance channels, nor are any proposed; therefore, BMPs addressing Element 8 are not applicable.

### Element 9: Control Pollutants (2.1.9)

The following pollutants are anticipated to be present on-site:

#### Table 2 – Pollutants

#### Pollutant (and source, if applicable)

Petroleum products, including fuel, oil, and grease, used for equipment operation and maintenance.

pH-modifying products used in cement concrete, including cement, cement kiln dust, fly ash, new concrete washing and curing waters, waste streams generated from concrete grinding and sawing, concrete pumping, and mixer washout waters.

Will maintenance, fueling, and/or repair of heavy equipment and vehicles occur on-site? ☐ Yes ⊠ No

#### BMP C153: Material Delivery, Storage, and Containment

Description: The following procedures should be utilized to prevent, reduce, or eliminate discharge of pollutants to the stormwater system from material delivery and storage activities. The overall objectives of this BMP are to minimize onsite hazardous material storage, store materials in a designated area, and install secondary containment if necessary. These procedures are suitable for use at all construction sites with delivery and storage of the following materials:

- Petroleum products such as fuel, oil and grease
- Soil stabilizers and binders (e.g. Polyacrylamide)
- Fertilizers, pesticides and herbicides
- Detergents
- Asphalt and concrete compounds
- Hazardous chemicals such as acids, lime, adhesives, paints, solvents and curing compounds
- Any other material that may be detrimental if released to the environment

The following steps should be taken to minimize risk:

- Temporary storage area should be located away from vehicular traffic, near the construction entrance(s), and away from waterways or storm drains.
- Material Safety Data Sheets (MSDS) should be supplied for all materials stored. Chemicals should be kept in their original labeled containers.
- Hazardous material storage on-site should be minimized.
- Hazardous materials should be handled as infrequently as possible.
- During the wet weather season (Oct 1 April 30), consider storing materials in a covered area.
- Materials should be stored in secondary containments, such as earthen dike, horse trough, or even a children's wading pool for non-reactive materials such as detergents, oil, grease, and paints. Small amounts of material may be secondarily contained in "bus boy" trays or concrete mixing trays.
- Do not store chemicals, drums, or bagged materials directly on the ground. Place these items on a pallet and, when possible, and within secondary containment.
- If drums must be kept uncovered, store them at a slight angle to reduce ponding of rainwater on the lids to reduce corrosion. Domed plastic covers are inexpensive and snap to the top of drums, preventing water from collecting.
- Liquids, petroleum products, and substances listed in 40 CFR Parts 110, 117, or 302 shall be stored in approved containers and drums and shall not be overfilled. Containers and drums shall be stored in temporary secondary containment facilities.

- Temporary secondary containment facilities shall provide for a spill containment volume able to contain 10% of the total enclosed container volume of all containers, or 110% of the capacity of the largest container within its boundary, whichever is greater.
- Secondary containment facilities shall be impervious to the materials stored therein for a minimum contact time of 72 hours.
- Secondary containment facilities shall be maintained free of accumulated rainwater and spills. In the event of spills or leaks, accumulated rainwater and spills shall be collected and placed into drums. These liquids shall be handled as hazardous waste unless testing determines them to be non-hazardous.
- Sufficient separation should be provided between stored containers to allow for spill cleanup and emergency response access.
- During the wet weather season (Oct 1 April 30), each secondary containment facility shall be covered during non-working days, prior to and during rain events.
- Keep material storage areas clean, organized and equipped with an ample supply of appropriate spill clean-up material (spill kit).
- The spill kit should include, at a minimum:
  - o 1-Water Resistant Nylon Bag
  - o 3-Oil Absorbent Socks 3"x 4'
  - o 2-Oil Absorbent Socks 3"x 10'
  - o 12-Oil Absorbent Pads 17"x19"
  - o 1-Pair Splash Resistant Goggles
  - o 3-Pair Nitrile Gloves
  - 10-Disposable Bags with Ties
  - o Instructions

Installation Schedules: Material handling and storage procedures should be followed any time hazardous or environmentally detrimental materials are handled or stored on site.

Responsible Staff: TBD

Will wheel wash or tire bath system BMPs be used during construction?  $\Box$  Yes  $\boxtimes$  No

Will pH-modifying sources be present on-site? ⊠ Yes □ No

#### Table 3 – pH-Modifying Sources

-	
	None
	Bulk cement
	Cement kiln dust
	Fly ash
$\square$	Other cementitious materials
$\square$	New concrete washing or curing waters
	Waste streams generated from concrete grinding and sawing
	Exposed aggregate processes

	Dewatering concrete vaults		
$\boxtimes$	Concrete pumping and mixer washout waters		
	Recycled concrete		
	Other (i.e. calcium lignosulfate) [please describe]		
BMF	BMP C151: Concrete Handling		

# Description: The following management practices should be utilized any time concrete is used

- Wash out concrete truck chutes, pumps, and internals into formed areas only. Assure that washout of concrete trucks is performed off site or in designated concrete washout areas. Do not wash out concrete trucks onto the ground, or into storm drains, open ditches, streets, or streams. Refer to BMP C154 for information on concrete washout areas.
- Return unused concrete remaining in the truck and pump to the originating batch plant for recycling. Do not dump excess concrete on site, except in designated concrete washout areas.
- Wash off hand tools including, but not limited to, screeds, shovels, rakes, floats, and trowels into formed areas only.
- Wash equipment difficult to move, such as concrete pavers, in areas that do not directly drain to natural or constructed stormwater conveyances.
- Do not allow washdown from areas, such as concrete aggregate driveways, to drain directly to natural or constructed stormwater conveyances.
- Contain washwater and leftover product in a lined container when no formed areas are available. Dispose of contained concrete in a manner that does not violate ground water or surface water quality standards.
- Always use forms or solid barriers for concrete pours, such as pilings, within 15-feet of surface waters.

Installation Schedules: Concrete handling measures should be implemented any time onsite concrete cement construction activities take place.

Inspection and Maintenance plan: Check containers for holes in the liner daily during concrete pours and repair the same day.

Responsible Staff: TBD

on site:

#### BMP C152: Sawcutting and Surfacing Pollution Prevention

Description: Sawcutting and surfacing operations generate slurry and process water that contains fine particles and high pH (concrete cutting), both of which can violate the water quality standards in the receiving water. Concrete spillage or concrete discharge to surface waters of the State is prohibited. Use this BMP to minimize and eliminate process water and slurry created through sawcutting or surfacing from entering waters of the State. Utilize the following management practices anytime sawcutting or surfacing operations take place. These activities include, but are not limited to, sawing, coring, grinding, roughening, hydro-demolition, bridge and road surfacing. This BMP should be implemented by following the guidelines listed below:

- Vacuum slurry and cuttings during cutting and surfacing operations.
- Slurry and cuttings shall not remain on permanent concrete or asphalt pavement overnight.
- Slurry and cuttings shall not drain to any natural or constructed drainage conveyance including stormwater systems. This may require temporarily blocking catch basins.
- Dispose of collected slurry and cuttings in a manner that does not violate ground water or surface water quality standards.
- Do not allow process water generated during hydro-demolition, surface roughening, or similar operations to drain to any natural or constructed drainage conveyance including stormwater systems.
- Dispose of process water in a manner that does not violate ground water or surface water quality standards.
- Handle and dispose cleaning waste material and demolition debris in a manner that does not cause contamination of water. Dispose of sweeping material from a pick-up sweeper at an appropriate disposal site.

Installation Schedules: The above-referenced sawcutting and surfacing pollution prevention measures should be implemented anytime either of these activities take place.

Inspection and Maintenance plan: Continually monitor operations to determine whether slurry, cuttings, or process water could enter waters of the state. If inspections show that a violation of water quality standards could occur, stop operations and immediately implement preventive measures such as berms, barriers, secondary containment, and vacuum trucks.

Responsible Staff: TBD

#### **BMP C154: Concrete Washout Area**

Description: To prevent or reduce discharge of concrete waste pollutants to stormwater, concrete washout will be conducted off site where practicable; in the event onsite washout is required, the following procedures should be followed:

Perform washout of concrete trucks off-site or in designated concrete washout areas only.

- Do not wash out concrete trucks onto the ground, or into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped on-site, except in designated concrete washout areas.
- Concrete washout areas may be prefabricated concrete washout containers, or selfinstalled structures (above-grade or below-grade).

- Prefabricated containers are most resistant to damage and protect against spills and leaks. Companies may offer delivery service and provide regular maintenance and disposal of solid and liquid waste.
- If self-installed concrete washout areas are used, below-grade structures are preferred over above-grade structures because they are less prone to spills and leaks.
- Self-installed above-grade structures should only be used if excavation is not practical. Installation Schedules: The above-referenced sawcutting and surfacing pollution prevention measures should be implemented anytime either of these activities take place.
- Education
  - Discuss the concrete management techniques described in this BMP with the ready-mix concrete supplier before any deliveries are made.
  - Educate employees and subcontractors on the concrete waste management techniques described in this BMP.
  - Arrange for contractor's superintendent or Certified Erosion and Sediment Control Lead (CESCL) to oversee and enforce concrete waste management procedures.
  - A sign should be installed adjacent to each temporary concrete washout facility to inform concrete equipment operators to utilize the proper facilities.

Inspection and Maintenance plan:

- Inspect and verify that concrete washout BMPs are in place prior to the commencement of concrete work.
- During periods of concrete work, inspect daily to verify continued performance.
  - Check overall condition and performance.
  - Check remaining capacity (% full).
  - If using self-installed washout facilities, verify plastic liners are intact and sidewalls are not damaged.
  - o If using prefabricated containers, check for leaks.
- Washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 12 inches.
- Washout facilities must be cleaned, or new facilities must be constructed and ready for use once the washout is 75% full.
- If the washout is nearing capacity, vacuum and dispose of the waste material in an approved manner.
- Do not discharge liquid or slurry to waterways, storm drains or directly onto ground.
- Do not use sanitary sewer without local approval.
- Place a secure, non-collapsing, non-water collecting cover over the concrete washout facility prior to predicted wet weather to prevent accumulation and overflow of precipitation.
- Remove and dispose of hardened concrete and return the structure to a functional condition. Concrete may be reused on-site or hauled away for disposal or recycling.
- When you remove materials from the self-installed concrete washout, build a new structure; or, if the previous structure is still intact, inspect for signs of weakening or

damage, and make any necessary repairs. Re-line the structure with new plastic after each cleaning.

Responsible Staff: TBD

Concrete trucks must not be washed out onto the ground, or into storm drains, open ditches, streets, or streams. Excess concrete must not be dumped on-site, except in designated concrete washout areas with appropriate BMPs installed.

Will uncontaminated water from water-only based shaft drilling for construction of building, road, and bridge foundations be infiltrated provided the wastewater is managed in a way that prohibits discharge to surface waters?

 $\Box$  Yes  $\boxtimes$  No

Water-only based shaft drilling is not expected to take place during construction.

## Element 10: Control Dewatering (2.1.10)

Dewatering at the site is not expected to be required. In the event it is required, the contractor shall update the SWPPP to include dewatering control BMPs.

## Element 11: Maintain BMPs (2.1.11)

All temporary and permanent Erosion and Sediment Control (ESC) BMPs shall be maintained and repaired as needed to ensure continued performance of their intended function.

Maintenance and repair shall be conducted in accordance with each particular BMP specification (see *Volume II of the SWMMWW or Chapter 7 of the SWMMEW*).

Visual monitoring of all BMPs installed at the site will be conducted at least once every calendar week and within 24 hours of any stormwater or non-stormwater discharge from the site. If the site becomes inactive and is temporarily stabilized, the inspection frequency may be reduced to once every calendar month.

All temporary ESC BMPs shall be removed within 30 days after final site stabilization is achieved or after the temporary BMPs are no longer needed.

Trapped sediment shall be stabilized on-site or removed. Disturbed soil resulting from removal of either BMPs or vegetation shall be permanently stabilized.

Additionally, protection must be provided for all BMPs installed for the permanent control of stormwater from sediment and compaction. BMPs that are to remain in place following completion of construction shall be examined and restored to full operating condition. If sediment enters these BMPs during construction, the sediment shall be removed and the facility shall be returned to conditions specified in the construction documents.

# Element 12: Manage the Project (2.1.12)

The project will be managed based on the following principles:

- Projects will be phased to the maximum extent practicable and seasonal work limitations will be taken into account.
- Inspection and monitoring:
  - Inspection, maintenance and repair of all BMPs will occur as needed to ensure performance of their intended function.
  - Site inspections and monitoring will be conducted in accordance with Special Condition S4 of the CSWGP. Sampling locations are indicated on the <u>Site Map</u>. Sampling station(s) are located in accordance with applicable requirements of the CSWGP.
- Maintain an updated SWPPP.
  - The SWPPP will be updated, maintained, and implemented in accordance with Special Conditions S3, S4, and S9 of the CSWGP.

As site work progresses the SWPPP will be modified routinely to reflect changing site conditions. The SWPPP will be reviewed monthly to ensure the content is current.

#### Table 5 – Management

$\square$	Design the project to fit the existing topography, soils, and drainage patterns
$\boxtimes$	Emphasize erosion control rather than sediment control
$\square$	Minimize the extent and duration of the area exposed
$\square$	Keep runoff velocities low
$\square$	Retain sediment on-site
$\square$	Thoroughly monitor site and maintain all ESC measures
	Schedule major earthwork during the dry season
	Other (please describe)

# Element 13: Protect Low Impact Development (LID) BMPs (2.1.13)

Bioretention and infiltration facilities will be constructed to manage stormwater runoff generated from post-developed new impervious areas of the Project Site. The facility shall be protected using the following procedures:

- Protect Bioretention BMPs from sedimentation through installation and maintenance of erosion and sediment control BMPs on portions of the site that drain into the facility. Restore the BMP to its fully functioning condition if it accumulates sediment during construction. Restoring the BMP must include removal of sediment and any sedimentladen amended soils, and replacing the removed soils with soils meeting the design specification.
- Prevent compacting infiltration BMPs by excluding construction equipment and foot traffic. Protect completed lawn and landscaped areas from compaction due to construction equipment.
- Keep all heavy equipment off existing soils under infiltration/bioretention facilities that have been excavated to final grade to retain the infiltration rate of the soils.

## **Pollution Prevention Team (3.0)**

Title	Name(s)	Phone Number
Certified Erosion and		
Sediment Control Lead		
(CESCL)		
Resident Engineer	David G. Spencer,PE	360-723-0392
Emergency Ecology		
Contact		
Emergency Permittee/	Aidan Willis	503-957-0966
Owner Contact		
Non-Emergency Owner	Aidan Willis	503-957-0966
Contact		
Monitoring Personnel		
Ecology Regional Office	Southwest Region	360-407-6300

#### Table 7 – Team Information

# Monitoring and Sampling Requirements (4.0)

Monitoring includes visual inspection, sampling for water quality parameters of concern, and documentation of the inspection and sampling findings in a site log book. A site log book will be maintained for all on-site construction activities and will include:

- A record of the implementation of the SWPPP and other permit requirements
- Site inspections
- Stormwater sampling data

File a blank form under Appendix D.

The site log book must be maintained on-site within reasonable access to the site and be made available upon request to Ecology or the local jurisdiction.

Numeric effluent limits may be required for certain discharges to 303(d) listed waterbodies. See CSWGP Special Condition S8 and Section 5 of this template.

# Site Inspection (4.1)

Site inspections will be conducted at least once every calendar week and within 24 hours following any discharge from the site. For sites that are temporarily stabilized and inactive, the required frequency is reduced to once per calendar month.

# **Reporting and Record Keeping (6.0)**

# **Record Keeping (6.1)**

# Site Log Book (6.1.1)

A site log book will be maintained for all on-site construction activities and will include:

- A record of the implementation of the SWPPP and other permit requirements
- Site inspections
- Sample logs

# **Records Retention (6.1.2)**

Records will be retained during the life of the project and for a minimum of three (3) years following the termination of permit coverage in accordance with Special Condition S5.C of the CSWGP.

Permit documentation to be retained on-site:

- CSWGP
- Permit Coverage Letter
- SWPPP
- Site Log Book

Permit documentation will be provided within 14 days of receipt of a written request from Ecology. A copy of the SWPPP or access to the SWPPP will be provided to the public when requested in writing in accordance with Special Condition S5.G.2.b of the CSWGP.

## Updating the SWPPP (6.1.3)

The SWPPP will be modified if:

- Found ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site.
- There is a change in design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the State.

The SWPPP will be modified within seven (7) days if inspection(s) or investigation(s) determine additional or modified BMPs are necessary for compliance. An updated timeline for BMP implementation will be prepared.

# Reporting (6.2)

## **Discharge Monitoring Reports (6.2.1)**

**Cumulative soil disturbance is less than one (1) acre; therefore**, Discharge Monitoring Reports (DMRs) will not be submitted to Ecology because water quality sampling is not being conducted at the site.

## Notification of Noncompliance (6.2.2)

If any of the terms and conditions of the permit is not met, and the resulting noncompliance may cause a threat to human health or the environment, the following actions will be taken:

- 1. Ecology will be notified within 24-hours of the failure to comply by calling the applicable Regional office ERTS phone number (Regional office numbers listed below).
- 2. Immediate action will be taken to prevent the discharge/pollution or otherwise stop or correct the noncompliance. If applicable, sampling and analysis of any noncompliance will be repeated immediately and the results submitted to Ecology within five (5) days of becoming aware of the violation.
- 3. A detailed written report describing the noncompliance will be submitted to Ecology within five (5) days, unless requested earlier by Ecology.

Anytime turbidity sampling indicates turbidity is 250 NTUs or greater, or water transparency is 6 cm or less, the Ecology Regional office will be notified by phone within 24 hours of analysis as required by Special Condition S5.A of the CSWGP.

- <u>Central Region</u> at (509) 575-2490 for Benton, Chelan, Douglas, Kittitas, Klickitat, Okanogan, or Yakima County
- <u>Eastern Region</u> at (509) 329-3400 for Adams, Asotin, Columbia, Ferry, Franklin, Garfield, Grant, Lincoln, Pend Oreille, Spokane, Stevens, Walla Walla, or Whitman County
- <u>Northwest Region</u> at (425) 649-7000 for Island, King, Kitsap, San Juan, Skagit, Snohomish, or Whatcom County
- <u>Southwest Region</u> at (360) 407-6300 for Clallam, Clark, Cowlitz, Grays Harbor, Jefferson, Lewis, Mason, Pacific, Pierce, Skamania, Thurston, or Wahkiakum

Include the following information:

- 1. Your name and / Phone number
- 2. Permit number
- 3. City / County of project
- 4. Sample results
- 5. Date / Time of call


- 6. Date / Time of sample
- 7. Project name

In accordance with Special Condition S4.D.5.b of the CSWGP, the Ecology Regional office will be notified if chemical treatment other than CO<sub>2</sub> sparging is planned for adjustment of high pH water.

# Appendix/Glossary

- A. Site Map
- B. BMP Details
- C. Site Inspection Form

# APPENDIX A: SITE MAP



	1	I					
				ſ			
						]	
			olm	a De	esign	, LLC	
CONTROL NOTES:	DSION CONTROL MEASURES AS NECESSARY TO	10 \$	Sout	h Pa Ste.	rkwc 102	iy Av	e.
	F FROM LEAVING THE PROJECT SITE.	Battl	(36	50) 72	23-03		
	BE REMOVED UNTIL SITE HAS BEEN FULLY STABILIZED.					<u>, , , , , , , , , , , , , , , , , , , </u>	
M SITE, IT MAY NOT BE NECESS CASE WHERE IT IS NOT NECESS HE PROPERTY LINE (IE CONSTR RK FROM CROSSING ONTO A	SARY AT THE DISCRETION OF THE CONTRACTOR. IN SARY, SOME SORT OF DEMARCATION SHALL BE MADE RUCTION FENCING) TO PREVENT CONSTRUCTION DJACENT PROPERTY. SITE GRADING LIMITS ARE SIBILITY FENCE MAY BE USED INSTEAD OF SILT FENCE	and the second sec	ALD ALL	G. SI	EN GROU	and	n
	BLIC STREET FREE FROM SEDIMENT, WHEEL BE INSTALLED IF CONTRACTOR IS TRACKING SEDIMENT	30	PROFE	SSIONA	ERED LENGT	23/20	22
SION CONTROL. IT IS THE COM	TH ALL REQUESTS OF THE CITY OR STATE REGARDING NTRACTOR'S RESPONSIBILITY TO APPROPRIATELY ORMWATER IN COMPLIANCE WITH LOCAL AND STATE						
IMENT TRAPS IF NECESSARY TO	IG DISTURBED, CONTRACTOR SHALL INSTALL O CONTROL SEDIMENT FROM LEAVING THE DETAIL FOR SEDIMENT TRAP IS E-2.40.						
T-CONSTRUCTION SOIL QUALI	TY AND DEPTH PER BMP T5.13 IS REQUIRED FOR DING IS COMPLETE.						
	ATE CLEARING LIMITS. D SEDIMENT CONTROL NOTES ON PAGE C02.01.						
	D SEDIMENT CONTROL NOTES ON FACE CO2.01.						
ON NOTES:							
-	res and appurtenances shall be demolished as ordance with local, state and federal						
	STOS OR OTHER HAZARDOUS MATERIALS SHALL BE CONTRACTOR IN ACCORDANCE WITH LOCAL, STATE		<b>AENTS</b>				
E REMOVAL SHALL BE COORDINATED WITH THE CITY FORESTER PRIOR TO REMOVAL ANY TREE OUTSIDE THE BOUNDARY OF THIS PROPERTY. WHERE TREES ARE MARKED PROTECTION, THEY SHALL BE PROTECTED TO THE DRIP LINE / ROOT ZONE BY A TREE DTECTION FENCE. NO GRADING SHALL OCCUR WITHIN THE TREE PROTECTION CE WITHOUT AUTHORIZATION FROM THE CITY'S FORESTER.			APARTMEN		S	ATION:	WOODLAND, WA
		OJECT NAME	S D		<b>AIDAN WILLIS</b>	CT LOC	DLAN
		PROJE	GOE	CLIENT	AIDAN	PROJE	MOO
DEMO 8	EROSION CONTROL LEGEND						
SF	SILT FENCE PER E-20						NO
	CONSTRUCTION ENTRANCE PER E-05					iew.	DESCRIPTION
E C C S	EXTG TREE TO BE REMOVED					Issued for review.	DESC
	PROTECT EXTG TREE TO REMAIN					ssued 1	
	INLET PROTECTION						ΠE
	A					6/24/2022	DATE
				$\triangleleft$	$\triangleleft$	∢	MARK
		PRC	DJE	CT:	22	2048	
			DESIGNED: DGS				
						DT	
		CHE SCA		ED:		GS	
		SCA		AS	NOI	ED	
		SHE	ET 1	TITLE			
	0 20' 40'	D	EM	OL	ITIC	N 8	&
NOTE: BAR IS ONE INCH ON ORIGINAL			EROSION CONTROL PLAN				
	NOTE: BAR IS ONE INCH ON ORIGINAL DRAWING, IF NOT ONE INCH ON THIS SHEET, ADJUST SCALE ACCORDINGLY.	SHE			∠∟ [	L/1	.1 4
PRELIMINI	ARY SITE PLAN REVIEW			201	.0	3	
· · · ∖ ⊑ ⊑ I / V \ I   N /		1					

You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C120: Temporary and Permanent Seeding

# **BMP C120: Temporary and Permanent Seeding**

#### Purpose

Seeding reduces erosion by stabilizing exposed soils. A well-established vegetative cover is one of the most effective methods of reducing erosion.

### **Conditions of Use**

Use seeding throughout the project on disturbed areas that have reached final grade or that will remain unworked for more than 30 days.

The optimum seeding windows for western Washington are April 1 through June 30 and September 1 through October 1.

Between July 1 and August 30 seeding requires irrigation until 75 percent grass cover is established.

Between October 1 and March 30 seeding requires a cover of mulch or an erosion control blanket until 75 percent grass cover is established.

Review all disturbed areas in late August to early September and complete all seeding by the end of September. Otherwise, vegetation will not establish itself enough to provide more than average protection.

Mulch is required at all times for seeding because it protects seeds from heat, moisture loss, and transport due to runoff. Mulch can be applied on top of the seed or simultaneously by hydroseeding. See <u>BMP C121: Mulching</u> for specifications.

Seed and mulch all disturbed areas not otherwise vegetated at final site stabilization. Final stabilization means the completion of all soil disturbing activities at the site and the establishment of a permanent vegetative cover, or equivalent permanent stabilization measures (such as pavement, riprap, gabions, or geotextiles) which will prevent erosion. See <u>BMP T5.13</u>: <u>Post-Construction Soil Quality and Depth</u>.

### **Design and Installation Specifications**

#### **General**

 Install channels intended for vegetation before starting major earthwork and hydroseed with a Bonded Fiber Matrix. For vegetated channels that will have high flows, install erosion control blankets over the top of hydroseed. Before allowing water to flow in vegetated channels, establish 75 percent vegetation cover. If vegetated channels cannot be established by seed before water flow; install sod in the channel bottom over top of hydromulch and erosion control blankets.

- Confirm the installation of all required surface water control measures to prevent seed from washing away.
- Hydroseed applications shall include a minimum of 1,500 pounds per acre of mulch with 3 percent tackifier.
   See <u>BMP C121: Mulching</u> for specifications.
- Areas that will have seeding only and not landscaping may need compost or meal-based mulch included in the hydroseed in order to establish vegetation. Re-install native topsoil on the disturbed soil surface before application. See <u>BMP T5.13</u>: Post-Construction Soil Quality and Depth.
- When installing seed via hydroseeding operations, only about 1/3 of the seed actually ends up in contact with the soil surface. This reduces the ability to establish a good stand of grass quickly. To overcome this, consider increasing seed quantities by up to 50 percent.
- Enhance vegetation establishment by dividing the hydromulch operation into two phases:
  - Phase 1- Install all seed and fertilizer with 25-30 percent mulch and tackifier onto soil in the first lift.
  - Phase 2- Install the rest of the mulch and tackifier over the first lift.
  - Or, enhance vegetation by:
    - Installing the mulch, seed, fertilizer, and tackifier in one lift.
    - Spread or blow straw over the top of the hydromulch at a rate of 800-1000 pounds per acre.
    - Hold straw in place with a standard tackifier.

Both of these approaches will increase cost moderately but will greatly improve and enhance vegetative establishment. The increased cost may be offset by the reduced need for:

- Irrigation.
- Reapplication of mulch.
- Repair of failed slope surfaces.

This technique works with standard hydromulch (1,500 pounds per acre minimum) and Bonded Fiber Matrix/ Mechanically Bonded Fiber Matrix (BFM/MBFMs) (3,000 pounds per acre minimum).

- Seed may be installed by hand if:
  - Temporary and covered by straw, mulch, or topsoil.
  - Permanent in small areas (usually less than 1 acre) and covered with mulch, topsoil, or erosion blankets.
- The seed mixes listed in <u>Table II-3.4</u>: <u>Temporary and Permanent Seed Mixes</u> include recommended mixes for both temporary and permanent seeding.
- Apply these mixes, with the exception of the wet area seed mix, at a rate of 120 pounds per acre. This rate can be reduced if soil amendments or slow-release fertilizers are used. Apply the wet area seed mix at a

rate of 60 pounds per acre.

Consult the local suppliers or the local conservation district for their recommendations. The appropriate mix depends on a variety of factors, including location, exposure, soil type, slope, and expected foot traffic. Alternative seed mixes approved by the local authority may be used, depending on the soil type and hydrology of the area.

#### Table II-3.4: Temporary and Permanent Seed Mixes

Common Name	Latin Name	% Weight	% Purity	% Germination	
Temporary Erosion Control Seed Mix					
A standard mix for areas requiring a temporary vegetative cover.					
Chewings or annual blue grass	Festuca rubra var. commutata or Poa anna	40	98	90	
Perennial rye	Lolium perenne	50	98	90	
Redtop or colonial bentgrass	Agrostis alba or Agrostis tenuis	5	92	85	
White dutch clover	Trifolium repens	5	98	90	
	Landscaping Seed Mix	·			
	A recommended mix for landscaping seed	ł.			
Perennial rye blend	Lolium perenne	70	98	90	
Chewings and red fescue blend	Festuca rubra var. commutata or Festuca rubra	30	98	90	
Low-Growing Turf Seed Mix					
A turf seed mix for dry situations where there is no need for watering. This mix requires very little maintenance.					
Dwarf tall fescue (several varieties)	Festuca arundinacea var.	45	98	90	
Dwarf perennial rye (Barclay)	Lolium perenne var. barclay	30	98	90	
Red fescue	Festuca rubra	20	98	90	
Colonial bentgrass	Agrostis tenuis	5	98	90	
Bioswale Seed Mix					
A seed mix for bioswales and other intermittently wet areas.					
Tall or meadow fescue	Festuca arundinacea or Festuca elatior	75-80	98	90	
Seaside/Creeping bentgrass	Agrostis palustris	10-15	92	85	

Common Name	Latin Name	% Weight	% Purity	% Germination		
Redtop bentgrass	Agrostis alba or Agrostis gigantea	5-10	90	80		
Wet Area Seed Mix A low-growing, relatively non-invasive seed mix appropriate for very wet areas that are not regulated wetlands. Consult						
Hydraulic Permit Authority (HPA) for seed mixes if applicable.						
Tall or meadow fescue	Festuca arundinacea or Festuca elatior	60-70	98	90		
Seaside/Creeping bentgrass	Agrostis palustris	10-15	98	85		
Meadow foxtail	Alepocurus pratensis	10-15	90	80		
Alsike clover	Trifolium hybridum	1-6	98	90		
Redtop bentgrass	Agrostis alba	1-6	92	85		
Meadow Seed Mix						
A recommended meadow seed mix for infrequently maintained areas or non-maintained areas where colonization by native plants is desirable. Likely applications include rural road and utility right-of-way. Seeding should take place in September or very early October in order to obtain adequate establishment prior to the winter months. Consider the appropriateness of clover, a fairly invasive species, in the mix. Amending the soil can reduce the need for clover.						
Redtop or Oregon bentgrass	Agrostis alba or Agrostis oregonensis	20	92	85		
Red fescue	Festuca rubra	70	98	90		
White dutch clover	Trifolium repens	10	98	90		

#### **Roughening and Rototilling**

- The seedbed should be firm and rough. Roughen all soil no matter what the slope. Track walk slopes before seeding if engineering purposes require compaction. Backblading or smoothing of slopes greater than 4H:1V is not allowed if they are to be seeded.
- Restoration-based landscape practices require deeper incorporation than that provided by a simple singlepass rototilling treatment. Wherever practical, initially rip the subgrade to improve long-term permeability, infiltration, and water inflow qualities. At a minimum, permanent areas shall use soil amendments to achieve organic matter and permeability performance defined in engineered soil/landscape systems. For systems that are deeper than 8 inches complete the rototilling process in multiple lifts, or prepare the engineered soil system per specifications and place to achieve the specified depth.

#### **Fertilizers**

• Conducting soil tests to determine the exact type and quantity of fertilizer is recommended. This will prevent the over-application of fertilizer.

- Organic matter is the most appropriate form of fertilizer because it provides nutrients (including nitrogen, phosphorus, and potassium) in the least water-soluble form.
- In general, use 10-4-6 N-P-K (nitrogen-phosphorus-potassium) fertilizer at a rate of 90 pounds per acre. Always use slow-release fertilizers because they are more efficient and have fewer environmental impacts. Do not add fertilizer to the hydromulch machine, or agitate, more than 20 minutes before use. Too much agitation destroys the slow-release coating.
- There are numerous products available that take the place of chemical fertilizers. These include several with seaweed extracts that are beneficial to soil microbes and organisms. If 100 percent cottonseed meal is used as the mulch in hydroseed, chemical fertilizer may not be necessary. Cottonseed meal provides a good source of long-term, slow-release, available nitrogen.

#### **Bonded Fiber Matrix and Mechanically Bonded Fiber Matrix**

- On steep slopes use Bonded Fiber Matrix (BFM) or Mechanically Bonded Fiber Matrix (MBFM) products. Apply BFM/MBFM products at a minimum rate of 3,000 pounds per acre with approximately 10 percent tackifier. Achieve a minimum of 95 percent soil coverage during application. Numerous products are available commercially. Most products require 24-36 hours to cure before rainfall and cannot be installed on wet or saturated soils. Generally, products come in 40-50 pound bags and include all necessary ingredients except for seed and fertilizer.
- Install products per manufacturer's instructions.
- BFMs and MBFMs provide good alternatives to blankets in most areas requiring vegetation establishment. Advantages over blankets include:
  - BFM and MBFMs do not require surface preparation.
  - Helicopters can assist in installing BFM and MBFMs in remote areas.
  - On slopes steeper than 2.5H:1V, blanket installers may require ropes and harnesses for safety.
  - Installing BFM and MBFMs can save at least \$1,000 per acre compared to blankets.

### Maintenance Standards

Reseed any seeded areas that fail to establish at least 75 percent cover (100 percent cover for areas that receive sheet or concentrated flows). If reseeding is ineffective, use an alternate method such as sodding, mulching, nets, or blankets.

- Reseed and protect by mulch any areas that experience erosion after achieving adequate cover. Reseed and protect by mulch any eroded area.
- Supply seeded areas with adequate moisture, but do not water to the extent that it causes runoff.

# Approved as Functionally Equivalent

#### BMP C120: Temporary and Permanent Seeding

Ecology has approved products as able to meet the requirements of this BMP. The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept these products, or may require additional testing prior to consideration for local use. Products that Ecology has approved as functionally equivalent are available for review on Ecology's website at:

https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Stormwater-permittee-guidanceresources/Emerging-stormwater-treatment-technologies

 Washington State Department of Ecology

 2019 Stormwater Management Manual for Western Washington (2019 SWMMWW)

 Publication No.19-10-021

You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C121: Mulching

# **BMP C121: Mulching**

#### **Purpose**

Mulching soils provides immediate temporary protection from erosion. Mulch also enhances plant establishment by conserving moisture, holding fertilizer, seed, and topsoil in place, and moderating soil temperatures. There are a variety of mulches that can be used. This section discusses only the most common types of mulch.

#### **Conditions of Use**

As a temporary cover measure, mulch should be used:

- For less than 30 days on disturbed areas that require cover.
- At all times for seeded areas, especially during the wet season and during the hot summer months.
- During the wet season on slopes steeper than 3H:1V with more than 10 feet of vertical relief.

Mulch may be applied at any time of the year and must be refreshed periodically.

For seeded areas, mulch may be made up of 100 percent:

- cottonseed meal;
- fibers made of wood, recycled cellulose, hemp, or kenaf;
- compost;
- or blends of these.

Tackifier shall be plant-based, such as guar or alpha plantago, or chemical-based such as polyacrylamide or polymers.

Generally, mulches come in 40-50 pound bags. Seed and fertilizer are added at time of application.

Recycled cellulose may contain polychlorinated biphenyl (PCBs). Ecology recommends that products should be evaluated for PCBs prior to use.

Refer to <u>BMP C126: Polyacrylamide (PAM) for Soil Erosion Protection</u> for conditions of use. PAM shall not be directly applied to water or allowed to enter a water body.

Any mulch or tackifier product used shall be installed per the manufacturer's instructions.

#### **Design and Installation Specifications**

#### BMP C121: Mulching

For mulch materials, application rates, and specifications, see <u>Table II-3.6: Mulch Standards and Guidelines</u>. Consult with the local supplier or the local conservation district for their recommendations. Increase the application rate until the ground is 95% covered (i.e. not visible under the mulch layer). Note: Thickness may be increased for disturbed areas in or near sensitive areas or other areas highly susceptible to erosion.

Where the option of "Compost" is selected, it should be a coarse compost that meets the size gradations listed in <u>Table II-3.5: Size Gradations of Compost as Mulch Material</u> when tested in accordance with Test Method 02.02-B found in *Test Methods for the Examination of Composting and Compost* (<u>Thompson, 2001</u>).

#### Table II-3.5: Size Gradations of Compost as Mulch Material

Sieve Size	Percent Passing
3"	100%
1"	90% - 100%
3/4"	70% - 100%
1/4"	40% - 100%

Mulch used within the ordinary high-water mark of surface waters should be selected to minimize potential flotation of organic matter. Composted organic materials have higher specific gravities (densities) than straw, wood, or chipped material. Consult the Hydraulic Permit Authority (HPA) for mulch mixes if applicable.

#### Maintenance Standards

The thickness of the mulch cover must be maintained.

Any areas that experience erosion shall be remulched and/or protected with a net or blanket. If the erosion problem is drainage related, then the problem shall be fixed and the eroded area remulched.

Mulch Material	Guideline	Description
Straw	Quality Standards	Air-dried; free from undesirable seed and coarse material.
	Application Rates	2"-3" thick; 5 bales per 1,000 sf or 2-3 tons per acre

#### **Table II-3.6: Mulch Standards and Guidelines**

Mulch Material	Guideline	Description	
	Remarks	Cost-effective protection when applied with adequate thickness. Hand-application generally requires greater thickness than blown straw. The thickness of straw may be reduced by half when used in conjunction with seeding. In windy areas straw must be held in place by crimping, using a tackifier, or covering with netting. Blown straw always has to be held in place with a tackifier as even light winds will blow it away. Straw, however, has several deficiencies that should be considered when selecting mulch materials. It often introduces and/or encourages the propagation of weed species and it has no significant long-term benefits It should also not be used within the ordinary high-water elevation of surface waters (due to flotation).	
Hydromulch	Quality Standards	No growth inhibiting factors.	
	Application Rates	Approx. 35-45 lbs per 1,000 sf or 1,500 - 2,000 lbs per acre	
	Remarks	Shall be applied with hydromulcher. Shall not be used without seed and tackifier unless the application rate is at least doubled. Fibers longer than about 3/4 - 1 inch clog hydromulch equipment. Fibers should be kept to less than 3/4 inch.	
Compost	Quality Standards	No visible water or dust during handling. Must be produced per <u>WAC 173-350</u> , Solid Waste Handling Standards, but may have up to 35% biosolids.	
	Application Rates	2" thick min.; approx. 100 tons per acre (approx. 750 lbs per cubic yard)	
	Remarks	More effective control can be obtained by increasing thickness to 3". Excellent mulch for protecting final grades until landscaping because it can be directly seeded or tilled into soil as an amendment. Compost used for mulch has a coarser size gradation than compost used for <u>BMP C125: Topsoiling / Composting</u> or <u>BMP T5.13: Post-Construction Soil</u> <u>Quality and Depth</u> . It is more stable and practical to use in wet areas and during rainy weather conditions. Do not use near wetlands or near phosphorous impaired water bodies.	
Chipped Site Vegetation	Quality Standards	Gradations from fines to 6 inches in length for texture, variation, and interlocking properties. Include a mix of various sizes so that the average size is between 2- and 4-inches.	
	Application Rates	2" thick min.;	
	Remarks	This is a cost-effective way to dispose of debris from clearing and grubbing, and it eliminates the problems associated with burning. Generally, it should not be used on slopes above approx. 10% because of its tendency to be transported by runoff. It is not recommended within 200 feet of surface waters. If permanent seeding or planting is expected shortly after mulch, the decomposition of the chipped vegetation may tie up nutrients important to grass establishment. Note: thick application of this material over existing grass, herbaceous species, and some groundcovers could smother and kill vegetation.	
Wood- Based Mulch	Quality Standards	No visible water or dust during handling. Must be purchased from a supplier with a Solid Waste Handling Permit or one exempt from solid waste regulations.	

Mulch Material	Guideline	Description
	Application Rates	2" thick min.; approx. 100 tons per acre (approx. 750 lbs. per cubic yard)
	Remarks	This material is often called "wood straw" or "hog fuel". The use of mulch ultimately improves the organic matter in the soil. Special caution is advised regarding the source and composition of wood-based mulches. Its preparation typically does not provide any weed seed control, so evidence of residual vegetation in its composition or known inclusion of weed plants or seeds should be monitored and prevented (or minimized).
	Quality Standards	A blend of loose, long, thin wood pieces derived from native conifer or deciduous trees with high length-to-width ratio.
Wood	Application Rates	2" thick min.
Strand Mulch	Remarks	Cost-effective protection when applied with adequate thickness. A minimum of 95-percent of the wood strand shall have lengths between 2 and 10-inches, with a width and thickness between 1/16 and 1/2-inches. The mulch shall not contain resin, tannin, or other compounds in quantities that would be detrimental to plant life. Sawdust or wood shavings shall not be used as mulch. [Specification 9-14.4(4) from the <i>Standard Specifications for Road, Bridge, and Municipal Construction</i> (WSDOT, 2016)

#### Washington State Department of Ecology

2019 Stormwater Management Manual for Western Washington (2019 SWMMWW)

Publication No.19-10-021

You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C123: Plastic Covering

## **BMP C123: Plastic Covering**

## **Purpose**

Plastic covering provides immediate, short-term erosion protection to slopes and disturbed areas.

## **Conditions of Use**

Plastic covering may be used on disturbed areas that require cover measures for less than 30 days, except as stated below.

- Plastic is particularly useful for protecting cut and fill slopes and stockpiles. However, the relatively rapid breakdown of most polyethylene sheeting makes it unsuitable for applications greater than six months.
- Due to rapid runoff caused by plastic covering, do not use this method upslope of areas that might be adversely impacted by concentrated runoff. Such areas include steep and/or unstable slopes.
- Plastic sheeting may result in increased runoff volumes and velocities, requiring additional on-site measures to counteract the increases. Creating a trough with wattles or other material can convey clean water away from these areas.
- To prevent undercutting, trench and backfill rolled plastic covering products.
- Although the plastic material is inexpensive to purchase, the cost of installation, maintenance, removal, and disposal add to the total costs of this BMP.
- Whenever plastic is used to protect slopes, install water collection measures at the base of the slope. These
  measures include plastic-covered berms, channels, and pipes used to convey clean rainwater away from
  bare soil and disturbed areas. Do not mix clean runoff from a plastic covered slope with dirty runoff from a
  project.
- Other uses for plastic include:
  - Temporary ditch liner.
  - Pond liner in temporary sediment pond.
  - Liner for bermed temporary fuel storage area if plastic is not reactive to the type of fuel being stored.
  - Emergency slope protection during heavy rains.
  - Temporary drainpipe ("elephant trunk") used to direct water.

## **Design and Installation Specifications**

- Plastic slope cover must be installed as follows:
  - 1. Run plastic up and down the slope, not across the slope.
  - 2. Plastic may be installed perpendicular to a slope if the slope length is less than 10 feet.
  - 3. Provide a minimum of 8-inch overlap at the seams.
  - 4. On long or wide slopes, or slopes subject to wind, tape all seams.
  - 5. Place plastic into a small (12-inch wide by 6-inch deep) slot trench at the top of the slope and backfill with soil to keep water from flowing underneath.
  - 6. Place sand filled burlap or geotextile bags every 3 to 6 feet along seams and tie them together with twine to hold them in place.
  - 7. Inspect plastic for rips, tears, and open seams regularly and repair immediately. This prevents high velocity runoff from contacting bare soil, which causes extreme erosion.
  - 8. Sandbags may be lowered into place tied to ropes. However, all sandbags must be staked in place.
- Plastic sheeting shall have a minimum thickness of 6 mil.
- If erosion at the toe of a slope is likely, a gravel berm, riprap, or other suitable protection shall be installed at the toe of the slope in order to reduce the velocity of runoff.

### Maintenance Standards

- Torn sheets must be replaced and open seams repaired.
- Completely remove and replace the plastic if it begins to deteriorate due to ultraviolet radiation.
- Completely remove plastic when no longer needed.
- Dispose of old tires used to weight down plastic sheeting appropriately.

### Approved as Functionally Equivalent

Ecology has approved products as able to meet the requirements of this BMP. The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept these products, or may require additional testing prior to consideration for local use. Products that Ecology has approved as functionally equivalent are available for review on Ecology's website at:

https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Stormwater-permittee-guidanceresources/Emerging-stormwater-treatment-technologies

#### Washington State Department of Ecology 2019 Stormwater Management Manual for Western Washington (2019 SWMMWW)

BMP C123: Plastic Covering

Publication No.19-10-021

You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C140: Dust Control

## **BMP C140: Dust Control**

## **Purpose**

Dust control prevents wind transport of dust from disturbed soil surfaces onto roadways, drainage ways, and surface waters.

## **Conditions of Use**

Use dust control in areas (including roadways) subject to surface and air movement of dust where on-site or offsite impacts to roadways, drainage ways, or surface waters are likely.

## **Design and Installation Specifications**

- Vegetate or mulch areas that will not receive vehicle traffic. In areas where planting, mulching, or paving is impractical, apply gravel or landscaping rock.
- Limit dust generation by clearing only those areas where immediate activity will take place, leaving the remaining area(s) in the original condition. Maintain the original ground cover as long as practical.
- Construct natural or artificial windbreaks or windscreens. These may be designed as enclosures for small dust sources.
- Sprinkle the site with water until the surface is wet. Repeat as needed. To prevent carryout of mud onto the street, refer to <u>BMP C105</u>: <u>Stabilized Construction Access</u> and <u>BMP C106</u>: <u>Wheel Wash</u>.
- Irrigation water can be used for dust control. Irrigation systems should be installed as a first step on sites where dust control is a concern.
- Spray exposed soil areas with a dust palliative, following the manufacturer's instructions and cautions regarding handling and application. Used oil is prohibited from use as a dust suppressant. Local governments may approve other dust palliatives such as calcium chloride or PAM.
- PAM (<u>BMP C126: Polyacrylamide (PAM) for Soil Erosion Protection</u>) added to water at a rate of 0.5 pounds per 1,000 gallons of water per acre and applied from a water truck is more effective than water alone. This is due to increased infiltration of water into the soil and reduced evaporation. In addition, small soil particles are bonded together and are not as easily transported by wind. Adding PAM may reduce the quantity of water needed for dust control. Note that the application rate specified here applies to this BMP, and is not the same application rate that is specified in <u>BMP C126: Polyacrylamide (PAM) for Soil Erosion Protection</u>, but the downstream protections still apply.

#### BMP C140: Dust Control

Refer to <u>BMP C126: Polyacrylamide (PAM) for Soil Erosion Protection</u> for conditions of use. PAM shall not be directly applied to water or allowed to enter a water body.

- Contact your local Air Pollution Control Authority for guidance and training on other dust control measures. Compliance with the local Air Pollution Control Authority constitutes compliance with this BMP.
- Use vacuum street sweepers.
- Remove mud and other dirt promptly so it does not dry and then turn into dust.
- Techniques that can be used for unpaved roads and lots include:
  - Lower speed limits. High vehicle speed increases the amount of dust stirred up from unpaved roads and lots.
  - Upgrade the road surface strength by improving particle size, shape, and mineral types that make up the surface and base materials.
  - Add surface gravel to reduce the source of dust emission. Limit the amount of fine particles (those smaller than .075 mm) to 10 to 20 percent.
  - Use geotextile fabrics to increase the strength of new roads or roads undergoing reconstruction.
  - Encourage the use of alternate, paved routes, if available.
  - Apply chemical dust suppressants using the admix method, blending the product with the top few inches of surface material. Suppressants may also be applied as surface treatments.
  - Limit dust-causing work on windy days.
  - Pave unpaved permanent roads and other trafficked areas.

## **Maintenance Standards**

Respray area as necessary to keep dust to a minimum.

Washington State Department of Ecology 2019 Stormwater Management Manual for Western Washington (2019 SWMMWW) Publication No.19-10-021 You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C151: Concrete Handling

## **BMP C151: Concrete Handling**

### **Purpose**

Concrete work can generate process water and slurry that contain fine particles and high pH, both of which can violate water quality standards in the receiving water. Concrete spillage or concrete discharge to waters of the State is prohibited. Use this BMP to minimize and eliminate concrete, concrete process water, and concrete slurry from entering waters of the State.

## **Conditions of Use**

Any time concrete is used, utilize these management practices. Concrete construction project components include, but are not limited to:

- Curbs
- Sidewalks
- Roads
- Bridges
- Foundations
- Floors
- Runways

Disposal options for concrete, in order of preference are:

- 1. Off-site disposal
- 2. Concrete wash-out areas (see BMP C154: Concrete Washout Area)
- 3. De minimus washout to formed areas awaiting concrete

### **Design and Installation Specifications**

 Wash concrete truck drums at an approved off-site location or in designated concrete washout areas only. Do not wash out concrete trucks onto the ground (including formed areas awaiting concrete), or into storm drains, open ditches, streets, or streams. Refer to <u>BMP C154: Concrete Washout Area</u> for information on concrete washout areas.

#### BMP C151: Concrete Handling

- Return unused concrete remaining in the truck and pump to the originating batch plant for recycling. Do not dump excess concrete on site, except in designated concrete washout areas as allowed in <u>BMP C154: Concrete Washout Area</u>.
- Wash small concrete handling equipment (e.g. hand tools, screeds, shovels, rakes, floats, trowels, and wheelbarrows) into designated concrete washout areas or into formed areas awaiting concrete pour.
- At no time shall concrete be washed off into the footprint of an area where an infiltration feature will be installed.
- Wash equipment difficult to move, such as concrete paving machines, in areas that do not directly drain to natural or constructed stormwater conveyance or potential infiltration areas.
- Do not allow washwater from areas, such as concrete aggregate driveways, to drain directly (without detention or treatment) to natural or constructed stormwater conveyances.
- Contain washwater and leftover product in a lined container when no designated concrete washout areas (or formed areas, allowed as described above) are available. Dispose of contained concrete and concrete washwater (process water) properly.
- Always use forms or solid barriers for concrete pours, such as pilings, within 15-feet of surface waters.
- Refer to <u>BMP C252: Treating and Disposing of High pH Water</u> for pH adjustment requirements.
- Refer to the Construction Stormwater General Permit (CSWGP) for pH monitoring requirements if the project involves one of the following activities:
  - Significant concrete work (as defined in the CSWGP).
  - The use of soils amended with (but not limited to) Portland cement-treated base, cement kiln dust or fly ash.
  - Discharging stormwater to segments of water bodies on the 303(d) list (Category 5) for high pH.

### Maintenance Standards

Check containers for holes in the liner daily during concrete pours and repair the same day.

#### Washington State Department of Ecology

2019 Stormwater Management Manual for Western Washington (2019 SWMMWW) Publication No.19-10-021 You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C152: Sawcutting and Surfacing Pollution Prevention

## **BMP C152: Sawcutting and Surfacing Pollution Prevention**

## **Purpose**

Sawcutting and surfacing operations generate slurry and process water that contains fine particles and high pH (concrete cutting), both of which can violate the water quality standards in the receiving water. Concrete spillage or concrete discharge to waters of the State is prohibited. Use this BMP to minimize and eliminate process water and slurry created through sawcutting or surfacing from entering waters of the State.

## **Conditions of Use**

Utilize these management practices anytime sawcutting or surfacing operations take place. Sawcutting and surfacing operations include, but are not limited to:

- Sawing
- Coring
- Grinding
- Roughening
- Hydro-demolition
- Bridge and road surfacing

## **Design and Installation Specifications**

- Vacuum slurry and cuttings during cutting and surfacing operations.
- Slurry and cuttings shall not remain on permanent concrete or asphalt pavement overnight.
- Slurry and cuttings shall not drain to any natural or constructed drainage conveyance including stormwater systems. This may require temporarily blocking catch basins.
- Dispose of collected slurry and cuttings in a manner that does not violate ground water or surface water quality standards.
- Do not allow process water generated during hydro-demolition, surface roughening or similar operations to drain to any natural or constructed drainage conveyance including stormwater systems. Dispose of process water in a manner that does not violate ground water or surface water quality standards.

 Handle and dispose of cleaning waste material and demolition debris in a manner that does not cause contamination of water. Dispose of sweeping material from a pick-up sweeper at an appropriate disposal site.

## Maintenance Standards

Continually monitor operations to determine whether slurry, cuttings, or process water could enter waters of the state. If inspections show that a violation of water quality standards could occur, stop operations and immediately implement preventive measures such as berms, barriers, secondary containment, and/or vacuum trucks.

Washington State Department of Ecology 2019 Stormwater Management Manual for Western Washington (2019 SWMMWW) Publication No.19-10-021 You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C153: Material Delivery, Storage, and Containment

## **BMP C153: Material Delivery, Storage, and Containment**

## **Purpose**

Prevent, reduce, or eliminate the discharge of pollutants to the stormwater system or watercourses from material delivery and storage. Minimize the storage of hazardous materials on-site, store materials in a designated area, and install secondary containment.

## **Conditions of Use**

Use at construction sites with delivery and storage of the following materials:

- Petroleum products such as fuel, oil and grease
- Soil stabilizers and binders (e.g., Polyacrylamide)
- Fertilizers, pesticides and herbicides
- Detergents
- Asphalt and concrete compounds
- Hazardous chemicals such as acids, lime, adhesives, paints, solvents, and curing compounds
- Any other material that may be detrimental if released to the environment

## **Design and Installation Specifications**

- The temporary storage area should be located away from vehicular traffic, near the construction entrance(s), and away from waterways or storm drains.
- Safety Data Sheets (SDS) should be supplied for all materials stored. Chemicals should be kept in their original labeled containers.
- · Hazardous material storage on-site should be minimized.
- Hazardous materials should be handled as infrequently as possible.
- During the wet weather season (Oct 1 April 30), consider storing materials in a covered area.
- Materials should be stored in secondary containments, such as an earthen dike, horse trough, or even a children's wading pool for non-reactive materials such as detergents, oil, grease, and paints. Small amounts of material may be secondarily contained in "bus boy" trays or concrete mixing trays.

- Do not store chemicals, drums, or bagged materials directly on the ground. Place these items on a pallet and, when possible, within secondary containment.
- If drums must be kept uncovered, store them at a slight angle to reduce ponding of rainwater on the lids to reduce corrosion. Domed plastic covers are inexpensive and snap to the top of drums, preventing water from collecting.
- Liquids, petroleum products, and substances listed in 40 CFR Parts 110, 117, or 302 shall be stored in approved containers and drums and shall not be overfilled. Containers and drums shall be stored in temporary secondary containment facilities.
- Temporary secondary containment facilities shall provide for a spill containment volume able to contain 10% of the total enclosed container volume of all containers, or 110% of the capacity of the largest container within its boundary, whichever is greater.
- Secondary containment facilities shall be impervious to the materials stored therein for a minimum contact time of 72 hours.
- Sufficient separation should be provided between stored containers to allow for spill cleanup and emergency response access.
- During the wet weather season (Oct 1 April 30), each secondary containment facility shall be covered during non-working days, prior to and during rain events.
- Keep material storage areas clean, organized and equipped with an ample supply of appropriate spill cleanup material (spill kit).
- The spill kit should include, at a minimum:
  - 1-Water Resistant Nylon Bag
  - 3-Oil Absorbent Socks 3"x 4'
  - 2-Oil Absorbent Socks 3"x 10'
  - 12-Oil Absorbent Pads 17"x19"
  - 1-Pair Splash Resistant Goggles
  - 3-Pair Nitrile Gloves
  - 10-Disposable Bags with Ties
  - Instructions

### Maintenance Standards

• Secondary containment facilities shall be maintained free of accumulated rainwater and spills. In the event of spills or leaks, accumulated rainwater and spills shall be collected and placed into drums. These liquids

shall be handled as hazardous waste unless testing determines them to be non-hazardous.

• Re-stock spill kit materials as needed.

#### Washington State Department of Ecology

2019 Stormwater Management Manual for Western Washington (2019 SWMMWW) Publication No.19-10-021 You are here: <u>2019 SWMMWW</u> > <u>Volume II - Construction Stormwater Pollution Prevention</u> > <u>II-3 Construction Stormwater BMPs</u> > BMP C154: Concrete Washout Area

## **BMP C154: Concrete Washout Area**

## **Purpose**

Prevent or reduce the discharge of pollutants from concrete waste to stormwater by conducting washout off-site, or performing on-site washout in a designated area.

## **Conditions of Use**

Concrete washout areas are implemented on construction projects where:

- Concrete is used as a construction material
- It is not possible to dispose of all concrete wastewater and washout off-site (ready mix plant, etc.).
- Concrete truck drums are washed on-site.

Note that auxiliary concrete truck components (e.g. chutes and hoses) and small concrete handling equipment (e.g. hand tools, screeds, shovels, rakes, floats, trowels, and wheelbarrows) may be washed into formed areas awaiting concrete pour.

At no time shall concrete be washed off into the footprint of an area where an infiltration feature will be installed.

### **Design and Installation Specifications**

#### **Implementation**

- Perform washout of concrete truck drums at an approved off-site location or in designated concrete washout areas only.
- Do not wash out concrete onto non-formed areas, or into storm drains, open ditches, streets, or streams.
- Wash equipment difficult to move, such as concrete paving machines, in areas that do not directly drain to natural or constructed stormwater conveyance or potential infiltration areas.
- Do not allow excess concrete to be dumped on-site, except in designated concrete washout areas as allowed above.
- Concrete washout areas may be prefabricated concrete washout containers, or self-installed structures (above-grade or below-grade).
- Prefabricated containers are most resistant to damage and protect against spills and leaks. Companies may offer delivery service and provide regular maintenance and disposal of solid and liquid waste.

- If self-installed concrete washout areas are used, below-grade structures are preferred over above-grade structures because they are less prone to spills and leaks.
- Self-installed above-grade structures should only be used if excavation is not practical.
- Concrete washout areas shall be constructed and maintained in sufficient quantity and size to contain all liquid and concrete waste generated by washout operations.

#### **Education**

- Discuss the concrete management techniques described in this BMP with the ready-mix concrete supplier before any deliveries are made.
- Educate employees and subcontractors on the concrete waste management techniques described in this BMP.
- Arrange for the contractor's superintendent or Certified Erosion and Sediment Control Lead (CESCL) to oversee and enforce concrete waste management procedures.
- A sign should be installed adjacent to each concrete washout area to inform concrete equipment operators to utilize the proper facilities.

#### **Contracts**

Incorporate requirements for concrete waste management into concrete supplier and subcontractor agreements.

#### Location and Placement

- Locate concrete washout areas at least 50 feet from sensitive areas such as storm drains, open ditches, water bodies, or wetlands.
- Allow convenient access to the concrete washout area for concrete trucks, preferably near the area where the concrete is being poured.
- If trucks need to leave a paved area to access the concrete washout area, prevent track-out with a pad of
  rock or quarry spalls (see <u>BMP C105</u>: <u>Stabilized Construction Access</u>). These areas should be far enough
  away from other construction traffic to reduce the likelihood of accidental damage and spills.
- The number of concrete washout areas you install should depend on the expected demand for storage capacity.
- On large sites with extensive concrete work, concrete washout areas should be placed in multiple locations for ease of use by concrete truck drivers.

#### Concrete Truck Washout Procedures

• Washout of concrete truck drums shall be performed in designated concrete washout areas only.

• Concrete washout from concrete pumper bins can be washed into concrete pumper trucks and discharged into designated concrete washout areas or properly disposed of off-site.

#### **Concrete Washout Area Installation**

- Concrete washout areas should be constructed as shown in the figures below, with a recommended minimum length and minimum width of 10 ft, but with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations.
- Plastic lining material should be a minimum of 10 mil polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.
- Lath and flagging should be commercial type.
- Liner seams shall be installed in accordance with manufacturers' recommendations.
- Soil base shall be prepared free of rocks or other debris that may cause tears or holes in the plastic lining material.

## Maintenance Standards

#### **Inspection and Maintenance**

- Inspect and verify that concrete washout areas are in place prior to the commencement of concrete work.
- Once concrete wastes are washed into the designated washout area and allowed to harden, the concrete should be broken up, removed, and disposed of per applicable solid waste regulations. Dispose of hardened concrete on a regular basis.
- During periods of concrete work, inspect the concrete washout areas daily to verify continued performance.
  - Check overall condition and performance.
  - Check remaining capacity (% full).
  - If using self-installed concrete washout areas, verify plastic liners are intact and sidewalls are not damaged.
  - If using prefabricated containers, check for leaks.
- Maintain the concrete washout areas to provide adequate holding capacity with a minimum freeboard of 12 inches.
- Concrete washout areas must be cleaned, or new concrete washout areas must be constructed and ready for use once the concrete washout area is 75% full.
- If the concrete washout area is nearing capacity, vacuum and dispose of the waste material in an approved manner.

- Do not discharge liquid or slurry to waterways, storm drains or directly onto ground.
- Do not discharge to the sanitary sewer without local approval.
- Place a secure, non-collapsing, non-water collecting cover over the concrete washout area prior to predicted wet weather to prevent accumulation and overflow of precipitation.
- Remove and dispose of hardened concrete and return the structure to a functional condition. Concrete may be reused on-site or hauled away for disposal or recycling.
- When you remove materials from a self-installed concrete washout area, build a new structure; or, if the
  previous structure is still intact, inspect for signs of weakening or damage, and make any necessary repairs.
  Re-line the structure with new plastic after each cleaning.


#### Removal of Concrete Washout Areas

- When concrete washout areas are no longer required for the work, the hardened concrete, slurries and liquids shall be removed and properly disposed of.
- Materials used to construct concrete washout areas shall be removed from the site of the work and disposed of or recycled.
- Holes, depressions or other ground disturbance caused by the removal of the concrete washout areas shall be backfilled, repaired, and stabilized to prevent erosion.

#### Figure II-3.7: Concrete Washout Area with Wood Planks



#### Figure II-3.8: Concrete Washout Area with Straw Bales



pdf download

#### Figure II-3.9: Prefabricated Concrete Washout Container w/Ramp



Washington State Department of Ecology 2019 Stormwater Management Manual for Western Washington (2019 SWMMWW) Publication No.19-10-021

## **Construction Stormwater Site Inspection Form**

Project Name	Permit #	Inspection Date		Time			
Name of Certified Erosion Sedime Print Name:	nt Control Lead (CESCL) or qua	alified inspector if <i>less thar</i>	n one acre				
Approximate rainfall amount sind	ce the last inspection (in inche	es):					
Approximate rainfall amount in t	he last 24 hours (in inches):						
Current Weather Clear Cl	oudy 🔄 Mist 🔄 Rain 🗌	Wind Fog					
A. Type of inspection: We	ekly Post Storm Event	Other					
B. Phase of Active Construction (a	heck all that apply):						
Pre Construction/installation of eros controls Concrete pours	Verti		Utilities	ure/storm/roads			
Offsite improvements		struction/buildings temporary stabilized	Final stabil	ization			
C. Questions:							
<ol> <li>Were all areas of construction</li> <li>Did you observe the presence sheen</li> </ol>	• · ·		Yes Yes	No No			
<ul> <li>3. Was a water quality sample taken during inspection? (<i>refer to permit conditions S4 &amp; S5</i>)</li> <li>4. Was there a turbid discharge 250 NTU or greater, or Transparency 6 cm or less?*</li> <li>5. If yes to #4 was it reported to Ecology?</li> <li>6. Is pH sampling required? pH range required is 6.5 to 8.5.</li> <li>Yes No</li> </ul>							

If answering yes to a discharge, describe the event. Include when, where, and why it happened; what action was taken, and when.

\*If answering yes to # 4 record NTU/Transparency with continual sampling daily until turbidity is 25 NTU or less/ transparency is 33 cm or greater.

Sampling Results:

Date:

Parameter	Method (circle one)	Result			Other/Note
		NTU cm pH		рН	
Turbidity	tube, meter, laboratory				
pН	Paper, kit, meter				

## D. Check the observed status of all items. Provide "Action Required "details and dates.

Element #	Inspection		BMPs spect		BMP needs maintenance	BMP failed	Action required
			no	n/a			(describe in section F)
1 Clearing Limits	Before beginning land disturbing activities are all clearing limits, natural resource areas (streams, wetlands, buffers, trees) protected with barriers or similar BMPs? (high visibility recommended)						
2 Construction Access	Construction access is stabilized with quarry spalls or equivalent BMP to prevent sediment from being tracked onto roads? Sediment tracked onto the road way was cleaned thoroughly at the end of the day or more frequent as necessary.						
3 Control Flow Rates	Are flow control measures installed to control stormwater volumes and velocity during construction and do they protect downstream properties and waterways from erosion? If permanent infiltration ponds are used for flow control during						
	construction, are they protected from siltation?						
4 Sediment Controls	All perimeter sediment controls (e.g. silt fence, wattles, compost socks, berms, etc.) installed, and maintained in accordance with the Stormwater Pollution Prevention Plan (SWPPP).						
	Sediment control BMPs (sediment ponds, traps, filters etc.) have been constructed and functional as the first step of grading. Stormwater runoff from disturbed areas is directed to sediment removal BMP.						
5 Stabilize Soils	Have exposed un-worked soils been stabilized with effective BMP to prevent erosion and sediment deposition?						

## **Construction Stormwater Site Inspection Form**

yes no n/a (describe i	Element #	Inspection		BMP: spect		BMP needs maintenance	BMP failed	Action required
Stabilize Soits       protected with sediment trapping measures and located away from drain linkt, waterways, and drainage channels?         Have soits been stabilized at the end of the shift, before a holiday or weekend if needed based on the weather forecast?       Image: transmitter of the shift based on the weather forecast?         6       Have soits been stabilized at the end of the shift, before a holiday or weekend if severate away from slopes and been diverted away from slopes and swater been diverted away from slopes and swaters are sufficient of stabilized and species on sides?         6       Have slote daway from slopes and disturbed areas with interceptor dikes, pipes and or wales?         1       Is off-site storm water managed separately from stormwater generated on the site?         a bend waterial placed on uphill side of trenches considerations?       Have check dawas been placed at regular intervals within constructed channels that are cut down a slope?         7       Storm drain within the influence of the project protected?         7       Storm drain within the influence of the project protected?         8       Have all on-site conveyance channels been designed, constructed and stabilized to prevent erosion of of outlets, adjacent stream banks, slopes and downstream conveyance systems?         9       Are waste materials and demolition detarmation of stormwater?         9       Are waste materials and demolition detarmation of stormwater?         9       Are waste materials and demolition detarmaterial perover the provided capable of containing 110% of the volume?				· ·				(describe in section F)
Cont.       inlet, waterways, and drainage channels?	5	Are stockpiles stabilized from erosion,						
inlet, waterways, and drainage channels?	Stabilize Soils	protected with sediment trapping						
channels?	Cont.							
Have soils been stabilized at the end of the shift, before a holiday or weekend if needed based on the weather forecast?       Image: Construct of the solution of the								
# the shift, before a holiday or weekend       if needed based on the weather       if needed based on the weather         6       been diverted away from slopes and       if needed based on the weather         7       been diverted away from slopes and       if needed based on swales?         8       is off-site storm water managed       if needed based on uphill         9       Storm data material placed on uphill       if needed based on a slope?         11       seconsiderations?       if needed based on a slope?         7       Storm drain inlets made operable       if needed based on a slope?         7       Storm drain inlets made operable       if needed based on site conveyance channels         8       Have all on-site conveyance channels       if needed based for one protected?         8       Have all on-site conveyance channels       if needed based for one protected?         9       Are existing storm drains within the influence of the project protected?       if needed based for one protected?         9       Are existing addrametrial placed to prevent erosion from of outlets, adjacent streme basks, slopes and downstream conveyance systems?       if needed based for one protected placed for prevent erosion of outlets, adjacent streme basks, slopes and downstream conveyance systems?       if needed based for or all the metrial?         9       Are existing add disposed of to prevent erosion of outlets, adjacent streme basks, slopes								
if needed based on the weather       image: construction of provided and provided prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?         9       Are waste materials and demolition disposed of to prevent constructed and provided construction are protected.         8       Have allo norstructed and provided provided provided construction are protected.         9       Are existing storm drains within the influence of the project protected?         10       Stabilized to prevent erosion from antally and space to provide and provided constructed and provided provided provided provided constructed and provided constend and proventer provided constructed and provided constructed an								
forecast?Image: state in the sta								
6       been diverted away from slopes and disturbed areas with interceptor dikes, pipes and or swales?       Image: Construction of the start of the s								
Protect       disturbed areas with interceptor dikes,		Has stormwater and ground water						
Slopes       pipes and or swales?       Image: separately from stormwater generated on the site?       Image: separa	6	been diverted away from slopes and						
Is off-site storm water managed separately from stormwater generated on the site?       Is excavated material placed on uphill side of trenches consistent with safety and space considerations?         Have check dams been placed at regular intervals within constructed channels that are cut down a slope?       Image: Construct of the project protected.         7       Storm drain inlets made operable during construction are protected.       Image: Construct of the project protected?         8       Have close on provided and influence of the project protected?       Image: Construct of the project protected?         8       Have all on-site conveyance channels stabilized to prevent erosion from of outlets, adjacent stream banks, slopes and downstream conveyance systems?       Image: Constructed and stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?       Image: Construct on all chemicals, liquid products, petroleum provided corable of containing 110% of the volume?         9       Are waste material?       Image: Containing 110% of the volume?       Image: Containing 10% of the volume?	Protect	disturbed areas with interceptor dikes,						
separately from stormwater generated on the site?       Image: separately from stormwater generated on the site?       Image: separately from stormwater generated on the site?         Is excavated material placed on uphill side of trenches consistent with safety and space considerations?       Image: separately from stormwater generated and space considerations?         Have check dams been placed at regular intervals within constructed channels that are cut down a slope?       Image: separately from stormwater generated channels that are cut down a slope?         Jorin Inlets       during construction are protected.       Image: separately from stormwater generated during construction are protected?         Are existing storm drains within the influence of the project protected?       Image: separately from stormwater generated during constructed and stabilized to prevent erosion from expected peak flows?       Image: separately from stormwater generated downs?         9       Are waste materials and demolition of outlets, adjacent stream banks, slopes and downstream convegance systems?       Image: separately from stormwater?         9       Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater?       Image: separately from stormwater?         9       Are waste material?       Image: separately from stormwater?       Image: separately from stormwater?         9       Are waste material?       Image: separately from stormwater?       Image: separately from stormwater?         9       Are waste material fram banks, slopes and downstr	Slopes	pipes and or swales?						
on the site?       Image: consider and placed on uphill side of trenches consistent with safety and space considerations?       Image: considerations?         Have check dams been placed at regular intervals within constructed channels that are cut down a slope?       Image: construct and place at the stabilized of the space considerations?         7       Storm drain inlets made operable during construction are protected.       Image: construct and slope?         8       Have all on-site conveyance channels been designed, constructed and stabilized to prevent erosion from expected peak flows?       Image: construct and place at the space consideration of outlets, adjacent stream banks, slopes and downstream conveyance systems?         9       Are waste materials and demolition debris handled and disposed of to provent contamination of stormwater?       Image: construct and products, perforemation?         Pollutants       Has cover been provided for all chemicals, liquid products, perforemation?       Image: construct and products, perforemation?         Has cover been provided for all chemicals, liquid products, perforemation?       Image: construct and products, perforemation?         Were contaminated surfaces cleaned immediately after a spill incident?       Image: construct and provent         Were BMPs used to prevent       Image: construct and provent       Image: construct and provent		Is off-site storm water managed						
side of trenches consistent with safety and space considerations?       Image: considerations of the project or considerations of the project protected.         Have check dams been placed at regular intervals within constructed channels that are cut down a slope?       Image: construction are protected.         T       Storm drain inlets made operable during construction are protected.       Image: construction are protected.         Are existing storm drains within the influence of the project protected?       Image: construction are protected.         8       Have all on-site conveyance channels       Image: construction are protected.         Channel and Outlets       been designed, constructed and stabilized to prevent erosion from expected peak flows?       Image: constructed and expected peak flows?         9       Are waste materials and demolition of outlets, adjacent stream banks, slopes and downstream conveyance systems?       Image: constructed and dispused of to prevent contamination of stormwater?         9       Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater?       Image: construct, petroleum provided capable of containing 110% of the volume?         Has secondary containment been provided capable of containing 110% of the volume?       Image: containing 10% of the volume?       Image: containing 10% of the volume?								
and space considerations?       Image: considerations?       Image: considerations?         Have check dams been placed at regular intervals within constructed channels that are cut down a slope?       Image: construction are protected.         7       Storm drain inlets made operable during construction are protected.       Image: construction are protected.         Are existing storm drains within the influence of the project protected?       Image: construction are protected?       Image: construction are protected?         8       Have all on-site conveyance channels       Image: constructed and figure to prevent erosion from from form form form form form for fuely, adjacent stream banks, slopes and downstream conveyance figure to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance figure to prevent erosion form form for fuely, adjacent stream banks, slopes and downstream conveyance figure to prevent erosion form figure to prevent contamination of stormwater?       Image: construction figure f		Is excavated material placed on uphill						
Have check dams been placed at regular intervals within constructed channels that are cut down a slope? <ul> <li>Annels that are cut down a slope?</li> <li>Storm drain inlets made operable</li> <li>during construction are protected.</li> <li>Are existing storm drains within the influence of the project protected?</li> <li>Have all on-site conveyance channels</li> <li>stabilized to prevent erosion from expected peak flows?</li> <li>Is stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?</li> <li>Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater?</li> <li>Has scoure been provided for all chemicals, liquid products, petroleum provided capable of containing 110% of the volume?</li> <li>Were contaminated surfaces cleaned immediately after a spill incident?</li> <li>Were BMPs used to prevent</li> <li>Were BMPs used to prevent</li> <li>Supes and prevent.</li> <li>Mere Surfaces cleaned immediately after a spill incident?</li> <li>Were BMPs used to prevent</li> <li>Surfaces cleaned</li> <li>Surface</li></ul>		side of trenches consistent with safety						
regular intervals within constructed channels that are cut down a slope?       Image: channels that are cut down a slope?         7       Storm drain inlets made operable       Image: channels that are cut down a slope?         0       during construction are protected.       Image: channels that are cut down a slope?         Are existing storm drains within the influence of the project protected?       Image: channels       Image: channels         8       Have all on-site conveyance channels       Image: channels       Image: channels         Stabilized to prevent erosion from       Image: channels       Image: channels       Image: channels         0utlets       expected peak flows?       Image: channels       Image: channels       Image: channels         0utlets       is stabilization, including armoring       Image: channels       Image: channels       Image: channels         9       Are waste materials and demolition       Image: channels       Image: channels       Image: channels         9       Are waste materials and demolition       Image: channels       Image: channels       Image: channels         9       Are waste materials and demolition       Image: channels       Image: channels       Image: channels         9       Are waste materials and demolition       Image: channels       Image: channels       Image: channels         9		and space considerations?						
channels that are cut down a slope?Image: slope and slope?Image: slope and slope?7Storm drain inlets made operable during construction are protected.Image: slope and slope?7Are existing storm drains within the influence of the project protected?Image: slope and slope?8Have all on-site conveyance channels stabilizeImage: slope and slope?8Have all on-site conveyance channels stabilized to prevent erosion from expected peak flows?Image: slope and slope?9Are waste materials and demolition of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: slope and slope?9Are waste materials and demolition controlImage: slope and downstream conveyance?Image: slope and slope?9Are waste materials and demolition chemicals, liquid products, petroleum products, and other material?Image: slope and slope and slope?9Are waste materials and demolition chemicals, liquid products, petroleum products, and other material?Image: slope and disposed of to prevent contamination of stormwater?Image: slope and disposed of to prevent contamination of stormwater?Image: slope and s		Have check dams been placed at						
7       Storm drain inlets made operable during construction are protected.         Are existing storm drains within the influence of the project protected?       Image: Construction are protected?         8       Have all on-site conveyance channels been designed, constructed and stabilized to prevent erosion from expected peak flows?       Image: Construction are protected?         9       Is stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?       Image: Construction are provided for all chemicals, liquid products, petroleum products, and other material?         9       Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater?       Image: Construct, and the material?         Has secondary containment been provided capable of containing 110% of the volume?       Image: Control Were BMPs used to prevent       Image: Control were BMPs used to prevent		regular intervals within constructed						
Drain Inlets       during construction are protected.		channels that are cut down a slope?						
Are existing storm drains within the influence of the project protected?       Image: Construct of the project protected?         8       Have all on-site conveyance channels been designed, constructed and stabilized to prevent erosion from expected peak flows?       Image: Construct of the project protect protect of the protect protect protect protect protect protect protect protect protect pro	-							
8Have all on-site conveyance channels been designed, constructed and stabilized to prevent erosion fromImage: constructed and stabilized to prevent erosion fromOutletsstabilized to prevent erosion from expected peak flows?Image: constructed and stabilized to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: constructed and stabilized to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: constructed and stabilized to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: constructed and stabilized to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: constructed and stabilized to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: constructed and stabilized to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?Image: constructed and erosion stabilized to prevent erosion of to ution of stormwater?9Are waste materials and demolition depris handled and disposed of to prevent contamination of stormwater?Image: constructed for all the score provided for all chemicals, liquid products, petroleum products, and other material?Image: constructed and the secondary containment been provided capable of containing 110% of the volume?Image: constructed and the secondary containment been provided capable of containing 110% of the volume?Image: constructed and the secondary containment been the volume?Were ontaminated surfaces cleaned immediately after a spill incident?Imag	Drain Inlets							
8       Have all on-site conveyance channels         Stabilize       been designed, constructed and         Channel and       stabilized to prevent erosion from         Outlets       Is stabilization, including armoring         material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance       systems?         9       Are waste materials and demolition         debris handled and disposed of to       prevent contamination of stormwater?         Has cover been provided for all       chemicals, liquid products, petroleum         products, and other material?       Has secondary containment been         provided capable of containing 110%       of the volume?         Were contaminated surfaces cleaned       immediately after a spill incident?		-						
Stabilize       been designed, constructed and       Image: Stabilized to prevent erosion from       Image: Stabilized to prevent erosion from         Outlets       expected peak flows?       Image: Stabilization, including armoring       Image: Stabilization, including armoring         Is stabilization, including armoring       material, adequate to prevent erosion       Image: Stabilization, including armoring       Image: Stabilization, including armoring         Is stabilization, including armoring       material, adequate to prevent erosion       Image: Stabilization, including armoring       Image: Stabilization, including armoring         Is stabilization, including armoring       material, adequate to prevent erosion       Image: Stabilization, including armoring       Image: Stabilization, including armoring         Is stabilization, including armoring       material, adequate to prevent erosion       Image: Stabilization, including armoring       Image: Stabilization, including armoring         Is stabilization, including armoring       Image: Stabilizatic, including armoring       Image: Sta		· · · ·						
Channel and       stabilized to prevent erosion from	-							
Outlets       expected peak flows?       Image: Constraint of the spectral spect		-						
Is stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems? 9 Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater? Has cover been provided for all chemicals, liquid products, petroleum products, and other material? Has secondary containment been provided capable of containing 110% of the volume? Were contaminated surfaces cleaned immediately after a spill incident? Were BMPs used to prevent		· · ·						
material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?       Image: Control debris handled and disposed of to prevent contamination of stormwater?         9       Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater?       Image: Control debris handled and disposed of to prevent contamination of stormwater?         Has cover been provided for all chemicals, liquid products, petroleum products, and other material?       Image: Control debris handled and the material?         Has secondary containment been provided capable of containing 110% of the volume?       Image: Control debris handled surfaces cleaned immediately after a spill incident?         Were BMPs used to prevent       Image: Control debris handled surfaces cleaned debris handlesurfaces cleaned debris handles handlesurfaces cleaned debris handl	Outlets							
of outlets, adjacent stream banks, slopes and downstream conveyance systems?       Image: Control systems and the conveyance of the conveyance o								
slopes and downstream conveyance       systems?         9       Are waste materials and demolition         debris handled and disposed of to       prevent contamination of stormwater?         Pollutants       prevent contamination of stormwater?         Has cover been provided for all       chemicals, liquid products, petroleum         products, and other material?       descent and the material?         Has secondary containment been       provided capable of containing 110%         of the volume?       were contaminated surfaces cleaned         Were BMPs used to prevent       were to prevent								
systems?       Image: Control debris handled and disposed of to debris handled and disposed of to prevent contamination of stormwater?       Image: Control debris handled and disposed of to debris handled and disposed of the volume products, petroleum products, and other material?       Image: Containing the debris handled and the debris handled been debris handled been debris handled been debris handled capable of containing 110% of the volume?       Image: Containing the debris handled been debri		-						
Control Pollutantsdebris handled and disposed of to prevent contamination of stormwater?Image: Contamination of stormwater?Has cover been provided for all chemicals, liquid products, petroleum products, and other material?Image: Contamination of stormwater?Has secondary containment been provided capable of containing 110% of the volume?Image: Contaminated surfaces cleaned immediately after a spill incident?Were BMPs used to preventImage: Contaminated surfaces cleaned immediately after a spill incident?Image: Contaminated surfaces cleaned immediately after a spill incident?								
Pollutants       prevent contamination of stormwater?       Image: Contamination of stormwater?       Image: Contamination of stormwater?         Has cover been provided for all chemicals, liquid products, petroleum products, and other material?       Image: Contamination of stormwater?       Image: Contamination of stormwater?       Image: Contamination of stormwater?         Has cover been provided for all chemicals, liquid products, petroleum products, and other material?       Image: Contamination of stormwater?       Image: Contaminater?       I	9	Are waste materials and demolition						
Has cover been provided for all chemicals, liquid products, petroleum products, and other material?Image: Constraint of the secondary containment been provided capable of containing 110% of the volume?Image: Constraint of the secondary contains the secondary containing 110% of the volume?Image: Constraint of the secondary containing 110% of the volume?Were contaminated surfaces cleaned immediately after a spill incident?Image: Constraint of the secondary contained surfaces cleaned the volume?Image: Constraint of the secondary contained surfaces cleaned the secondary containe	Control	debris handled and disposed of to						
chemicals, liquid products, petroleum	Pollutants	prevent contamination of stormwater?						
products, and other material?Image: Containable of containing 110%Image: Containable of containing 110%Provided capable of containing 110%Image: Containable of containing 110%Image: Containable of containab		· ·						
Has secondary containment been       provided capable of containing 110%          of the volume?          Were contaminated surfaces cleaned          immediately after a spill incident?          Were BMPs used to prevent								
provided capable of containing 110%								
of the volume?								
Were contaminated surfaces cleaned       Immediately after a spill incident?       Immediately after a spill incident?         Were BMPs used to prevent       Immediately after a spill incident?       Immediately after a spill incident?		_ ·						
immediately after a spill incident?								
Were BMPs used to prevent								
					$\left  \right $			
		-						
modifying sources?								

## **Construction Stormwater Site Inspection Form**

Element #	Inspection		BMPs Inspected		BMP needs maintenance	BMP	Action
			no	n/a	maintenance	failed	required (describe in section F)
9 Cont.	Wheel wash wastewater is handled and disposed of properly.						section ry
10 Control Dewatering	Concrete washout in designated areas. No washout or excess concrete on the ground.						
	Dewatering has been done to an approved source and in compliance with the SWPPP.						
	Were there any clean non turbid dewatering discharges?						
11 Maintain BMP	Are all temporary and permanent erosion and sediment control BMPs maintained to perform as intended?						
12 Manage the	Has the project been phased to the maximum degree practicable?						
Project	Has regular inspection, monitoring and maintenance been performed as required by the permit?						
	Has the SWPPP been updated, implemented and records maintained?						
13 Protect LID	Is all Bioretention and Rain Garden Facilities protected from sedimentation with appropriate BMPs?						
	Is the Bioretention and Rain Garden protected against over compaction of construction equipment and foot traffic to retain its infiltration capabilities?						
	Permeable pavements are clean and free of sediment and sediment laden- water runoff. Muddy construction equipment has not been on the base material or pavement.						
	Have soiled permeable pavements been cleaned of sediments and pass infiltration test as required by stormwater manual methodology?						
	Heavy equipment has been kept off existing soils under LID facilities to retain infiltration rate.						

#### E. Check all areas that have been inspected. 🖌

All in place BMPs All disturbed soils All concret	e wash out area 📃 All material storage areas 🗌
All discharge locations All equipment storage areas	All construction entrances/exits

F. Elements checked "Action Required" (section D) describe corrective action to be taken. List the element number; be specific on location and work needed. Document, initial, and date when the corrective action has been completed and inspected.

Element #	Description and Location	Action Required	Completion Date	Initials

Attach additional page if needed

#### Sign the following certification:

"I certify that this report is true, accurate, and complete, to the best of my knowledge and belief"

Inspected by: (print)		(Signature)	 Date:	
Title/Qualification of In	spector:	_		

# APPENDIX D Soil Report



United States Department of Agriculture

Natural Resources Conservation

Service

A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

## Custom Soil Resource Report for **Cowlitz County, Washington**



## Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/? cid=nrcs142p2\_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

## Contents

Preface	2
How Soil Surveys Are Made	
Soil Map	
Soil Map	
Legend	
Map Unit Legend	
Map Unit Descriptions	11
Cowlitz County, Washington	13
101—Kelso silt loam, 8 to 15 percent slopes	13
160—Pilchuck loamy fine sand, 0 to 8 percent slopes	14
References	15

## **How Soil Surveys Are Made**

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.


Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

## Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



	MAP L	EGEND	)	MAP INFORMATION
Area of Int	terest (AOI)	00	Spoil Area	The soil surveys that comprise your AOI were mapped at
	Area of Interest (AOI)	۵	Stony Spot	1:24,000.
Soils	Soil Map Unit Polygons	0	Very Stony Spot	Warning: Soil Map may not be valid at this scale.
~	Soil Map Unit Lines	\$	Wet Spot	Enlargement of maps beyond the scale of mapping can cause
	Soil Map Unit Points	$\triangle$	Other	misunderstanding of the detail of mapping and accuracy of soil
_	Point Features		Special Line Features	line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed
o	Blowout	Water Fea		scale.
	Borrow Pit	$\sim$	Streams and Canals	
*	Clay Spot	Transport	a <b>tion</b> Rails	Please rely on the bar scale on each map sheet for map measurements.
0	Closed Depression		Interstate Highways	
X	Gravel Pit	$\widetilde{}$	US Routes	Source of Map: Natural Resources Conservation Service Web Soil Survey URL:
0 0 0	Gravelly Spot	~	Major Roads	Coordinate System: Web Mercator (EPSG:3857)
Ø	Landfill	-	Local Roads	Maps from the Web Soil Survey are based on the Web Mercator
A.	Lava Flow	Backgrou	ind	projection, which preserves direction and shape but distorts
عليه	Marsh or swamp		Aerial Photography	distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more
~	Mine or Quarry			accurate calculations of distance or area are required.
0	Miscellaneous Water			This product is generated from the USDA-NRCS certified data as
0	Perennial Water			of the version date(s) listed below.
$\vee$	Rock Outcrop			Soil Survey Area: Cowlitz County, Washington
+	Saline Spot			Survey Area Data: Version 22, Aug 23, 2021
°.°	Sandy Spot			Soil map units are labeled (as space allows) for map scales
÷	Severely Eroded Spot			1:50,000 or larger.
0	Sinkhole			Date(s) aerial images were photographed: Apr 26, 2019—Jun
≽	Slide or Slip			11, 2019
ø	Sodic Spot			The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## **Map Unit Legend**

Map Unit Symbol Map Unit Name		Acres in AOI	Percent of AOI
101	Kelso silt loam, 8 to 15 percent slopes	1.2	92.9%
160	Pilchuck loamy fine sand, 0 to 8 percent slopes	0.1	7.1%
Totals for Area of Interest		1.3	100.0%

## **Map Unit Descriptions**

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however,

onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

### **Cowlitz County, Washington**

#### 101—Kelso silt loam, 8 to 15 percent slopes

#### **Map Unit Setting**

National map unit symbol: 2f13 Elevation: 50 to 200 feet Mean annual precipitation: 40 to 60 inches Mean annual air temperature: 50 to 52 degrees F Frost-free period: 165 to 180 days Farmland classification: Farmland of statewide importance

#### **Map Unit Composition**

*Kelso and similar soils:* 80 percent *Minor components:* 10 percent *Estimates are based on observations, descriptions, and transects of the mapunit.* 

#### **Description of Kelso**

#### Setting

Landform: Escarpments, terraces Parent material: Alluvium

#### **Typical profile**

*H1 - 0 to 11 inches:* silt loam *H2 - 11 to 34 inches:* silt loam *H3 - 34 to 60 inches:* silt loam

#### **Properties and qualities**

Slope: 8 to 15 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Moderately well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 24 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: High (about 11.3 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified Land capability classification (nonirrigated): 3e Hydrologic Soil Group: C Ecological site: F002XA004WA - Puget Lowlands Forest Forage suitability group: Soils with Moderate Limitations (G002XV602WA) Other vegetative classification: Soils with Moderate Limitations (G002XV602WA) Hydric soil rating: No

#### **Minor Components**

#### Hazeldell

*Percent of map unit:* 5 percent *Hydric soil rating:* No

#### Olympic

Percent of map unit: 5 percent

Hydric soil rating: No

#### 160—Pilchuck loamy fine sand, 0 to 8 percent slopes

#### **Map Unit Setting**

National map unit symbol: 2f45 Elevation: 10 to 50 feet Mean annual precipitation: 40 to 60 inches Mean annual air temperature: 50 to 54 degrees F Frost-free period: 165 to 195 days Farmland classification: Prime farmland if irrigated

#### Map Unit Composition

Pilchuck and similar soils: 85 percent Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Pilchuck**

#### Setting

Landform: Flood plains Parent material: Alluvium

#### **Typical profile**

H1 - 0 to 12 inches: loamy fine sand H2 - 12 to 36 inches: fine sand H3 - 36 to 60 inches: gravelly sand

#### **Properties and qualities**

Slope: 0 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Somewhat excessively drained
Capacity of the most limiting layer to transmit water (Ksat): High to very high (5.95 to 19.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: NoneRare
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 3.5 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified Land capability classification (nonirrigated): 4s Hydrologic Soil Group: A Ecological site: F002XA005WA - Puget Lowlands Moist Forest Forage suitability group: Droughty Soils (G002XV402WA) Other vegetative classification: Droughty Soils (G002XV402WA) Hydric soil rating: No

## References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/ nrcs/detail/national/soils/?cid=nrcs142p2\_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/ home/?cid=nrcs142p2 053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/ detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/ nrcs/detail/soils/scientists/?cid=nrcs142p2\_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/? cid=nrcs142p2\_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE\_DOCUMENTS/nrcs142p2\_052290.pdf